



**Intertek Testing Services**  
ETL SEMKO

8431 Murphy Drive  
Middleton, WI 53562

**ITS TEST REPORT No. J99031222-231  
TEST OF A WOOD BURNING STOVE  
FOR EMISSIONS & EFFICIENCY USING  
EPA METHOD 28 AND 5G-3  
MODEL: 3410 OWL  
FOR  
MORSO JERNSTOBERI A/S  
FURVEJ 6  
NYKOBING MORS 7900  
DENMARK**

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 1 of 18

TEST OF A WOOD BURNING STOVE  
FOR

EMISSIONS AND EFFICIENCY

PER

EPA METHODS 28 AND 5G-3  
FOR  
MORSO JERNSTOBERI  
NYKOBING MORS, DENMARK

TESTED BY:

INTERTEK TESTING SERVICES NA INC.  
8431 MURPHY DRIVE  
MIDDLETON, WISCONSIN 53562

TEST DATES: JULY 11-14,2000  
REPORT DATE: JULY 18, 2000

---

All services undertaken are subject to the following general policy: Reports are submitted for exclusive use of the clients to whom they are addressed. Their significance is subject to the adequacy and representative character of the samples and to the comprehensiveness of the tests, examinations, or surveys made. No quotations from reports or use of the Intertek Testing Services NA name, logo, or registered (WH) mark is permitted except as expressly authorized by Intertek Testing Services NA Inc. in writing.

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 2 of 18

## I. INTRODUCTION

A.	General.....	4
B.	Test Unit Description.....	4
C.	Results.....	4
D.	Pretest Information.....	5
E.	Report Organization.....	5

## II. SUMMARY OF TEST RESULTS

A.	Emissions.....	6
B.	Weighted Average Calculation.....	6
C.	Test Facility Conditions.....	7
D.	Fuel Qualities.....	7
E.	Dilution Tunnel Flow Rate Measurement and Sampling Data (5G-3).....	8
F.	Dilution Tunnel Dual Train Precision.....	8
G.	General Summary of Results.....	9

## III. PROCESS DESCRIPTION

A.	Discussion.....	9
B.	Unit Dimensions.....	10
C.	Air Supply System.....	10
D.	Operation during Test.....	10
E.	Start-Up Operation.....	11

## IV. SAMPLING SYSTEMS

A.	Sampling Locations.....	11
	1. Dilution Tunnel (Figure 1).....	12
B.	Operational Drawings	
	1. Stack Gas Sample Train (Figure 2).....	13
	2. Dilution Tunnel Sample Systems (Figure 3).....	14
C.	Equipment List.....	15

## V. SAMPLING METHODS

A.	Particulate.....	16
B.	Efficiency.....	16

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 3 of 18

## VI. QUALITY ASSURANCE

A.	Instrument Calibration	
	1. Dry Gas Meters .....	16
	2. Stack Sample rotometer .....	16
	3. Gas Analyzers .....	17
B.	Test Method Procedures	
	1. Leak Check Procedures .....	18
	2. Tunnel Velocity / Flow Measurement .....	18
	3. PM Sampling System Proportionality (5G-3) .....	18

## VII. PHOTOGRAPHS

## VIII. APPENDICES

Data and Calculation Forms .....	A
Laboratory Operating Procedure .....	B
Sampling Proportionality Results .....	C
Dry Gas Meter Calibration Data .....	D
Other Calibration Data .....	E
Drawings and Specifications .....	F
Operators Manual .....	G
Calculation Procedures and Sample Calculations .....	H
Efficiency and Heat Output Results .....	I
Unit Pre-Burn Documentation .....	J

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 4 of 18

## I. INTRODUCTION

### I.A. GENERAL

From July 11 through 14, 2000 Intertek Testing Services NA Inc. (ITS) conducted tests on Morso's model 3410 (Owl) wood burning stove to determine compliance with U.S. EPA emissions regulations.

Rick Armstrong and Ayn Chappelle-Steinlein conducted tests. Present, as an observer for tests was Derik Andors of Ferguson, Andors and Co. representing Morso. The tests were conducted at the Intertek Testing Services NA Inc. laboratory located at 8431 Murphy Drive, Middleton, Wisconsin. The laboratory elevation is 860 feet above sea level. Tests were conducted to EPA Method 28 and 5G-3 criteria.

### I.B. TEST UNIT DESCRIPTION

Morso's model 3410 (Owl) wood burning stove is rectangular in shape sitting on four legs. The Unit is constructed from cast iron with a glass and cast iron door that was hinged on the left. The single door gives access to both the firebox for fuel loading and to the ash pan. The bottom of the firebox is a grate. The sides of the stove are embossed with three owls. The sole control is a lever located below the ash-lip. Combustion by-products exit through a six-inch flue collar located centrally at the rear of the top. (See photograph pages)

### I.C. RESULTS

The unit as tested produced a weighted average emissions rate of 3.469 grams/hour and did not exceed any of the emissions rate caps specified in the EPA regulations. The unit thus meets EPA certification requirements for 1990.

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 5 of 18

## I.D. PRETEST INFORMATION

The test unit was received at Intertek Testing Services NA Inc. in Middleton, Wisconsin on July 6, 2000 via Emery. The unit was inspected upon receipt and found to be in good condition. The unit was set up following the manufacturer's instructions without difficulty. Following assembly, the unit was placed on the test stand and instrumented with thermocouples in the specified locations. Prior to beginning the emissions tests the unit was operated for a minimum of 10 hours at high-to-medium burn rates. The unit was found to be operating satisfactory during this break-in. The 14 plus hours of pre-burning was conducted on July 7, 2000. The fuel used for the break-in process is all Red Oak cordwood with Douglas Fir scrap as kindling. The moisture content of the cordwood was 16-20% on the wet basis.

Following the pre-burn break-in process, the unit was allowed to cool. The chimney system and laboratory dilution tunnel was cleaned using standard wire brush chimney cleaning equipment.

On July 10, 2000, the unit was ready for testing.

## I.E. REPORT ORGANIZATION

This report includes summaries of all data necessary to determine compliance with the regulations. Raw data, calibration records, intermediate calculations, drawings and specifications and other supporting information are contained in appendices to this report.

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 6 of 18

## II. SUMMARY OF TEST RESULTS

### II.A. EMISSIONS

Run Number	Test Date	Burn Rate (kg/hr)	Emission Rate (g/hr)	Adjusted Emission Rate (g/hr)	Heating Efficiency** (% Overall)
1	7/11/00	.0700	5.648	7.658	59.07
2	7/12/00	1.698	1.360	2.347	65.53
3	7/1200	1.958	1.087	1.951	74.84
4	7/12/00	0.818	2.210	3.514	64.91

\*\*Calculated as specified in CSA B-415

### II.B. WEIGHTED AVERAGE CALCULATION

Run Number	Burn Rate	(E)			(K)				
		Adjusted Emission Rate g/hr	Output (OHE)*(BTU/HR)	Prob	Weighting Factor	(KxE)	(KxOHE)		
1	0.700	7.658	59.07	8440.74	.1500	.2322	1.7785	13.72	
4	0.818	3.510	64.91	9863.61	.2322	.6894	2.4198	44.75	
2	1.698	2.347	65.53	20474.82	.8394	.6747	1.5836	44.21	
3	1.958	1.951	74.84	23609.96	.9070	.1606	.3133	.1202	
Sums:						1.75696	6.0952	114.70	

Weighted Average Emissions Rate:  $6.0952 \div 1.75696 = 3.4692$

Weighted Average Overall Heating Efficiency:  $114.70 \div 1.75696 = 65.28\%$

\*Calculated as specified in CSA B-415

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 7 of 18

## II.C. TEST FACILITY CONDITIONS

Run Number	Room Temperature (F)		Barometric Pressure (in. Hg)		Relative Humidity (%)		Air Velocity (ft/min)	
	Before	After	Before	After	Before	After	Before	After
1	82	83	29.15	29.12	74	64	0	0
2	85	84	29.12	29.12	57	45	0	0
3	89	89	29.12	29.12	45	38	0	0
4	83	85	29.15	29.12	63	50	0	0

## II.D. FUEL QUALITIES

Run Number	Pre-Test Load			Test Load					
	Loading Weight (lb.)	Moisture Content Dry Basis (%)	Coal Bed Weight (lb.)	Weight Wet Basis (lb.)	Density Wet Basis (lbs/ft <sup>3</sup> )	Moisture Content Dry Basis (%)	Piece Length (in.)	Number of 2x4's 4x4's	
1	10.69	20.65	1.6	6.72	6.733	21.53	14.00	3	0
2	9.34	21.59	1.6	6.66	6.633	21.59	14.00	3	0
3	8.57	19.49	1.5	6.50	6.533	20.45	14.00	3	0
4	10.47	21.40	1.6	6.46	6.492	20.97	14.00	3	0



# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 8 of 18

## E. DILUTION TUNNEL FLOW RATE MEASUREMENTS AND SAMPLING DATA (5G-3)

Average Dilution Tunnel Measurements					Sample Data			
Run Number	Burn Time (min)	Velocity (ft/sec)	Volumetric Flow Rate (dscf/min)	Total Temp. (°R)	Sample Volume (dscf)		Particulate Catch (mg)	
					1	2	1	2
1	215	13.63	143.11	553.48	49.58	49.24	32.8	32.2
2	87	13.75	140.03	570.50	20.03	20.14	3.60	2.90
3	75	14.10	141.10	580.22	17.19	17.07	2.30	2.10
4	177	13.67	141.43	561.53	40.83	40.59	10.2	11.0

## I.F. DILUTION TUNNEL DUAL TRAIN PRECISION

Run Number	Sample Ratios		Total Emissions (grams)		% Deviation
	Train 1	Train 2	Train 1	Train 2	
1	620.60	624.86	20.36	20.12	0.97
2	608.15	604.8	2.19	1.75	5.74
3	615.78	619.88	1.42	1.30	7.00
4	613.05	616.70	6.25	6.78	6.76

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 9 of 18

## I.G. GENERAL SUMMARY OF RESULTS

Run Number	Burn Rate (kg/hr)	Average Temperature (F) Combustion	In Surface Temperature (F) Surface	Change In Surface Temperature (F)	Initial Draft (in. H <sub>2</sub> O)	Primary Air Setting	Run Time (min)	Average Draft (in. H <sub>2</sub> O)
1	0.700	463.87	320.72	-54.8	0.050	full closed	215	.042
2	1.698	735.5	448.32	-37.40	0.076	hole #2	87	.076
3	1.958	804.78	498.64	-48.80	0.075	full open	75	.085
4	0.818	548.11	364.16	-104.8	0.057	hole #1	177	.050

## III. PROCESS DESCRIPTION

### III.A. DISCUSSION

RUN #1 (July 11,2000) the primary air was set at full closed. The test was loaded in 25 seconds. The door was open for 4 minutes and the primary air was open for 5 minutes. Burn time was 215 minutes making the burn rate 0.700 kg/hour, a category 1-burn rate.

RUN #2 (July 12,2000) the air control was set at hole #2. The test was loaded in 20 seconds. The door was open for 1 minute. The air control was set to the second hole at 5:00. Burn time was 87 minutes for category a 3-burn rate of 1.698 kg/hr.

RUN #3 (July 12, 2000) the air control was set to full open. The test was loaded in 20 seconds. The door was open for 55 seconds. Burn time was 75 minutes for a category 4-burn rate of 1.958 kg/hr.

RUN #4 (July 13, 2000) the primary air control was set hole #1. The test was loaded in 30 seconds. The air control was set to the first hole at 5 min. The door was closed at 4 minutes. Burn time was 117 minutes for a category 2-burn rate of 0.818 kg/hr.

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 10 of 18

## III.B. UNIT DIMENSIONS

27-1/8" high, 19" wide and 19" deep.

## III.C. AIR SUPPLY SYSTEM

Controlled primary combustion air enters the unit at the lower rear of the unit where it is channeled above the door where it empties into the firebox as air wash. Secondary air enters the unit at the lower rear also but is uncontrolled. Secondary air is channeled to the baffle that has outlet holes in it. Additional secondary air is channeled under the grate and enters the firebox at the lower front center and is directed at the coal bed. Combustion products then exit the unit through a six-inch flue collar located centrally at the rear of the stovetop.

## III.D. OPERATION DURING TEST

The stove and laboratory equipment worked with no problems during the tests.

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 11 of 18

## III.E. START-UP OPERATION

Each test was started with a clean firebox and the scale zeroed. A fire was started using newspaper and Douglas Fir scraps for kindling. For all tests the fire was started with two to three pounds of kindling. When the kindling was burning well a small amount of the pre-test fuel was loaded. After this was burning well additional pre-test fuel was added until the required one hour. Pretest loads were fired on high until burning well. Stirring was done as required to insure uniform charcoalization. At least one hour prior to loading the air controls was set to the approximate position used during the test. Stirring was limited to less than 1 minute during the last 15 minutes of the pre-test.

## IV. SAMPLING SYSTEMS

### IV.A. SAMPLING LOCATIONS

Particulate samples are collected from the dilution tunnel at a point 20 feet from the tunnel entrance. The tunnel has two elbows and two mixing baffles in the system ahead of the sampling section. (See Figure 3.) The sampling section is a continuous 13 foot section of 6 inch diameter pipe straight over its entire length. Tunnel velocity pressure is determined by a standard Pitot tube located 60 inches from the beginning of the sampling section. The dry bulb thermocouple is located six inches downstream from the Pitot tube. Tunnel samplers are located 60 inches downstream of the Pitot tube and 36 inches upstream from the end of this section. (See Figure 1.)

Stack gas samples are collected from the steel chimney section 8 feet  $\pm$  6 inches above the scale platform. (See Figure 2.)

## IV.A.(1) DILUTION TUNNEL




FIGURE 1

## IV.B. OPERATIONAL DRAWINGS

### IV.B.(1) STACK GAS SAMPLE TRAIN





FIGURE 2

## IV.B.(2). DILUTION TUNNEL SAMPLE SYSTEMS



**Figure 3**

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 15 of 18

## IV.B. EMISSION AND EFFICIENCY EQUIPMENT LIST

<u>ITEM DESCRIPTION</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>SERIAL #</u>
1. CO2 Analyzer (WHI#010)	HORIBA	PIR-2000	607023
2. CO Analyzer (WHI #009)	HORIBA	PIR-2000	6110019
3. O2 Analyzer (WHI #011)	BECKMAN	755	1001926
4. Dry Gas Meter (WHI #012)	Rockwell	T-110	26866
5. Dry Gas Meter (WHI #013)	Rockwell	T-110	26873
6. Rotometer (WHI # 015)	Matheson	602 Tube	
7. Rotometer (3) (WHI # 016)	Matheson	603 Tube	
8. Rotometer (2) (WHI # 019)	Matheson	604 Tube	
9. Hot Wire Anemometer (WHI #021)	Alnor	8525	MD 1057
10. Inclined Manometer (WHI #022)	Dwyer	125-AV	
11. Pitot Tube (WHI # 044)			
12. Manometer 0-10" (WHI #024)	Dwyer	400-10	
13. Mercury Barometer (WHI # 142)	Meriam	310EC10WM	184550-X1
14. Draft Indicator (WHI #027)	Dwyer	2000-00	R60825 M29
15. Scale, 1000# Cap./Record.(WHI #025)	Toledo Masstron	ML222	8013
16. Readout for 1000# Scale (WHI #007)	NCI	5780	C800174
17. Scale, 75# Capacity (WHI #006)	NCI	3824-100	762117
18. Readout for 75# Scale (WHI #008)	NCI	5780	G800082
19. Analytical Balance (WHI #028)	OHAUS	G-110	5336
20. Dial-o-gram Balance 2610 g (WHI # 031)	OHAUS	1650	
21. Audit Weights 1 mg-100 g/Class-S (WHI # 029)	Ainsworth	4254-S	39392
22. Diaphragm Pumps (4) (WHI # 032 - 035)	Dayton	ZO24 (1) 2Z866 (3)	
23. Method 5H Glassware (WHI # 036)	Andersen	4" Filter, 4-250 ml Impingers	
24. Gases; Calibration, Zero, Span	Matheson		
25. Regulators for Gases (6) (WHI # 037 - 043)	Matheson	8-(XXXX)	
26. High Accuracy Needle Valves (9)	Matheson		
27. Solenoid Valves (12) (WHI # 045)	Dayton		
28. Switches (Misc.) (WHI # 045)	Dayton		
29. ORSAT Gas Analyzer (WHI # 048)	Fisher	D	
30. Oxygen Bomb Calorimeter (WHI # 047)	Parr	1341	4514
31. Moisture Meter (WHI #049)	Delmhorst	RC-1C	14356
32. Humidity Chamber (WHI # 050)	Lab Built		
33. Dilution Tunnel (WHI # 046)	Lab Built		
34. Spirometer (WHI # 51)	Lab Built		
35. Data Acquisition System (WHI # 052)	Lab Built		
36. Drying Oven (WHI # 002)	Blue-M	SW-11TA-1	SW-291
37. Filter Holders, 47-mm (8) (WHI # 053)	Nalgene		
38. Type-K Meter (WHI #054)	Omega	199	21662
39. Digital Voltmeter (WHI # 055)	Newport	2004-3	6090022-3
40. Type K Thermocouple Wire 24 Ga.	Gordon	Special Limits of Error	
41. Type K T/C Plugs	Gordon	K-901/900	
42. Dry Gas Meter (WHI #014)	Rockwell	T-110	27002
43. Audit Weights; 5#, 10# (WHI # 160)	Rice Lake Weighing System		Class-F
44. Sling Psychrometer (WHI # 126)	Taylor		
45. Chart Recorder (WHI # 056)	Cole-Palmer	2030-0000	221063
46. Infrared Pyrometer (WHI #102)	Omega	OS-2000A	A4048T
47. Class C Weights 1-500 g (WHI # 161)	Ohaus		
48. Bomb Calorimeter Thermometer (WHI # 162).	Parr	1603	3K9347
49. Microtector Gauge (WHI # 103)	Dwyer	1430	
50. Bubble flow meter (WHI # 415)	Humonics	650	570192
51. Soxhlet extractor (WHI # 413)	Fisher Scientific		
52. ESS Unit (WHI # 416)	Omni		
53. Unimantle (WHI # 413)			
54. Magnehelic (WHI #027)			

Prepared January 1988 by Rick Curkeet / Rev. May1997 by Rick Armstrong



# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 16 of 18

## V. SAMPLING METHODS

### V.A. PARTICULATE SAMPLING

Particulates were sampled in strict accordance with EPA Method 5G-3. This method uses two identical sampling systems with Gelman A/E 61631 binder free, 47-mm diameter filters. The dryers used in the sample systems are filled with "Drierite" before each test run.

### V.B. EFFICIENCY

Efficiencies reported were based on Method CSA-B415 (calculation). Stack gas analysis for oxygen, carbon dioxide and carbon monoxide was performed in accordance with EPA Method 5H.

## VI. QUALITY ASSURANCE

### VI.A. INSTRUMENT CALIBRATION

#### VI.A.(1). DRY GAS METERS

At the conclusion of each test program the dry gas meters are checked against our standard dry gas meter. Three runs are made on each dry gas meter used during the test program. The average calibration factors obtained are then compared with the six-month calibration factor and, if within 5%, the six-month factor is used to calculate standard volumes. Results of this calibration are contained in Appendix D.

An integral part of the post test calibration procedure is a leak check of the pressure side by plugging the system exhaust and pressurizing the system to 10" W.C. The system is judged to be leak free if it retains the pressure for at least 10 minutes.

The standard dry gas meter is calibrated every 6 months using a Spirometer designed by the EPA Emissions Measurement Branch. The process involves sampling the train operation for 1 cubic foot of volume. With readings made to .001 ft<sup>3</sup>, the resolution is .1%, giving an accuracy higher than the ±2% required by the standard.

#### VI.A.(2). STACK SAMPLE ROTAMETER

The stack sample rotometer is checked by running three tests at each flow rate used during the test program. The flow rate is checked by running the rotometer in series with one of the dry gas meters for 10 minutes with the rotometer at a constant setting. The dry gas meter volume measured is then corrected to standard temperature and pressure conditions. The flow rate determined is then used to calculate actual sampled volumes.

## VI.A.(3). GAS ANALYZERS

The continuous analyzers are zeroed and spanned before each test with appropriate gases. A mid-scale multi-component calibration gas is then analyzed (values are recorded). At the conclusion of a test, the instruments are checked again with zero, span and calibration gases (values are recorded only). The drift in each meter is then calculated and must not exceed 5% of the scale used for the test.

At the conclusion of each unit test program, a five-point calibration check is made. This calibration check must meet accuracy requirements of the applicable standards. Consistent deviations between analyzer readings and calibration gas concentrations are used to correct data before computer processing. Data is also corrected for interferences as prescribed by the instrument manufacturers instructions. Calibration gases are checked by ORSAT analysis when received to verify suppliers analysis.

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: Owl

Page 18 of 18

## VI.B. TEST METHOD PROCEDURES

### VI.B.(1). LEAK CHECK PROCEDURES

Before and after each test, each sample train is tested for leaks. Leakage rates are measured and must not exceed 0.02 CFM or 4% of the sampling rate. Leak checks are performed checking the entire sampling train, not just the dry gas meters. Pre-test and post-test leak checks are conducted with a vacuum of 10 inches of mercury. Vacuum is monitored during each test and the highest vacuum reached is then used for the post test vacuum value. If leakage limits are not met, the test run is rejected. During, these tests the vacuum was typically less than 2 inches of mercury. Thus, leakage rates reported are expected to be much higher than actual leakage during the tests.

### VI.B.(2). TUNNEL VELOCITY/FLOW MEASUREMENT


The tunnel velocity is calculated from a center point pitot tube signal multiplied by an adjustment factor. This factor is determined by a traverse of the tunnel as prescribed in EPA Method 1. Final tunnel velocities and flow rates are calculated from EPA Method 2, Equation 6.9 and 6.10. (Tunnel cross sectional area is the average from both lines of traverse.)

Pitot tubes are cleaned before each test and leak checks are conducted after each test.


### VI.B.(3). PM SAMPLING PROPORTIONALITY (5G-3)

Proportionality was calculated in accordance with EPA Method 5G-3. The data and results are included in Appendix C.

All tests were conducted, analyzed, and reported on by:

  
Rick Armstrong, Engineering Technician

Reviewed By:

  
Edwin Hodgson, Project Manager



  
William Keen, Engineering Technician

# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: 3410 (Owl)

Photograph pg. 1 of 5





# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: 3410 (Owl)

Photograph pg. 2 of 5




# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: 3410 (Owl)

Photograph pg. 3 of 5





# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: 3410 (Owl)

Photograph pg. 4 of 5




# Intertek Testing Services

Report Date: July 18, 2000  
Client: Morso Jernstoberi

Report #: J99031222-231  
Model: 3410 (Owl)

Photograph pg. 5 of 5





# APPENDIX A

Intertek Testing Services

SFBA EPA ADJUSTED EMISSION RESULTS

Manufacturer:

Morso

RESULTS

Model:

Owl

Date:

07/11/00

AVERAGE ADJUSTED EMISSION R

7.657

Run:

1

Project #:

31222

Burn Rate (Dry kg/hr):

0.700

Test Duration:

215

(minutes)

PRESSURE FACTOR:

0.97426

BAROMETRIC PRESSURE

Average: 29.15

TEMPERATURE FACTORS

Start: 29.15

DGM #1:

0.97171

End: 29.15

DGM #2:

0.97183

DRY GAS METER VALUES

VOLUMES SAMPLED

DGM #1

Final: 942.465

DGM #1:

49.60437

Initial: 890.868

DGM #2:

49.26674

DGM #2

Final: 319.193

TOTAL TUNNEL VOLUME (scf):

30776.659

Initial: 267.710

SAMPLE RATIOS

TEMPERATURES (DEG. RANKIN)

Sample Train 1:

620.442

DGM #1: 543.370

Sample Train 2:

624.694

DGM #2: 543.304

TOTAL EMISSIONS

CALIBRATION FACTORS

Sample Train 1 (g):

20.3505

DGM #1: 1.0155

Sample Train 2 (g):

20.1152

DGM #2: 1.0107

EMISSION RATES

TUNNEL FLOW RATE:

143.147

Sample Train 1 (g/hr):

5.6792

Sample Train 2 (g/hr):

5.6135

PARTICULATE CATCH (mg)

ADJUSTED EMISSION RATES

Sample Train 1:

32.8

Sample Train 1 (g/hr):

7.6936

Sample Train 2:

32.2

Sample Train 2 (g/hr):

7.6197

DEVIATION:

0.97%

**Intertek Testing Services**

**SFBA EPA ADJUSTED EMISSION RESULTS**

<b>Manufacturer:</b>	Morso	<b>RESULTS</b>	
<b>Model:</b>	Owl		
<b>Date:</b>	07/12/00	<b>AVERAGE ADJUSTED EMISSION RATE</b>	2.347
<b>Run:</b>	2		
<b>Project #:</b>	31222	<b>Burn Rate (Dry kg/hr):</b>	1.698
<b>Test Duration (minutes):</b>	87		

<b>PRESSURE FACTOR:</b>	0.97326	<b>BAROMETRIC PRESSURE</b>	
		<b>Average:</b>	29.12
<b>TEMPERATURE FACTORS</b>		<b>Start:</b>	29.12
<b>DGM #1:</b>	0.97480	<b>End:</b>	29.12
<b>DGM #2:</b>	0.97841		

<b>VOLUMES SAMPLED</b>		<b>DRY GAS METER VALUES</b>	
<b>DGM #1:</b>	20.03185	<b>DGM #1</b>	<b>Final:</b> 963.286
<b>DGM #2:</b>	20.14291		<b>Initial:</b> 942.494
<b>TOTAL TUNNEL VOLUME (scf):</b>	12182.364	<b>DGM #2</b>	<b>Final:</b> 340.133
			<b>Initial:</b> 319.204

<b>SAMPLE RATIOS</b>		<b>TEMPERATURES (DEG. RANKIN)</b>	
<b>Sample Train 1:</b>	608.150	<b>DGM #1:</b>	541.650
<b>Sample Train 2:</b>	604.797	<b>DGM #2:</b>	539.650

<b>TOTAL EMISSIONS</b>		<b>CALIBRATION FACTORS</b>	
<b>Sample Train 1 (g):</b>	2.1893	<b>DGM #1:</b>	1.0155
<b>Sample Train 2 (g):</b>	1.7539	<b>DGM #2:</b>	1.0107

<b>EMISSION RATES</b>		<b>TUNNEL FLOW RATE:</b>	140.027
<b>Sample Train 1 (g/hr):</b>	1.5099		
<b>Sample Train 2 (g/hr):</b>	1.2096	<b>PARTICULATE CATCH (mg)</b>	

<b>ADJUSTED EMISSION RATES</b>		<b>Sample Train 1:</b>	3.6
<b>Sample Train 1 (g/hr):</b>	2.5621	<b>Sample Train 2:</b>	2.9
<b>Sample Train 2 (g/hr):</b>	2.1314		

**DEVIATION:** 18.35%

If deviation is greater than 7.5% due to low particulate catch  
 The two emission rates shall not differ by 7.5%  
 of the weighted average emission rate limit (4.1 or 7.5) (5g-3)

Use the following:

<b>Catalytic units</b>	10.51%
7.5% of 4.1 g/hr	
<b>Non catalytic units</b>	5.74%
7.5% of 7.5 g/hr	

Intertek Testing Services

SFBA EPA ADJUSTED EMISSION RESULTS

Manufacturer:	Morso	RESULTS	
Model:	Owl		
Date:	07/12/00	AVERAGE ADJUSTED EMISSION R/	1.951
Run:	3		
Project #:	31222	Burn Rate (Dry kg/hr):	1.958
Test Duration: (minutes)	75		

PRESSURE FACTOR:	0.97326	BAROMETRIC PRESSURE	Average:	29.12
------------------	---------	---------------------	----------	-------

TEMPERATURE FACTORS		Start:	29.12
DGM #1:	0.97029	End:	29.12
DGM #2:	0.97367		

VOLUMES SAMPLED		DRY GAS METER VALUES	
DGM #1:	17.18597	DGM #1	Final: 981.236
DGM #2:	17.07237		Initial: 963.315
TOTAL TUNNEL VOLUME (scf):	10582.814	DGM #2	Final: 357.966
			Initial: 340.141

SAMPLE RATIOS		TEMPERATURES (DEG. RANKIN)	
Sample Train 1:	615.782	DGM #1:	544.167
Sample Train 2:	619.880	DGM #2:	542.278

TOTAL EMISSIONS		CALIBRATION FACTORS	
Sample Train 1 (g):	1.4163	DGM #1:	1.0155
Sample Train 2 (g):	1.3017	DGM #2:	1.0107

EMISSION RATES		TUNNEL FLOW RATE:	141.104
Sample Train 1 (g/hr):	1.1330	PARTICULATE CATCH (mg)	
Sample Train 2 (g/hr):	1.0414	Sample Train 1:	2.3

ADJUSTED EMISSION RATES		Sample Train 2:	2.1
Sample Train 1 (g/hr):	2.0188		
Sample Train 2 (g/hr):	1.8823		

DEVIATION:	7.00%
------------	-------

Intertek Testing Services			
SFBA EPA ADJUSTED EMISSION RESULTS			
Manufacturer:	Morso	RESULTS	
Model:	Owl		
Date:	07/13/00	AVERAGE ADJUSTED EMISSION R	3.514
Run:	4		
Project #:	31222	Burn Rate (Dry kg/hr):	0.818
Test Duration: (minutes)	177		
PRESSURE FACTOR:		0.97376	BAROMETRIC PRESSURE
TEMPERATURE FACTORS			Average: 29.135
	DGM #1:	0.97129	Start: 29.15
	DGM #2:	0.97479	End: 29.12
DRY GAS METER VALUES			
VOLUMES SAMPLED		DGM #1	Final: 1023.779
	DGM #1:	40.83437	Initial: 981.264
	DGM #2:	40.59271	
TOTAL TUNNEL VOLUME (scf):		25033.674	DGM #2
			Final: 400.294
			Initial: 357.982
SAMPLE RATIOS		TEMPERATURES (DEG. RANKIN)	
	Sample Train 1:	613.054	DGM #1: 543.605
	Sample Train 2:	616.704	DGM #2: 541.658
TOTAL EMISSIONS		CALIBRATION FACTORS	
	Sample Train 1 (g):	6.2532	DGM #1: 1.0155
	Sample Train 2 (g):	6.7837	DGM #2: 1.0107
EMISSION RATES		TUNNEL FLOW RATE:	
	Sample Train 1 (g/hr):	2.1197	141.433
	Sample Train 2 (g/hr):	2.2996	PARTICULATE CATCH (mg)
ADJUSTED EMISSION RATES		Sample Train 1:	10.2
	Sample Train 1 (g/hr):	3.3953	Sample Train 2:
	Sample Train 2 (g/hr):	3.6328	11
DEVIATION:		6.76%	

Manufacturer MORSO Model OWL Date 7/7/00  
 Job # 31222 Run \_\_\_\_\_ Tech RA/ACS

### EMISSIONS TESTING UNIT PREPARATION

Unit description (check all that apply)

- |   |   |                         |
|---|---|-------------------------|
| <input checked="" type="checkbox"/> Stove         | <input checked="" type="checkbox"/> Top Vent  | _____ Manual Draft      |
| <input type="checkbox"/> Insert                   | <input checked="" type="checkbox"/> Rear Vent | _____ Bimetal Spring    |
| _____ Catalytic                                   | <input checked="" type="checkbox"/> Grate     | _____ Remote Thermostat |
| <input checked="" type="checkbox"/> Non-catalytic | <input checked="" type="checkbox"/> Ashpan    | _____ Blower or Fans    |
| <input type="checkbox"/> Other: _____             |   |                         |

Unit received with all parts:  Yes \_\_\_\_\_ No  
 Manual: \_\_\_\_\_ Yes \_\_\_\_\_ No  
 Drawings: \_\_\_\_\_ Yes \_\_\_\_\_ No  
 Specifications: \_\_\_\_\_ Yes \_\_\_\_\_ No

Materials of construction: \_\_\_\_\_  
 \_\_\_\_\_

Air introduction: \_\_\_\_\_  
 Control mechanism: \_\_\_\_\_

Unit net weight with all components: 216 lbs. 97.9 Kg.  
 Unit fire box volume: 995 Ft<sup>3</sup> (attach fire box volume calculations and drawings)  
 Ideal Load Weight: 6.97 lbs. (Volume x 7)  
 Load Weight Range: (±10% of ideal weight) 6.27 lbs. to 7.66 lbs.  
 Ideal piece length specification: \_\_\_\_\_ inches. (5/6 of longest fire box dimension)  
 Thermocouples attached: 5 Attached by: RA (attach T/C map)

#### Unit conditioned prior to test

10 hours at medium burn rate (non-catalytic) (attach burn log)      \_\_\_\_\_ 50 hours at medium burn rate (attach burn log)

Date started: 7-7-00 Date completed: 7-7-00

Catalyst manufacturer: \_\_\_\_\_  
 Serial number: \_\_\_\_\_ Dimensions: \_\_\_\_\_ Cell size: \_\_\_\_\_ cells/in.<sup>2</sup>

Unit ready for testing (date): \_\_\_\_\_ Initialed: \_\_\_\_\_




Manufacturer MORSO Model OWL Date \_\_\_\_\_

Job # 31222 Run \_\_\_\_\_ Tech RA/ACS

Measurements By: RA

Checked By: \_\_\_\_\_

**FIRE BOX VOLUME CALCULATION**



$$\text{Volume} = A+B+C+D+E-F$$

$$A = 7.375 \times 12.5 \times 15.375 = 1417.38$$

$$B = 9.375 \times 1 \times 15.375 = 144.14$$

$$C = 6.375 \times 1 \times 15.375 = 98.01$$

$$D = 3.5 \times 1 \times 15.375 = 53.81$$

$$E = 3 \left( \frac{.5 \times 3 \times 15.375}{2} \right) = 34.59$$

$$F = 1 \times 1.875 \times 15.375 = 28.83$$

Volume = 1719.1 cubic inches  
or .995 cubic feet



Manufacturer MORSO Model OWL Date 7/7/00 Page 4 of 48  
Job # 31222 Run \_\_\_\_\_ Tech RA/ACS

**Thermocouple Location**

Thermocouples are placed centrally on the top, back, right and left sides and the bottom and numbered as shown below.

TC#	LOCATION
5	UNIT TOP
6	UNIT BACK
7	UNIT RIGHT
8	UNIT LEFT
9	UNIT BOTTOM

Manufacturer MORSO Model OWL Date 7/11/08

Job # 31722 Run 1 Tech RA/ACS

**PRETEST DILUTION TUNNEL TRAVERSE RUN**

Barometric pressure ( $P_{bar}$ ) 29.15 (inches Hg.) Static pressure ( $P_s$ ) .107 (inches w.c.)

Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area:  $0.1963Ft^2$

Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head $\Delta_p$ (inches H <sub>2</sub> O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$
A-Centroid	3.00	.040	104	.2000
B-Centroid	3.00	.039	101	.1975
A-1	0.40	.037	103	.1924
A-2	1.50	.041	103	.2025
A-3	4.50	.040	103	.2000
A-4	5.60	.036	103	.1897
B-1	0.40	.036	102	.1897
B-2	1.50	.039	101	.1975
B-3	4.50	.040	101	.2000
B-4	5.60	.034	101	.1844
AVERAGE			102.2	.1954

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}}$$

$$V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction .9830

Where,

$C_p$  = Pitot tube coefficient = 0.99 for standard pitot

$\Delta_p$  = manometer reading (inches H<sub>2</sub>O)

$T_s$  = average absolute dilution tunnel temperature (°F + 460)

$P_s$  = absolute dilution tunnel gas pressure or  $P_{bar} + P_g$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

$P_g$  = static pressure inches H<sub>2</sub>O

13.6

$M_s$  = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)

$K_p$  = 85.49 Pitot tube constant, (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

$(\sqrt{\Delta_p})_{avg}$  = Average of the square roots of the velocity heads ( $\Delta_p$ ) measured at each traverse point.

$(\sqrt{\Delta_p})_{centroid}$  = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H<sub>2</sub>O)

Manufacturer MORSO Model OWL Date 7/11/00

Job # 31222 Run 1 Tech RA/ACS

**Pre/Post Checks**

Moisture Meter Calibration Check:

Time: <u>0800</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

**Facility Conditions:**

Air Velocity.....  
Smoke Capture Check.....

Pre-Test	Post-Test
Ø fpm	Ø ✓ fpm
✓	✓

**Wood Heater Conditions:**

Date Wood Heater Stack Cleaned.....  
Date Dilution Tunnel Cleaned.....  
Induced Draft Check.....  
Tunnel Velocity.....  
Flow Rate 140-cfm ±10%.....

7/10/00	
7/10/00	
Ø	Ø
.039	
	143.147

**Pitot Leak Check:**

Side A.....  
Side B.....

✓	✓
✓	✓

**Temperature System:**

Ambient (65°- 90°F).....  
Wood Heater Surface (±125°F).....

-54.8	°F
143.147	°F

**Proportional Checks:**

CO Analyzer Drift Check.....  
CO<sub>2</sub> Analyzer Check.....  
O<sub>2</sub> Analyzer Check.....  
Thermocouple check.....

✓	
✓	
✓	
✓	

**Sampling Train ID Numbers:**

Probe.....  
Filter Front.....  
Filter Back.....  
Filter Thermocouple.....  
Filter 5G-3 (<90°F).....

Train 1	Train 2
3	4
5	7
6	8
19	22
✓	✓

**Thermocouple Identification Number**

Flue .....1  
Dilution Tunnel Wet Bulb .....4  
Unit Right Side .....7  
Catalyst/Combustion Chamber .....10

Room .....2  
Unit Top .....5  
Unit Left Side .....8

Dilution Tunnel Dry Bulb .....3  
Unit Back .....6  
Unit Bottom .....9

Manufacturer MORSO Model OWL Date 7/11/00

Job # 31227 Run 1 Tech RA/ACS

## Pre-Test Scale Audit

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>100</u> mg.

### LIMITS OF WEIGHT RANGES

*ANALYTICAL SCALE*: ..... 50%-150% of dry filter weight, ± 0.1 mg  
*PLATFORM SCALE*: ..... 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%  
*WOOD SCALE*: ..... 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%

Manufacturer MORSO Model GWL Date 7/11/00

Job # 31222 Run 1 Tech RA/ACS

## SAMPLING EQUIPMENT CHECK OUT

### Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft <sup>3</sup> )	890.858	942.471	267.710	319,200
Initial 1minute DGM (ft <sup>3</sup> )	890.858	890.471	267.710	319,200
Change (C) (ft <sup>3</sup> )	0	0	0	0
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

### Leakage Checks Flue Gas Sampler

Plugged Probe	Pre Test	Post Test
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer Moroso Model CML Date 7/11/00  
 Job # 31222 Run 1 Tech RA/ACS

## CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
	Actual	Should Be	Actual	Should Be	Actual	Should Be
CO	0	0	9.99	9.99	2.35	2.36
CO <sub>2</sub>	0	0	24.65	24.65	5.79	5.88
O <sub>2</sub>	0	0	20.93	20.93	5.66	5.55
	Actual	Should Be	Actual	Should Be	Actual	Should Be

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	.02	10.02	2.37	.02	.03	.02	✓	
CO <sub>2</sub>	.02	24.74	5.79	.02	.09	0	✓	
O <sub>2</sub>	.11	20.89	5.71	.11	.04	.05	✓	

\* Greater than ± 5% of the range used.

Manufacturer MORSO Model OWL Date 7-11-00  
 Job # 31222 Run 1 Tech RA ACS

### DILUTION TUNNEL PARTICULATE SAMPLER DATA

FILTER TYPE: Gelman 47mm A/E

Samples in Desecrator. Date: 7-11-00 Time: 15:32

	SYSTEM 1		SYSTEM 2	
	Probe and Front Half Housing # <u>3</u>	Filter Numbers <u>5+6</u>	Probe and Front Half Housing # <u>4</u>	Filter Numbers <u>7+8</u>
Post Test Weight:	<u>93.1213</u> grams	<u>.2667</u> grams	<u>89.9736</u> grams	<u>.2596</u> grams
Pre Test Weight:	<u>93.1213</u> grams	<u>.2339</u> grams	<u>89.9736</u> grams	<u>.2274</u> Grams
Gain:	<u>0</u> grams	<u>.0328</u> grams	<u>0</u> grams	<u>.0322</u> Grams
	a1	b1	a2	b2

Total Gain: a1 + b1 = .0328 grams      a2 + b2 = .0322 grams

		SYSTEM 1			SYSTEM 2			TEMP °F	HUMID %
Pre-test Weight Record	Probe & Housing Number	Front Filter Number	Back Filter Number	Probe & Housing Number	Front Filter Number	Back Filter Number			
Date	Time	<u>3</u>	<u>5</u>	<u>6</u>	<u>4</u>	<u>7</u>	<u>8</u>		
<u>7-10-00</u>	<u>7:15</u>	<u>93.1210</u>	<u>.1166</u>	<u>.1181</u>	<u>89.9732</u>	<u>.1146</u>	<u>.1124</u>	<u>78</u>	<u>48</u>
<u>7-11-00</u>	<u>7:15</u>	<u>93.1213</u>	<u>.1163</u>	<u>.1176</u>	<u>89.9736</u>	<u>.1148</u>	<u>.1126</u>	<u>73</u>	<u>46</u>
		Total			Total				
		<u>.2339</u>			<u>.2274</u>				

		SYSTEM 1		SYSTEM 2		TEMP °F	HUMID %
Pre-test Weight Record	Probe & Housing Number	Combined Filter Weight Number	Probe & Housing Number	Combined Filter Weight Number			
Date	Time	<u>3</u>	<u>5+6</u>	<u>4</u>	<u>7+8</u>		
<u>7-11-00</u>	<u>15:32</u>	<u>93.1216</u>	<u>.2694</u>	<u>89.9740</u>	<u>.2606</u>	<u>80</u>	<u>45</u>
<u>7-12-00</u>	<u>7:00</u>	<u>93.1214</u>	<u>.2668</u>	<u>89.9737</u>	<u>.2602</u>	<u>74</u>	<u>48</u>
<u>7-13-00</u>	<u>7:05</u>	<u>93.1213</u>	<u>.2467</u>	<u>89.9736</u>	<u>.2596</u>	<u>73</u>	<u>49</u>
<u>7-14-00</u>	<u>7:20</u>	<u>93.1213</u>	<u>.2667</u>	<u>89.9736</u>	<u>.2596</u>	<u>78</u>	<u>50</u>

Manufacturer NORSO Model OWL Date 7/11/00  
 Job # 31222 Run 1 Tech RA/ACS

## TEST DATA LOG

### RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft <sup>3</sup> )	942.465	379.193
Initial (ft <sup>3</sup> )	890.868	267.710

### AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.15	29.12
Wet Bulb (°F)	70	70
Dry Bulb (°F)	74	79
Humidity (%)	74	64







Manufacturer Moroso Model OW Date 7-1-00

Job # 31222 Run 1 Tech RA ACS

AIR CONTROL FULL CLOSED

SWITCH NUMBER				1	2	3	4	5	6	7	8	9	10			
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0	10:17	0	3.20	439	83	114	82	631	256	419	401	344	824	0.40	0.74	C
1		10	3.60	335	82	103	82	597	290	431	414	368	679	0.40	0.64	C
2		20	3.2	286	84	99	82	526	287	410	399	371	595	0.40	0.65	C
3		30	2.9	289	82	100	82	470	289	386	380	371	548	0.40	0.62	C
4		40	2.7	240	82	96	82	423	290	372	371	373	500	0.40	0.55	L
5		50	2.4	223	83	95	83	388	290	359	361	370	467	0.40	0.55	L
6		60	1.9	222	83	92	83	362	287	347	350	369	465	0.40	0.525	Tails
7		70	1.7	205	82	94	84	349	285	327	338	368	429	0.40	0.50	C
8		80	1.7	195	83	87	84	334	271	326	328	361	417	0.40	0.45	C
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments:  
11:43 FIRE STIRRED DOOR OPEN 45 SEC

1046 - FIRE STIRRED  
1113 - FIRE STIRRED



Manufacturer NORSO Model OML Date 7/12/00

Job # 31222 Run 2 Tech RA/ACS

### PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure ( $P_{bar}$ ) 29.12 (inches Hg.) Static pressure ( $P_g$ ) 115 (inches w.c.)

Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area:  $0.1963\text{Ft}^2$

Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head $\Delta_p$ (inches H <sub>2</sub> O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$
A-Centroid	3.00	.040	116	.2000
B-Centroid	3.00	.040	114	.2000
A-1	0.40	.038	111	.1949
A-2	1.50	.040	110	.2000
A-3	4.50	.040	110	.2000
A-4	5.60	.037	111	.1924
B-1	0.40	.038	114	.1949
B-2	1.50	.040	114	.2000
B-3	4.50	.040	114	.2000
B-4	5.60	.036	113	.1897
AVERAGE			112.7	.1972

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}} \quad V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction .9860

Where,

$C_p$  = Pitot tube coefficient = 0.99 for standard pitot

$\Delta_p$  = manometer reading (inches H<sub>2</sub>O)

$T_s$  = average absolute dilution tunnel temperature (°F + 460)

$P_s$  = absolute dilution tunnel gas pressure or  $P_{bar} + P_g$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

$P_g$  = static pressure inches H<sub>2</sub>O

13.6

$M_s$  = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)

$K_p$  = 85.49 Pitot tube constant, (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

$(\sqrt{\Delta_p})_{avg}$  = Average of the square roots of the velocity heads ( $\Delta_p$ ) measured at each traverse point.

$(\sqrt{\Delta_p})_{centroid}$  = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H<sub>2</sub>O)

Manufacturer MORSO Model DWC Date 7-12-00  
 Job # 31222 Run 2 Tech RA ACS

**Pre/Post Checks**

Moisture Meter Calibration Check:

Time: <u>7:45</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

**Facility Conditions:**

Air Velocity.....  
 Smoke Capture Check.....

Pre-Test	Post-Test
0 fpm	0 fpm
0 ✓	0 ✓

**Wood Heater Conditions:**

Date Wood Heater Stack Cleaned.....  
 Date Dilution Tunnel Cleaned.....  
 Induced Draft Check.....  
 Tunnel Velocity.....  
 Flow Rate 140-cfm ±10%.....

7-10-00	
7-10-00	
0	0
040	
	140.027

**Pitot Leak Check:**

Side A.....  
 Side B.....

✓	✓
✓	✓

**Temperature System:**

Ambient (65°- 90°F).....  
 Wood Heater Surface (±125°F).....

✓	°F
-37.4	°F

**Proportional Checks:**

CO Analyzer Drift Check.....  
 CO<sub>2</sub> Analyzer Check.....  
 O<sub>2</sub> Analyzer Check.....  
 Thermocouple check.....

✓	
✓	
✓	
✓	

**Sampling Train ID Numbers:**

Probe.....  
 Filter Front.....  
 Filter Back.....  
 Filter Thermocouple.....  
 Filter 5G-3 (<90°F).....

Train 1	Train 2
5	6
9	11
10	12
19	22
✓	✓

**Thermocouple Identification Number**

Flue .....1  
 Dilution Tunnel Wet Bulb .....4  
 Unit Right Side .....7  
 Catalyst/Combustion Chamber .....10

Room .....2  
 Unit Top .....5  
 Unit Left Side .....8

Dilution Tunnel Dry Bulb .....3  
 Unit Back .....6  
 Unit Bottom .....9

Manufacturer MORSO Model Owl Date 7-12-50  
 Job # 31222 Run 2 Tech RA ACS

## SAMPLING EQUIPMENT CHECK OUT

### Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft <sup>3</sup> )	942.494	963.296	319.204	340.140
Initial 1minute DGM (ft <sup>3</sup> )	942.494	963.296	319.204	340.140
Change (C) (ft <sup>3</sup> )	0	0	0	0
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

### Leakage Checks Flue Gas Sampler

	Pre Test	Post Test
Plugged Probe		
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MORSO Model OWL Date 7-12-00

Job # 31222 Run 2 Tech RA ACS

## Pre-Test Scale Audit

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <span style="margin-left: 20px;"><u>100</u> mg, Class S</span>	100 Grams <span style="margin-left: 20px;"><u>100</u> mg.</span>

### LIMITS OF WEIGHT RANGES

**ANALYTICAL SCALE:** ..... 50%-150% of dry filter weight, ± 0.1 mg

**PLATFORM SCALE** ..... 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%

**WOOD SCALE** ..... 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%



Manufacturer MORSO Model OWL Date 7/12/00  
 Job # 31222 Run 2 Tech RA/ACS

## CONTINUOUS ANALYZERS

### Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
	Actual	Should Be	Actual	Should Be	Actual	Should Be
CO	∅	∅	9.99	9.99	2.34	2.36
CO <sub>2</sub>	∅	∅	24.65	24.65	5.75	5.88
O <sub>2</sub>	∅	∅	20.93	20.93	5.65	5.55

### Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	.01	10.05	2.38	.01	.05	.04	✓	
CO <sub>2</sub>	.01	24.40	5.88	.01	.25	.13	✓	
O <sub>2</sub>	.02	20.83	5.72	.02	.10	.07	✓	

\* Greater than ± 5% of the range used.

Manufacturer MORSO Model OWL Date 7/12/00  
 Job # 31222 Run 2 Tech RA/ACS

### DILUTION TUNNEL PARTICULATE SAMPLER DATA

FILTER TYPE: Gelman 47mm AF  
 Samples in Desecrator. Date: 7/12/00 Time: 1145

	SYSTEM 1		SYSTEM 2	
	Probe and Front Half Housing # <u>5</u>	Filter Numbers <u>9+10</u>	Probe and Front Half Housing # <u>6</u>	Filter Numbers <u>11+12</u>
Post Test Weight:	<u>91.0642</u> grams	<u>.2380</u> grams	<u>91.5728</u> grams	<u>.2310</u> grams
Pre Test Weight:	<u>91.0642</u> grams	<u>.2344</u> grams	<u>91.5728</u> grams	<u>.2281</u> Grams
Gain:	<u>.0</u> grams	<u>.0036</u> grams	<u>.0</u> grams	<u>.0029</u> Grams
	a1	b1	a2	b2

Total Gain: a1 + b1 = .0036 grams    a2 + b2 = .0029 grams

Pre-test Weight Record		SYSTEM 1			SYSTEM 2			TEMP °F	HUMID %
		Probe & Housing Number	Front Filter Number	Back Filter Number	Probe & Housing Number	Front Filter Number	Back Filter Number		
Date	Time	<u>5</u>	<u>9</u>	<u>10</u>	<u>6</u>	<u>11</u>	<u>12</u>		
<u>7-11-00</u>	<u>7:25</u>	<u>91.0641</u>	<u>.1166</u>	<u>.1177</u>	<u>91.5732</u>	<u>.1144</u>	<u>.1143</u>	<u>73</u>	<u>46</u>
<u>7-12-00</u>	<u>7:05</u>	<u>91.0642</u>	<u>.1166</u>	<u>.1178</u>	<u>91.5728</u>	<u>.1139</u>	<u>.1142</u>	<u>74</u>	<u>48</u>
Total		<u>.2344</u>			Total			<u>.2281</u>	

Pre-test Weight Record		SYSTEM 1		SYSTEM 2		TEMP °F	HUMID %
		Probe & Housing Number	Combined Filter Weight Number	Probe & Housing Number	Combined Filter Weight Number		
Date	Time	<u>5</u>	<u>9+10</u>	<u>6</u>	<u>11+12</u>		
<u>7-12-00</u>	<u>11:45</u>	<u>91.0644</u>	<u>.2384</u>	<u>91.5728</u>	<u>.2315</u>	<u>80</u>	<u>45</u>
<u>7-13-00</u>	<u>7:05</u>	<u>91.0643</u>	<u>.2382</u>	<u>91.5728</u>	<u>.2313</u>	<u>73</u>	<u>49</u>
<u>7-14-00</u>	<u>7:20</u>	<u>91.0642</u>	<u>.2380</u>	<u>91.5728</u>	<u>.2310</u>	<u>78</u>	<u>50</u>
<u>7-17-00</u>	<u>7:30</u>	<u>91.0642</u>	<u>.2380</u>	<u>91.5728</u>	<u>.2310</u>	<u>74</u>	<u>50</u>

Manufacturer MOESO Model OWL Date 7/12/00  
 Job # 31222 Run 2 Tech RA/ACS

## TEST DATA LOG

### RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft <sup>3</sup> )	963.286	340.133
Initial (ft <sup>3</sup> )	942.494	319.204

### AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.12	29.12
Wet Bulb (°F)	67	67
Dry Bulb (°F)	75	82
Humidity (%)	57	45





Manufacturer MORSO

Model OWL

Date 7/12/00

Job # 31227 Run 2 Tech RA/ACS

HOLE #2 (AIR CONTROL)

SWITCH NUMBER			1	2	3	4	5	6	7	8	9	10				
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0	9:15	0	4.80	462	82	118	80	574	186	352	306	293	772	.045	.075	T
1		10	3.8	445	82	117	81	562	217	404	358	329	794	.045	.075	C
2		20	2.9	434	84	117	82	576	248	427	393	360	765	.045	.082	C
3		30	2.3	403	85	115	82	549	273	438	417	405	703	.045	.082	C
4		40	1.8	375	84	112	85	506	291	406	420	445	646	.045	.082	C
5		50	2.2	398	90	104	85	521	303	436	422	463	700	.115	.080	C
6		60	1.7	369	86	111	84	505	309	433	421	487	644	.040	.075	C
7		70														
8		80														
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments: 10.1 P st. read fire, door open 1 min

SEE MAIN COMMENTS

READING#	REAL TIME	ELAPSED TIME	WEIGHT REMAIN.	CO	CO <sub>2</sub>	O <sub>2</sub>	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CAT IN/OUT	CAT CENTER	GAS SMPL ROTO.	DGM #1 READING	DGM #2 READING	ROTO 2 READING	DGM TEMP INLET	DGM TEMP OUTLET	FILTER TEMP	TUNNEL VELOCITY	DRAFT	SMOKE	MAX DGM PRESS
0	1019	0	6.6	52	5.76	14.3	362	85	111	84	443	310	419	436	490	568		135	042.49	319.2	120	76	76	76	040	026	2	
1		10	300	27	15.42	4.37	518	90	128	85	429	309	421	440	499	962		135	944.8	321.5	120	78	77	89	039	082	2	
2		20	350	07	14.80	5.84	516	89	122	79	720	321	432	418	457	735		135	947.1	323.9	120	79	77	89	039	083	2	
3		30	330	05	14.71	5.60	508	88	120	78	726	340	455	435	433	970		135	949.5	326.3	120	79	78	90	038	083	2	
4		40	1.20	03	12.82	19.4	418	89	117	78	754	366	418	459	432	902		135	951.9	328.7	120	80	79	87	040	080	2	
5		50	1.60	29	7.08	13.0	392	88	101	78	610	383	481	471	442	738		135	0524.3	331.1	120	81	79	85	040	080	2	
6		60	1.40	68	6.28	14.03	365	88	103	77	524	382	465	458	451	610		135	054.0	333.5	120	81	80	85	040	075	2	
7		70	30	188	5.01	15.30	336	86	101	76	473	372	446	439	453	587		135	959.0	325.9	120	82	81	83	040	072	2	
8		80	01	173	4.21	15.82	307	86	98	76	432	335	406	415	427	503		135	961.5	338.4	120	82	83	85	040	070	2	
9		87.99	0	143	4.18	15.82	235	84	98	74	403	322	411	400	425	530		135	963.2	340.1	120	83	82	84	040	056	2	
10		100																										
11		110																										
12		120																										
13		130																										
14		140																										
15		150																										
16		160																										
17		170																										
18		180																										
19		190																										
20		200																										
21		210																										
22		220																										
23		230																										
24		240																										
25		250																										
26		260																										
27		270																										
28		280																										
29		290																										
30		300																										
31		310																										
32		320																										
33		330																										
34		340																										
35		350																										
36		360																										
37		370																										
38		380																										
39		390																										
40		400																										
41		410																										
42		420																										
43		430																										
44		440																										
45		450																										
46		460																										
47		470																										
48		480																										

Handwritten notes: "1608/11" and "11/16/00" with a signature.

door open 1 minute, controls fell open for

COMMENTS:  
TEST LOADED IN 20 SECONDS

Manufacturer MORSO Model OWL Date 7/12/00

Job # 31227 Run 3 Tech RA/ACS

### PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure ( $P_{bar}$ ) 29.12 (inches Hg.) Static pressure ( $P_q$ ) 1.25 (inches w.c.)

Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area:  $0.1963\text{Ft}^2$

Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head $\Delta_p$ (inches H <sub>2</sub> O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$
A-Centroid	3.00	.040	116	
B-Centroid	3.00	.040	120	
A-1	0.40	.036	118	
A-2	1.50	.040	117	
A-3	4.50	.040	116	
A-4	5.60	.036	118	
B-1	0.40	.035	118	
B-2	1.50	.040	119	
B-3	4.50	.041	119	
B-4	5.60	.035	117	
AVERAGE				

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}} \quad V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction .9781

Where,

$C_p$  = Pitot tube coefficient = 0.99 for standard pitot

$\Delta_p$  = manometer reading (inches H<sub>2</sub>O)

$T_s$  = average absolute dilution tunnel temperature (°F + 460)

$P_s$  = absolute dilution tunnel gas pressure or  $P_{bar} + P_g$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

$P_g$  = static pressure inches H<sub>2</sub>O

$M_s$  = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)

$K_p$  = 85.49 Pitot tube constant, (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

- $(\sqrt{\Delta_p})_{avg}$  = Average of the square roots of the velocity heads ( $\Delta_p$ ) measured at each traverse point.
- $(\sqrt{\Delta_p})_{centroid}$  = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H<sub>2</sub>O)



Manufacturer HORSO Model OML Date 7/12/00  
 Job # 31222 Run 3 Tech RA/ACS

**Pre/Post Checks**

Moisture Meter Calibration Check:

Time: <u>7:45</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

**Facility Conditions:**

Air Velocity.....  
 Smoke Capture Check.....

Pre-Test	Post-Test
0 fpm	0 fpm
✓	✓

**Wood Heater Conditions:**

Date Wood Heater Stack Cleaned.....  
 Date Dilution Tunnel Cleaned.....  
 Induced Draft Check.....  
 Tunnel Velocity.....  
 Flow Rate 140-cfm ±10%.....

7-10-00	
7-10-00	
0	0
540	
	141.164

**Pitot Leak Check:**

Side A.....  
 Side B.....

✓	
✓	

**Temperature System:**

Ambient (65°- 90°F).....  
 Wood Heater Surface (±125°F).....

	✓ °F
	°F

**Proportional Checks:**

CO Analyzer Drift Check.....  
 CO<sub>2</sub> Analyzer Check.....  
 O<sub>2</sub> Analyzer Check.....  
 Thermocouple check.....

	✓
	✓
	✓
	✓

**Sampling Train ID Numbers:**

Probe.....  
 Filter Front.....  
 Filter Back.....  
 Filter Thermocouple.....  
 Filter 5G-3 (<90°F).....

Train 1	Train 2
7	8
13	15
14	16
19	22
✓	✓

**Thermocouple Identification Number**

Flue .....1  
 Dilution Tunnel Wet Bulb .....4  
 Unit Right Side .....7  
 Catalyst/Combustion Chamber .....10

Room.....2  
 Unit Top .....5  
 Unit Left Side .....8

Dilution Tunnel Dry Bulb.....3  
 Unit Back.....6  
 Unit Bottom.....9

Manufacturer MORSO Model OWL Date 7/12/00 Page 2948  
 Job # 31222 Run 3 Tech RA/OCS

**Pre-Test Scale Audit**

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>10</u> <u>or</u> mg.

**LIMITS OF WEIGHT RANGES**

*ANALYTICAL SCALE* .....50%-150% of dry filter weight, ± 0.1 mg  
*PLATFORM SCALE* .....20%-80% of ideal test load weight, ± 0.1 lbs. or 1%  
*WOOD SCALE* .....20%-80% of ideal test load weight, ± 0.1 lbs. or 1%

Manufacturer Moroso Model OWL Date 7/12/00  
 Job # 31222 Run 3 Tech RA/ACS

## SAMPLING EQUIPMENT CHECK OUT

### Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft <sup>3</sup> )	963.315	981.250	340.141	357.979
Initial 1minute DGM (ft <sup>3</sup> )	963.315	981.250	340.141	357.978
Change (C) (ft <sup>3</sup> )	0	0	0	.001
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

### Leakage Checks Flue Gas Sampler

Plugged Probe	Pre Test	Post Test
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MORSO Model OWL Date 7/12/00  
 Job # 31222 Run 3 Tech RA/ACS

## CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
CO	0	0	9.99	9.99	2.35	2.36
CO <sub>2</sub>	0	0	24.65	24.65	5.79	5.88
O <sub>2</sub>	0	0	20.93	20.93	5.66	5.55
	Actual	Should Be	Actual	Should Be	Actual	Should Be

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
CO	0	10.00	2.34	0	.01	.01	✓	
CO <sub>2</sub>	.01	24.62	5.78	.01	.03	.01	✓	
O <sub>2</sub>	.02	20.80	5.73	.02	.13	.07	✓	

\* Greater than ± 5% of the range used.

Manufacturer MORSO Model OWL Date \_\_\_\_\_

Job # 31222 Run 3 Tech RA/ACS

### DILUTION TUNNEL PARTICULATE SAMPLER DATA

FILTER TYPE: Gelman 47mm A/E  
 Samples in Desecrator. Date: 7/12/00 Time: 1540

	SYSTEM 1		SYSTEM 2	
	Probe and Front Half Housing # <u>7</u>	Filter Numbers <u>13 + 14</u>	Probe and Front Half Housing # <u>8</u>	Filter Numbers <u>15 + 16</u>
Post Test Weight:	<u>90.9534</u> grams	<u>.2346</u> grams	<u>92.1912</u> grams	<u>.2292</u> grams
Pre Test Weight:	<u>90.9534</u> grams	<u>.2323</u> grams	<u>92.1911</u> grams	<u>.2272</u> Grams
Gain:	<u>.0</u> grams	<u>.0023</u> grams	<u>.0001</u> grams	<u>.0020</u> Grams
	a1	b1	a2	b2

Total Gain: a1 + b1 = .0023 grams    a2 + b2 = .0021 grams

		SYSTEM 1			SYSTEM 2			TEMP °F	HUMID %
Pre-test Weight Record	Probe & Housing Number	Front Filter Number	Back Filter Number	Probe & Housing Number	Front Filter Number	Back Filter Number			
Date	Time	<u>7</u>	<u>13</u>	<u>14</u>	<u>8</u>	<u>15</u>	<u>16</u>		
<u>7-12-00</u>	<u>7:05</u>	<u>90.9534</u>	<u>.1160</u>	<u>.1164</u>	<u>92.1911</u>	<u>.1140</u>	<u>.1134</u>	<u>74</u>	<u>48</u>
<u>7-12-00</u>	<u>11:50</u>	<u>90.9534</u>	<u>.1162</u>	<u>.1161</u>	<u>92.1911</u>	<u>.1137</u>	<u>.1135</u>	<u>80</u>	<u>45</u>
Total		<u>.2323</u>			Total			<u>.2272</u>	

		SYSTEM 1		SYSTEM 2		TEMP °F	HUMID %
Pre-test Weight Record	Probe & Housing Number	Combined Filter Weight Number		Probe & Housing Number	Combined Filter Weight Number		
Date	Time	<u>7</u>	<u>13 + 14</u>		<u>8</u>	<u>15 + 16</u>	
<u>7-12-00</u>	<u>13:40</u>	<u>90.9535</u>	<u>.2349</u>		<u>92.1914</u>	<u>.2292</u>	
<u>7-13-00</u>	<u>7:05</u>	<u>90.9534</u>	<u>.2346</u>		<u>92.1912</u>	<u>.2292</u>	
<u>7-14-00</u>	<u>7:20</u>	<u>90.9534</u>	<u>.2346</u>		<u>92.1912</u>	<u>.2292</u>	
<u>7-17-00</u>	<u>7:30</u>	<u>90.9534</u>	<u>.2346</u>		<u>92.1912</u>	<u>.2292</u>	

Manufacturer MOROO Model OWL Date 7/12/00  
 Job # 31222 Run 3 Tech RA/ACS

**TEST DATA LOG**

**RAW DRY GAS METER READINGS**

	System 1	System 2
Final (ft <sup>3</sup> )	981.236	357.966
Initial (ft <sup>3</sup> )	963.315	340.141

**AMBIENT CONDITIONS**

	Start	End
Barometer. (inches Hg)	29.12	29.12
Wet Bulb (°F)	67	69
Dry Bulb (°F)	82	88
Humidity (%)	45	38

Manufacturer MORSO Model AWL Date 7/12/00

Job # 31222 Run 3 Tech RA/ACS

## FUEL DATA

### PRE-TEST LOAD

**FUEL DESCRIPTION:**

Kindling weight: 2.5 lbs. Consisting of: Scrap and paper Fire lit Time: 12:45  
 Pre-test load weight: \_\_\_\_\_ lbs. Consisting of: 2X4X inches Time loaded: \_\_\_\_\_  
 Pre-test moisture content: Uncorrected: 18.26 % Corrected Dry: 19.49 % Wet: 16.31 %

Test Air Control Settings: FULL OPEN Time: 12:45  
 Test Unit Fan Settings: \_\_\_\_\_ Time: \_\_\_\_\_

### TEST LOAD

	Lower Limit	Ideal	Upper Limit
Test Load Weight:	<u>6.27</u> Lbs.	<u>6.97</u> lbs.	<u>7.66</u> Lbs.
Fire Box Volume:	<u>.995</u> Ft. <sup>3</sup>	Ideal Length:	_____ Inches
Load Volume:	<u>.1667</u> Ft. <sup>3</sup>	Loading Density:	<u>6.533</u> lbs/ft <sup>3</sup>
Number of Spacers	<u>12</u> 3/4x1 1/2x5	Load Density:	<u>39.000</u> lbs/ft <sup>3</sup>

Piece Size	Weight	Meter Moisture Content (% dry)*		
<u>2 x 4 x 14</u> in.	<u>1.97</u> lbs.	<u>19.0</u> %	<u>18.0</u> %	<u>19.5</u> %
<u>2 x 4 x 14</u> in.	<u>1.96</u> lbs.	<u>20.0</u> %	<u>18.5</u> %	<u>18.9</u> %
<u>2 x 4 x 14</u> in.	<u>2.57</u> lbs.	<u>19.0</u> %	<u>19.0</u> %	<u>20.6</u> %
x x in.	_____ lbs.	_____ %	_____ %	_____ %
x x in.	_____ lbs.	_____ %	_____ %	_____ %
x x in.	_____ lbs.	_____ %	_____ %	_____ %
x x in.	_____ lbs.	_____ %	_____ %	_____ %

\*Uncorrected range = 17.9% to 23.1%

TEST LOAD WEIGHT: 6.50 lbs. DRY WEIGHT: 2.45 kg.  
 AVERAGE MOISTURE CONTENT:  
 (DRY) 19.17 % CORRECTED TO TWO PIN: (DRY) 20.45 % (WET) 17.00 %  
 COAL BED RANGE: 1.3 lbs. to 1.6 lbs. (20% to 25% of test load)  
 TEST CHARGE:  
 Time loaded: 14:12 Coal bed weight: 1.5 lbs. Coal bed weight = \_\_\_\_\_ % of test load weight

CHARCOALIZATION: good | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | poor





Manufacturer MORSO Model OWL Date 7/12/00  
 Job # 31222 Run 3 Tech RA/ACS

SWITCH NUMBER		1	2	3	4	5	6	7	8	9	10						
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE	
0	12:57	0	3.80	433	82	123	76	333	226	239	250	219	655	.875	.037	C	
1		10	2.40	460	82	118	76	413	220	294	271	230	743	.875	.040	C	
2		20	7.50	399	84	108	76	461	240	355	309	279	691	.875	.040	L	
3		30	6.40	496	84	121	76	536	338	382	316	313	792	.875	.040	L	
4		40	4.90	522	86	126	76	630	294	414	345	338	870	.875	.040	T	
5		50	3.60	527	86	127	77	661	271	441	395	371	886	.875	.045	C	
6		60	2.70	190	88	123	77	636	302	455	431	423	831	.875	.040	C	
7		70	2.10	465	88	120	77	608	337	454	455	467	790	.080	.040	C	
8		80															
9		90															
10		100															
11		110															
12		120															
13		130															
14		140															
15		150															
16		160															
17		170															
18		180															
19		190															
20		200															
21		210															
22		220															
23		230															
24		240															
25		250															

Comments:  
FIRE STOPPED 1411 for 10 seconds

WHI LTO#: 31222 AIR CONTROL FULL OPEN MODEL: 04C  
 MANUFACTURER: MERSO SWITCH NUMBER: H16H DATE: 7-17-88 RUN#: 3 TECHNICIAN: RA-025

READING	REAL TIME	ELAPSED TIME	WEIGHT REMAIN.	CO	CO <sub>2</sub>	O <sub>2</sub>	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RT. SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CAT EXIT	CAT CENTER	GAS SMPLE ROTO.	DGM #1 READING	DGM #2 READING	ROTO 1 READING	ROTO 2 READING	DGM TEMP INLET	DGM TEMP OUTLET	DGM TEMP	FILTER TEMP	TUNNEL VELOCITY	DRAFT	SMOKE	MAX DGM PRESS	
0	1412	0	1.50	176	5.26	13.26	428	89	111	78	563	562	450	463	521	690		135	963.3	120	82	82	80	80	80	80	80	80	80	80	
1		10	1.70	08	15.34	11.96	507	89	131	78	623	367	452	456	521	1035		135	965.1	120	82	82	80	80	80	80	80	80	80	80	
2		20	1.20	03	13.88	6.60	568	89	134	80	768	379	481	455	499	1035		135	968.0	120	83	83	81	81	81	81	81	81	81	81	81
3		30	1.10	0A	12.85	7.35	544	89	130	80	749	205	500	470	494	1035		135	970.4	120	83	83	81	81	81	81	81	81	81	81	81
4		40	1.10	10	9.18	10.60	481	89	124	80	679	424	511	486	510	1035		135	972.8	120	84	84	83	83	83	83	83	83	83	83	83
5		50	1.01	24	6.88	11.94	423	89	117	80	575	458	504	489	522	723		135	975.2	120	85	85	84	84	84	84	84	84	84	84	84
6		60	1.00	04	6.47	13.76	394	89	113	80	508	413	488	475	557	679		135	977.6	120	86	86	85	85	85	85	85	85	85	85	85
7		70	1.0	80	6.14	14.11	375	89	110	80	473	396	471	460	566	626		135	980.0	120	86	86	86	86	86	86	86	86	86	86	86
8		75	1.0	50	5.45	14.82	363	89	111	81	460	396	471	462	531	619		135	981.2	120	87	87	85	85	85	85	85	85	85	85	85
9		100																													
10		110																													
11		120																													
12		130																													
13		140																													
14		150																													
15		160																													
16		170																													
17		180																													
18		190																													
19		200																													
20		210																													
21		220																													
22		230																													
23		240																													
24		250																													
25		260																													
26		270																													
27		280																													
28		290																													
29		300																													
30		310																													
31		320																													
32		330																													
33		340																													
34		350																													
35		360																													
36		370																													
37		380																													
38		390																													
39		400																													
40		410																													
41		420																													
42		430																													
43		440																													
44		450																													
45		460																													
46		470																													
47		480																													
48																															

75 MIN  
 1.958 kg/hr

Door open for 55 seconds

COMMENTS:  
 TEST LOADED IN 20 SECONDS

Manufacturer MORSO Model DWL Date 7-13-00

Job # 31222 Run 4 Tech RA ACS

### PRETEST DILUTION TUNNEL TRAVERSE RUN

Barometric pressure ( $P_{bar}$ ) 29.15 (inches Hg.) Static pressure ( $P_g$ ) .110 (inches w.c.)

Inside diameter: Port A 6in. Port B 6in. Tunnel cross sectional area:  $0.1963\text{Ft}^2$

Pitot tube type: Standard

Traverse Point	Position (inches)	Velocity Head $\Delta_p$ (inches H <sub>2</sub> O)	Tunnel Temperature (°F)	$\sqrt{\Delta_p}$
A-Centroid	3.00	.041	104	.2025
B-Centroid	3.00	.039	105	.1975
A-1	0.40	.037	105	.1924
A-2	1.50	.041	105	.2025
A-3	4.50	.041	104	.2025
A-4	5.60	.036	105	.1897
B-1	0.40	.037	105	.1924
B-2	1.50	.039	105	.1975
B-3	4.50	.039	105	.1975
B-4	5.60	.036	105	.1897
		AVERAGE	+ 104.58	.1964

Adjustment factor application

$$V_s = K_p C_p F_p (\sqrt{\Delta_p})_{AVG} \sqrt{\frac{T_s}{P_s M_s}}$$

$$V_s = K_p C_p (\sqrt{\Delta_p})_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Pitot correction 9821

Where,

$C_p$  = Pitot tube coefficient = 0.99 for standard pitot

$\Delta_p$  = manometer reading (inches H<sub>2</sub>O)

$T_s$  = average absolute dilution tunnel temperature (°F + 460)

$P_s$  = absolute dilution tunnel gas pressure or  $P_{bar} + P_g$

$$F_p = \frac{(\sqrt{\Delta_p})_{avg}}{(\sqrt{\Delta_p})_{centroid}}$$

$P_g$  = static pressure inches H<sub>2</sub>O  
13.6

$M_s$  = 28.56, wet molecular weight of stack gas (alternatively, it may be measured)

$K_p$  = 85.49 Pitot tube constant, (conversion factor for English units)

Adjustment factor for alternative Pitot tube placement:

$(\sqrt{\Delta_p})_{avg}$  = Average of the square roots of the velocity heads ( $\Delta_p$ ) measured at each traverse point.

$(\sqrt{\Delta_p})_{centroid}$  = Average of the square roots of the velocity heads measured at the tunnel centroid (inches of H<sub>2</sub>O)

Manufacturer MORSO Model DWL Date 7-13-00  
 Job # 31222 Run 4 Tech RA ACS

**Pre/Post Checks**

Moisture Meter Calibration Check:

Time: <u>7:50</u>	X: <input checked="" type="checkbox"/>	Y: <input checked="" type="checkbox"/>	12: <input checked="" type="checkbox"/>	22: <input checked="" type="checkbox"/>
-------------------	--	--	---	---

**Facility Conditions:**

Air Velocity.....  
 Smoke Capture Check.....

Pre-Test	Post-Test
0 fpm	0 fpm
✓	✓

**Wood Heater Conditions:**

Date Wood Heater Stack Cleaned.....  
 Date Dilution Tunnel Cleaned.....  
 Induced Draft Check.....  
 Tunnel Velocity.....  
 Flow Rate 140-cfm ±10%.....

7-10-00	
7-10-00	
0	0
1040	
	141,486

**Pitot Leak Check:**

Side A.....  
 Side B.....

✓	✓
✓	✓

**Temperature System:**

Ambient (65°- 90°F).....  
 Wood Heater Surface (±125°F).....

	✓	°F
	-104.8	°F

**Proportional Checks:**

CO Analyzer Drift Check.....  
 CO<sub>2</sub> Analyzer Check.....  
 O<sub>2</sub> Analyzer Check.....  
 Thermocouple check.....

	✓
	✓
	✓
	✓

**Sampling Train ID Numbers:**

Probe.....  
 Filter Front.....  
 Filter Back.....  
 Filter Thermocouple.....  
 Filter 5G-3 (<90°F).....

	Train 1	Train 2
Probe	9	10
Filter Front	17	19
Filter Back	18	20
Filter Thermocouple	19	22
Filter 5G-3 (<90°F)	✓	✓

**Thermocouple Identification Number**

Flue.....1  
 Dilution Tunnel Wet Bulb.....4  
 Unit Right Side.....7  
 Catalyst/Combustion Chamber.....10

Room.....2  
 Unit Top.....5  
 Unit Left Side.....8

Dilution Tunnel Dry Bulb.....3  
 Unit Back.....6  
 Unit Bottom.....9

Manufacturer MORSO Model OWC Date 7-13-08  
 Job # 31222 Run 4 Tech RA ACS

**Pre-Test Scale Audit**

Scale Type	Audit Weight	Measured Weight
Platform	<u>10</u> lbs., Class F	<u>10.0</u> lbs.
Wood	<u>10</u> lbs., Class F	<u>10.00</u> lbs.
Analytical	100 Grams <u>100</u> mg, Class S	<u>100</u> Grams <u>100</u> mg.

**LIMITS OF WEIGHT RANGES**

**ANALYTICAL SCALE:** ..... 50%-150% of dry filter weight, ± 0.1 mg  
**PLATFORM SCALE:** ..... 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%  
**WOOD SCALE:** ..... 20%-80% of ideal test load weight, ± 0.1 lbs. or 1%

Manufacturer MORSO Model OWL Date 7-13-00  
 Job # 31222 Run 4 Tech RA

## SAMPLING EQUIPMENT CHECK OUT

### Leakage Checks Tunnel Samplers

	SYSTEM 1		SYSTEM 2	
	Pre-Test	Post-Test	Pre-Test	Post-Test
Unplugged Flow Rate = .25cfm				
Vacuum (inches Hg.)	10"	10"	10"	10"
Final 1minute DGM (ft <sup>3</sup> )	981.264	23.784	357.982	400.304
Initial 1minute DGM (ft <sup>3</sup> )	981.264	23.784	357.982	400.304
Change (C) (ft <sup>3</sup> )	0	0	0	0
Allowable leakage .04 x Sample rate or .02cfm	0.0100	0.0100	0.0100	0.0100
Check OK	✓	✓	✓	✓

### Leakage Checks Flue Gas Sampler

	Pre Test	Post Test
Plugged Probe		
Vacuum (inches Hg.)	10"	10"
Rotometer Reading (mm)	0	0
Flow Rate (CFM)	0	0
Allowable (.04 x Sample Rate)		
Check OK	✓	✓

Manufacturer MORSO Model OWC Date 7-13-00  
 Job # 31222 Run 4 Tech RA ACS

## CONTINUOUS ANALYZERS

Pre-Test (Adjust and Record)

	ZERO		SPAN		CAL. (Record Only)	
	Actual	Should Be	Actual	Should Be	Actual	Should Be
CO	0	0	9.99	9.99	234	2.36
CO <sub>2</sub>	0	0	24.65	24.65	5.78	5.88
O <sub>2</sub>	0	0	20.93	20.93	5.67	5.55

Post Test (Record Only)

	Zero	Span	Cal.	Zero Drift	Span Drift	Cal. Drift	OK?	Not OK*
'CO	.01	10.07	2.36	.08	.02	.02	✓	
CO <sub>2</sub>	.03	24.92	5.86	.27	.08	.08	✓	
O <sub>2</sub>	.06	20.81	5.72	.12	.05	.05	✓	

\* Greater than ± 5% of the range used.

Manufacturer MORSO Model QNL Date 7/13/00  
 Job # 31222 Run A Tech RA/ACS

### DILUTION TUNNEL PARTICULATE SAMPLER DATA

FILTER TYPE: Gelman 47mm A/E  
 Samples in Desecrator. Date: 7/13/00 Time: 1408

	SYSTEM 1		SYSTEM 2	
	Probe and Front Half Housing # <u>9</u>	Filter Numbers <u>17 + 18</u>	Probe and Front Half Housing # <u>10</u>	Filter Numbers <u>19 + 20</u>
Post Test Weight:	<u>92.2260</u> grams	<u>.2382</u> grams	<u>92.0565</u> grams	<u>.2442</u> grams
Pre Test Weight:	<u>92.2260</u> grams	<u>.2780</u> grams	<u>92.0565</u> grams	<u>.2332</u> Grams
Gain:	<u>∅</u> grams	<u>-.0102</u> grams	<u>∅</u> grams	<u>.0110</u> Grams
	a1	b1	a2	b2

Total Gain: a1 + b1 = -.0102 grams    a2 + b2 = .0110 grams

		SYSTEM 1			SYSTEM 2			TEMP	HUMID
Pre-test Weight Record		Probe & Housing Number	Front Filter Number	Back Filter Number	Probe & Housing Number	Front Filter Number	Back Filter Number	°F	%
Date	Time	<u>9</u>	<u>17</u>	<u>18</u>	<u>10</u>	<u>19</u>	<u>20</u>		
<u>7-12-00</u>	<u>12:06</u>	<u>92.2263</u>	<u>.1149</u>	<u>.1133</u>	<u>92.0570</u>	<u>.1193</u>	<u>.1153</u>	<u>80</u>	<u>45</u>
<u>7-13-00</u>	<u>7:05</u>	<u>92.2260</u>	<u>.1151</u>	<u>.1129</u>	<u>92.0565</u>	<u>.1180</u>	<u>.1152</u>	<u>73</u>	<u>49</u>
		Total	<u>.2280</u>		Total	<u>.2332</u>			

		SYSTEM 1		SYSTEM 2		TEMP	HUMID
Pre-test Weight Record		Probe & Housing Number	Combined Filter Weight Number	Probe & Housing Number	Combined Filter Weight Number	°F	%
Date	Time	<u>9</u>	<u>17 + 18</u>	<u>10</u>	<u>19 + 20</u>		
<u>7-13-00</u>	<u>14:08</u>	<u>92.2266</u>	<u>.2394</u>	<u>92.0569</u>	<u>.2456</u>	<u>82</u>	<u>50</u>
<u>7-14-00</u>	<u>7:20</u>	<u>92.2261</u>	<u>.2392</u>	<u>92.0565</u>	<u>.2444</u>	<u>78</u>	<u>50</u>
<u>7-17-00</u>	<u>7:30</u>	<u>92.2260</u>	<u>.2383</u>	<u>92.0565</u>	<u>.2442</u>	<u>74</u>	<u>50</u>
<u>7-17-00</u>	<u>10:45</u>	<u>92.2260</u>	<u>.2382</u>	<u>92.0565</u>	<u>.2442</u>	<u>77</u>	<u>49</u>



Manufacturer MORSO Model DWL Date 7-13-00  
 Job # 31222 Run 4 Tech RA Aes

## TEST DATA LOG

### RAW DRY GAS METER READINGS

	System 1	System 2
Final (ft <sup>3</sup> )	1023.779	400.294
Initial (ft <sup>3</sup> )	981.264	357.982

### AMBIENT CONDITIONS

	Start	End
Barometer. (inches Hg)	29.15	29.12
Wet Bulb (°F)	68	71 <del>BFALS</del>
Dry Bulb (°F)	76	85
Humidity (%)	63	50

Manufacturer MORSO Model OWL Date 7-13-08

Job # 31222 Run 4 Tech RA ACS

## FUEL DATA

### PRE-TEST LOAD

**FUEL DESCRIPTION:**

Kindling weight: 2.20 lbs. Consisting of: Scrap and paper Fire lit Time: 8:42  
 Pre-test load weight: 6.46 lbs. Consisting of: 2X4X inches Time loaded: \_\_\_\_\_  
 Pre-test moisture content: Uncorrected: 20.00 % Corrected Dry: 21.40 % Wet: 17.63 %

Test Air Control Settings: HOLE 1 Time: 9:35  
 Test Unit Fan Settings: \_\_\_\_\_ Time: \_\_\_\_\_

### TEST LOAD

	Lower Limit	Ideal	Upper Limit
Test Load Weight:	<u>6.27</u> Lbs.	<u>6.97</u> lbs.	<u>7.66</u> Lbs.
Fire Box Volume:	<u>1.995</u> Ft. <sup>3</sup>	Ideal Length:	_____ Inches
Load Volume:	_____ Ft. <sup>3</sup>	Loading Density:	<u>1,6492</u> lbs/ft <sup>3</sup>
Number of Spacers:	<u>12</u> <sup>3/4</sup> x1 <sup>1/2</sup> x5	Load Density:	<u>38,760</u> lbs/ft <sup>3</sup>

Piece Size	Weight	Meter Moisture Content (% dry)*			
<u>2 x 4 x 14</u> in.	<u>2.27</u> lbs.	<u>20.5</u> %	<u>18.5</u> %	<u>19.5</u> %	%
<u>2 x 4 x 14</u> in.	<u>2.27</u> lbs.	<u>21</u> %	<u>19.5</u> %	<u>20.5</u> %	%
<u>2 x 4 x 14</u> in.	<u>1.92</u> lbs.	<u>19.5</u> %	<u>18</u> %	<u>19.5</u> %	%
x x in.	lbs.	%	%	%	%
x x in.	lbs.	%	%	%	%
x x in.	lbs.	%	%	%	%
x x in.	lbs.	%	%	%	%

\*Uncorrected range = 17.9% to 23.1%


TEST LOAD WEIGHT: 6.46 lbs. DRY WEIGHT: 2.42 kg.  
 AVERAGE MOISTURE CONTENT:  
 (DRY) 20.00 % (WET) 17.63 % CORRECTED TO TWO PIN: (DRY) 21.40 % (WET) 17.34 %  
 COAL BED RANGE: 1.3 lbs. to 1.4 lbs. (20% to 25% of test load)  
 TEST CHARGE: ACS  
 Time loaded: 1055 Coal bed weight: 1.6 lbs. Coal bed weight = 24 % of test load weight

CHARCOALIZATION: good |~~X~~|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---| poor

Manufacturer MORSO Model DWL Date 7-13-00

Job # 31222 Run 4 Tech RA ACS

**COMMENTS**

0901	3.3 LBS	PREBURN FUEL ADDED
0912	4.75 LBS	PRE BURN FUEL ADDED
0948	1.26 LBS	PRE BURN FUEL ADDED
1017	1.16 LBS	PRE BURN FUEL ADDED
		<p>TEST LOAD CONFIGURATION</p> 

• K:\groups test forms sfa&ccc eval-sht testdata cesheets 9

Manufacturer MORSO Model OWL Date 7/13/00

Job # 31222 Run A Tech R6/KS

SWITCH NUMBER		1	2	3	4	5	6	7	8	9	10					
READING #	REAL TIME	ELAPSED TIME	WEIGHT REMAINING	FLUE GAS TEMP	ROOM TEMP	TUNNEL DRY BULB	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RIGHT SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CATALYST DOWNSTREAM	TUNNEL VELOCITY	DRAFT	SMOKE
0	936	0	4.0	465	83	118	76	583	218	366	346	317	813	.043	.076	C
1		10	3.10	400	83	109	77	599	249	406	378	326	768	.045	.076	C
2		20	3.60	401	84	109	77	608	273	412	394	333	764	.045	.080	C
3		30	2.70	387	84	107	77	585	285	410	403	356	737	.045	.080	C
4		40	2.10	365	83	106	79	560	297	411	413	375	702	.045	.080	C
5		50	2.80	358	83	107	80	549	310	402	416	388	675	.045	.075	C
6		60	2.10	333	85	105	81	513	379	396	410	393	637	.041	.075	C
7		70	1.90	313	84	104	81	480	313	392	401	398	605	.041	.075	C
8		80														
9		90														
10		100														
11		110														
12		120														
13		130														
14		140														
15		150														
16		160														
17		170														
18		180														
19		190														
20		200														
21		210														
22		220														
23		230														
24		240														
25		250														

Comments: FIRE STIRRED AT 10:54 DOOR OPEN 40 SEC

*CSA*

READING	REAL TIME	ELAPSED TIME	WEIGHT REMAIN	CO	CO <sub>2</sub>	O <sub>2</sub>	FLUE GAS TEMP	ROOM TEMP	TUNNEL TEMP	TUNNEL WET BULB	UNIT TOP	UNIT BACK	UNIT RT. SIDE	UNIT LEFT SIDE	UNIT BOTTOM	CAT EXIT	CAT CENTER	GAS SEMPL. ROTO.	DGM #1 READING	ROTO 1 READING	DGM TEMP INLET	DGM TEMP OUTLET	FILTER TEMP	DGM #2 READING	ROTO 2 READING	DGM TEMP INLET	DGM TEMP OUTLET	FILTER TEMP	TUNNEL VELOCITY	DRAFT	SMOKE	MAX DGM PRESS		
0	10:00	0	144	32	5.22	14.4	308	83	103	82	453	306	392	393	401	405		135	987.2	120	77	78	74	357.9	120	76	74	74	040	057	0			
1		10	5.20	78	5.40	14.98	333	84	109	83	460	310	368	373	373	373	373	135	983.6	120	78	78	85	360.3	120	77	76	85	040	061	2			
2		20	4.40	10	13.45	7.15	424	84	112	85	508	301	373	358	414	413		135	985.9	120	79	79	87	362.7	120	78	76	87	040	081	2			
3		30	5.10	02	14.80	5.73	435	86	114	85	562	310	372	368	385	526		135	988.3	120	80	80	89	365.2	120	79	78	86	040	091	2			
4		40	7.10	00	15.87	4.44	425	88	113	87	718	346	408	390	367	935		135	990.0	120	81	81	88	367.5	120	79	78	88	040	101	2			
5		50	1.50	09	16.09	4.16	310	88	110	84	614	342	421	404	352	748		135	991.6	120	82	82	89	369.9	120	80	79	89	040	111	2			
6		60	3.30	56	16.33	3.37	316	86	105	86	588	348	426	415	350	640		135	993.0	120	83	82	86	372.3	120	81	80	87	040	121	2			
7		70	1.10	01	16.17	3.91	278	87	102	85	474	336	366	407	323	583		135	998.0	120	84	83	85	374.7	120	82	81	85	040	131	2			
8		80	1.08	08	16.55	4.41	262	86	101	85	434	326	345	402	365	546		135	1000.4	120	84	83	85	377.0	120	82	81	86	040	141	2			
9	9.90	90	1.08	16	16.40	4.52	247	86	101	85	404	314	380	390	348	513		135	1002.8	120	85	84	85	379.4	120	83	82	86	040	151	2			
10		100	1.00	09	16.43	4.28	234	86	101	85	382	302	367	374	360	500		135	1005.2	120	86	85	84	381.8	120	83	82	85	040	161	2			
11		110	1.70	13	16.18	4.72	172	84	98	86	370	291	340	369	363	481		135	1007.6	120	86	85	85	384.2	120	84	83	85	040	171	2			
12		120	1.60	150	16.20	5.20	224	85	97	86	352	279	352	358	358	463		135	1010.0	120	86	86	85	386.6	120	84	83	86	040	181	2			
13		130	1.40	120	16.10	5.36	216	85	97	86	342	276	340	348	351	473		135	1012.4	120	86	86	85	389.0	120	84	84	86	040	191	2			
14		140	1.30	130	16.10	5.91	208	85	96	86	328	262	333	340	342	421		135	1014.8	120	86	86	85	391.4	120	85	84	86	040	201	2			
15		150	1.50	150	16.15	6.16	198	85	95	86	318	256	321	330	332	371		135	1017.2	120	87	87	86	393.8	120	85	84	86	040	211	2			
16		160	1.10	160	16.25	6.91	190	85	94	87	298	252	310	320	328	375		135	1019.6	120	87	87	86	396.2	120	86	85	86	040	221	2			
17		170	1.10	160	16.34	6.88	186	85	94	87	284	246	300	310	310	360		135	1022.0	120	88	88	85	398.6	120	86	85	86	040	231	2			
18	17.7	180	1.08	175	16.54	6.88	184	85	94	86	270	243	294	304	304	361		135	1024.4	120	88	88	84	400.0	120	86	85	86	040	241	2			
19		190																	1023.7															
20		200																																
21		210																																
22		220																																
23		230																																
24		240																																
25		250																																
26		260																																
27		270																																
28		280																																
29		290																																
30		300																																
31		310																																
32		320																																
33		330																																
34		340																																
35		350																																
36		360																																
37		370																																
38		380																																
39		390																																
40		400																																
41		410																																
42		420																																
43		430																																
44		440																																
45		450																																
46		460																																
47		470																																
48		480																																

177  
 818 KPH

COMMENTS: TEST LOADED IN 30 SECONDS DOOR CLOSED 4 MINUTES, AIR CONTROL CLOSED 5 MINUTES

## **APPENDIX B**

## INTRODUCTION

This document provides a step by step guide for the technician conducting tests to EPA standard requirements. Procedures outlined here, when followed, will result in tests in conformance with EPA Methods 28 and 5G-3. This guide cannot cover every possible contingency that may develop during a particular test program. Many questions that may arise can be answered by a complete understanding of the test standards and their intent. When in doubt on any detail check with the laboratory manager and be sure you understand the procedures involved.

The primary measurements to be obtained are particulate emission data and efficiency data. The technician's duties include the following steps. It is critical that all spaces on the data forms be properly filled in. Each test must be represented by a complete record of what was done and when.

### I. APPLIANCE INSPECTION AND SET-UP

- A. Incoming Inspection
- B. Unit Set-Up

### II. SAMPLING SYSTEMS - SET-UP

- A. Gas Analysis
- B. Dilution Tunnel

### III. TEST CONDUCT

- A. Pre-Test Fuel Load
- B. Test Fuel Load
- C. Unit Start - up
- D. Test Run

### IV. POST TEST PROCEDURE

- A. Leak Checks
- B. Particulate Sample Recovery

The technician running this test must be familiar with the following EPA documents that are to be kept in the laboratory at all times.

- 1. Method 28
- 2. Method 28A
- 3. Method 5G-3
- 4. Method 5H

## I. APPLIANCE INSPECTION AND SET-UP

### A. Incoming Inspection

1. Check for completeness of unit including parts, accessories, installation and operating instructions, drawings and specifications, etc. Note any discrepancies or missing parts.
2. Check for shipping damage. If damage has occurred, notify the laboratory manager. In some cases repairs may be made, provided the manufacturer and laboratory manager concur that repairs will not affect the units performance. If damage is irreparable, a new unit will need to be obtained.
3. Note whether unit is catalytic or non-catalytic.
4. Mark unit with manufacturer's name, model number, work order number and date received.
5. If unit is safety listed, note label data including listing agency and serial number.

### B. Unit Set-Up

1. All units must be operated in-house for a break-in period as follows (the unit may be connected to a lab chimney). NOTE: Inserts are tested as if they are freestanding stoves.
  - a. Non-catalytic units: 10 hours minimum burn time with a stack temperature of at least 250<sup>o</sup> Fahrenheit (medium burn rate, Douglas Fir scrap or cordwood.) A stack thermocouple must be installed and stack temperature recorded at 1-hour intervals or on chart recorder.
  - b. Catalytic units: 50 hours minimum burn time with catalyst temperature in excess of 800<sup>o</sup> Fahrenheit (medium burn rate, Douglas Fir scraps or cordwood). Record catalyst temperature at 1-hour intervals or on chart recorder.
2. Once break-in is completed, allow unit to cool then clean unit thoroughly.
3. Thermocouples must be attached to surfaces of unit prior to testing. EPA requires a thermocouple on the outside bottom of the firebox. This must be installed prior to putting the unit on the scale. In some cases the required thermocouple locations will be inaccessible on finished units. Check with the laboratory manager if problems are encountered in proper thermocouple attachment.
4. Prior to placing unit on scale, the scale must be turned on and allowed to warm up for 1-hour minimum.
5. Place unit on scale and align so chimney will be centered in hood. Record the weight of the unit and all accessories. (Do not weight with chimney attached.)



6. Chimney and connector should be cleaned with a wire brush prior to mounting. Attach chimney and connector then seal all joints. Be sure single wall stove pipe terminates and insulated pipe starts at proper level above scale platform. Chimney must be supported from scale so that it does not touch test enclosure or hood walls.
7. Measure firebox dimensions and record on appropriate data form. Make a three dimensional sketch of the firebox including firebrick, baffles, and obstructions. Calculate firebox volume in cubic feet. See Section 6.2.4 of EPA Method 28 for details.
8. If unit is equipped with a catalyst additional thermocouples must be installed downstream of, and inside catalyst (upstream optional).
9. Plug thermocouples into data acquisition system jacks and verify that all instrumentation is working properly.
10. Dilution tunnel must be cleaned prior to each certification test series, and at anytime a higher burn rate follows a lower burn rate.

## II. SAMPLING SYSTEMS SET-UP

### A. Gas Analysis

1. All instruments should be turned on and allowed to warm up for 1-hour minimum.
2. Prior to calibrating, make sure that the outlet pressure on each calibration gas bottle reads 10 PSI. Adjust flow meters at each gas analyzer to required flow.

All gas analyzers (CO<sub>2</sub>, CO, O<sub>2</sub>) are zeroed on nitrogen. The O<sub>2</sub> analyzer is spanned on air and set for 20.93%. CO<sub>2</sub> and CO analyzers are spanned with their respective gases.

Calibrate analyzers as follows:

- a. With calibration switch at "SPAN", adjust all span controls to values specified on span gas label.
  - b. Switch to "ZERO" and adjust zero controls to provide 0.00 readout on all analyzers.
  - c. Repeat a. and b. until no further adjustment is required.
  - d. Record these values on the appropriate data sheet.
  - e. Switch to "CAL." and record all analyzer values.
3. Response time synchronization check.
    - a. With switch at "SAMPLE" and no fire in unit, allow readings to stabilize (O<sub>2</sub> analyzer should read 20.93, CO and CO<sub>2</sub> should read 0.00).
    - b. Switch to "CAL" setting and start the stopwatch. Note the time required for each unit to reach the calibration gas bottle value. If all three analyzers reach this value within 5 seconds of each other, synchronization is adequate. If not, contact the laboratory manager. Synchronization is adjusted by either internal instrument setting or adjustment of sample line length.
    - c. Use EPA Method 5H 6.7-6.9 procedures to check calibration of instruments.

4. Sample clean-up train.
  - a. Load a new filter in 4-inch glass filter holder.
  - b. Load four Impingers as follows:
    - #1: 100 ml. distilled water and 5 ml.  $H_2SO_4$
    - #2: 100 ml. distilled water and 5 ml.  $H_2SO_4$
    - #3: Empty
    - #4: 200-300 grams Drierite.
  - c. Place Impingers in container and connect with greased "U TUBES".  
(Grease carefully on bottom half of ball joint so that grease will not get into tubes.)
  - d. Connect filter to impinger #1 and sample line to impinger #4.
  - e. Connect stack probe to filter.
  - f. Leak check system as follows:
    - 1) Plug probe.
    - 2) Turn on sample system and increase flow rate slowly.
    - 3) Set vacuum adjust valve to obtain a vacuum of 10 inches mercury.
    - 4) If sapphire float in rotometer does not stabilize below 10 on scale, system must be resealed.
    - 5) Repeat leak check procedure until satisfactory results are obtained.
    - 6) Unplug probe slowly, then decrease flow rate slowly before shutting off system.
  - g. Just prior to starting test, fill impinger container with ice.

B. Dilution Tunnel Sample Train Set-Up:

1. Filters and holders.

- a. Clean probes and filter holder front housings carefully and desiccate to a constant weight prior to use.
- b. Filters and filter probe combinations should be numbered and labeled prior to use.
- c. Weigh desiccated filters and probe filter units on analytical balance. Record weights on appropriate form. Note that probe and front half of front filter holder is to be weighed as a unit.
- d. Carefully assemble filter holder units and connect to sampling systems.
- e. Check Silica gel columns for adequate dry absorbent (blue color).

2. Leak checking.

- a. Each sample system is to be checked for leakage prior to inserting probes in tunnel.
- b. Plug probes and start samplers. Adjust pump bypass valve to produce a vacuum reading of 10 inches mercury. NOTE: During test, highest vacuum recorded is required for posttest leak check.
- c. Allow vacuum indication to stabilize at 10" mercury, record dry gas meter readings, (DGM<sub>1</sub>, DGM<sub>2</sub>). At a convenient DGM value start stopwatch. Time for 1 minute then stop vacuum pumps. Record dry gas meter readings again, (DGM<sub>3</sub>, DGM<sub>4</sub>). NOTE: If rotometer ball is floating above the 5-mm mark, system is leaking too much and all seals should be checked.
- d. Calculate leakage rate as follows.

$$\text{System 1: } DGM_3 - DGM_1 = CFM_1$$

$$\text{System 2: } DGM_4 - DGM_2 = CFM_2$$

If CFM<sub>1</sub> or CFM<sub>2</sub> is greater than 0.02 cfm, or <sub>1</sub>S greater than 0.04 x Sample Rate, leakage is unacceptable and system must be resealed.

For most tests the sample rate will be 0.25 cfm, thus leakage rates in excess of 0.04 x 0.25 = 0.010 cfm are not acceptable.

- e. To prevent contamination, do not insert probes in tunnel until the start of the test run.

### III. TEST CONDUCT

#### A. Pre-Test Fuel Load

1. Using 2x4 Douglas Fir cut enough pieces to approximate test load weight. (Piece length must be greater than 1/3 of the test load length.)
2. Measure percent moisture content using Delmhorst moisture meter. The average percent moisture must be within 19 to 25 percent.

#### B. Test Fuel Load

1. Determine optimum load weight by multiplying firebox volume (cubic feet) by 7. This is the ideal load weight.
2. Determine piece size mix i.e. <1.5 cubic feet volume use 2x4's only; 1.5 ft<sup>3</sup> to 3.0 ft<sup>3</sup> use a mix of 2.4's and 4x4's; >3.0 ft<sup>3</sup> use only 4x4's. Ideal length is 5/6 of the longest firebox dimension.
3. Weigh out test load and appropriate number of spacers and adjust weight by shortening or lengthening all pieces equally if necessary.
4. Construct test loads by attaching spacers as shown in EPA Method 28.
5. Measure and record moisture content of each fuel piece (use three sides). Determine if fuel load moisture content is within required range (19-25%). If not, construct new fuel pieces using wood with required moisture content. All wood in the humidity chamber is Douglas Fir and should be within range. Contact laboratory manager if you cannot find suitable pieces.

#### C. Unit Start-Up

1. With all doors and air controls closed, zero draft Magnehelic using screw located at bottom of meter.
2. Before lighting a fire, turn on dilution tunnel and set flow rate to 140 scfm (approximately 715 fpm) if burn rate is to be less than 3 kg/hr. For higher burn rates set flow for a 150:1 air fuel ratio (see chart for approximate values).
3. Check draft imposed on cold stove. All inlets must be closed and a draft gauge in the chimney. If draft is greater than 0.005 inches water column, adjust tunnel to stack gap until draft is less than 0.005 inches water column.
4. With hot wire anemometer check for ambient airflow around unit (must be less than 50 ft/min).
5. Zero scale and start fire with newspaper and Douglas Fir kindling. (Make sure stack sample probe is on the unit.)

6. Once kindling is burning well, add preload fuel. Operate at high fire for sufficient time to get fuel load burning well. Then adjust settings to intended test run levels.
7. Perform the dilution tunnel traverse as prescribed in Method 28, Section 6.3. (Pitot tube should be carefully cleaned prior to each test.)
8. Pretest load must burn for a minimum of 1 hour. Record stove surface, catalyst, room and flue temperatures.
9. Stir fire often during preburn (after a reading) to get a good coal bed. Fire can only be raked once (door open 1 minute or less) during the 15 minutes prior to the start of the test.

#### D. Test Run

1. Stack gas analyzers should be on and in the sample mode.
2. When the fuel bed is between 20-25% of the test load weight the test is to be started.
  - a. Insert the sample probes into the tunnel being careful not to hit sides of tunnel with probe tip.
  - b. Check tunnel Pitot tube for proper position.
  - c. Record initial readings.
  - d. Turn on probe sample systems and start timing test.
  - e. Tare platform scale.
  - f. Open stove doors and load stove. Close door or follow manufacturer's start-up procedures. Five minutes is the maximum time before all doors and controls must be set to final positions for duration of test.
  - g. Record length of time door and bypass are open, include any air control setting adjustments.
  - h. Every 10 minutes record the following:
    - 1) Dry gas meter readings.
    - 2) Weight remaining.
    - 3) All thermocouple temperatures.
    - 4) Tunnel Pitot tube reading.
    - 5) Draft reading.
    - 6) Rotometer readings.
  - i. Filter temperatures shall not exceed 901F anytime during the test. If approaching 901F turn on cooling pump. Filters must be kept above the dilution tunnel wet bulb temperature in order to prevent condensation.
  - j. Regularly check impinger for ice level during test.
  - k. After 30 seconds of 0.00 lbs. weight, and on the minute, shut off sample trains and record last reading.
  - l. Record final dry gas meter values.

#### IV. POST TEST PROCEDURES

##### A. Leak Checks

###### 1. Dilution Tunnel

- a. Remove both sample probes from tunnel and plug with rubber stopper.
- b. Turn on sample system and set vacuum to 10" mercury or to the highest value reached during the test.
- c. At a convenient value start stop watch. Record DGM starting value.
- d. After 1 minute stop sample system and record ending DGM value.
- e. Calculate leakage rate per pre-test description (see II.B.2.c.).

###### 2. Gas Analyzers

- a. Set stack sample flow to about 75 mm on the rotometer.
- b. Plug with rubber stopper.
- c. Adjust vacuum to 10" mercury.
- d. Let system stabilize then record rotometer readings.
- e. If rotometer readings do not equal zero check with laboratory manager.
- f. SLOWLY unplug probe and decrease flow rate to zero.
- g. Turn off stack sampling system.
- h. Zero, span and calibrate the analyzers (see Gas Analysis). RECORD ONLY these meter values.

##### B. Particulate Sample Recovery

1. Disassemble filter holder and scrape gasket with scalpel. Collect all loose material on filters.
2. Weigh and record probes and filters for each train. NOTE: 24 hours of desiccation must pass before final "no change" weight values can be recorded.
3. Weigh and record probes and fillers at 2-hour intervals until weight change between weighing is less than 0.5 mg.

#### V. DISPOSITION OF TESTED UNIT.

In order to meet the requirements of section 60.535(g) of the EPA's 40CFR Part 60 Standards of Performance for New Stationary Sources; New Residential Wood Heaters, Intertek Testing Services seals certified wood heaters by strapping the unit to a pallet and covering the unit with stretch wrap. A copy of the EPA certificate is attached and our WHI logo stamped on the stretch wrap in various positions and then another layer of stretch wrap is used to cover the markings and copy of the certificate. Any breaking of the stretch wrap seal will be easily noticeable. The unit is then shipped back to the manufacturer.

# APPENDIX C



Manufacturer: Morso  
 Model: Owl  
 Date: 07/11/00  
 Run: 1  
 Project #: 31222  
 Test Duration: 215  
 Total Gas Volume (DGM 1): 49.5686  
 Total Gas Volume (DGM 2): 49.14104  
 Average Barometric Pressure: 29.15  
 Molecular Weight: 28.56  
 Pitot Correction: 0.983  
 Calibration Factor (DGM #1): 1.0155  
 Calibration Factor (DGM #2): 1.0107  
 (1) VS: 0.029802  
 (2) VS: 0.030061

Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	Filter Face	Filter Face
								Velocity DGM 1	Velocity DGM 2
0	890.8	79	79	267.7	77	77	93		
10	893.2	80	80	270.0	79	78	100	20.01	19.14
20	895.6	81	81	272.4	80	78	96	19.97	19.95
30	898.0	82	82	274.6	81	79	96	19.93	18.25
40	900.4	83	83	277.2	82	81	95	19.90	21.51
50	902.8	85	84	279.6	84	82	96	19.84	19.80
60	905.2	84	84	282.0	83	83	100	19.86	19.80
70	907.6	84	84	284.4	84	84	101	19.86	19.77
80	910.0	84	84	286.8	84	84	99	19.86	19.77
90	912.4	84	84	289.3	85	85	98	19.86	20.55
100	914.7	84	84	291.6	85	85	96	19.03	18.91
110	917.0	85	85	293.9	85	85	96	19.00	18.91
120	919.5	85	84	296.3	86	86	94	20.67	19.69
130	921.9	85	85	298.7	85	86	93	19.82	19.71
140	924.3	84	85	301.1	85	86	93	19.84	19.71
150	926.7	84	84	303.5	85	85	94	19.86	19.73
160	929.1	84	84	305.9	84	85	94	19.86	19.75
170	931.5	84	84	308.3	84	85	88	19.86	19.75
180	933.9	84	84	310.7	84	85	87	19.86	19.75
190	936.3	84	84	313.1	84	85	86	19.86	19.75
200	938.7	83	83	315.5	83	84	85	19.90	19.78
210	941.2	83	83	317.9	84	84	85	20.73	19.77
215	942.4	83	83	319.1	83	84	85	19.90	19.78

Proportional Rate Calculations

(EPA Formulas from PR5G)

Stack area (ft<sup>2</sup>): 0.1963  
 Wood moisture (% wet): 17.71  
 Load Weight (lbs wet): 6.72  
 Burn Rate (Dry kg/hr): 0.700

Manufacturer: Morso  
 Model: Owl  
 Date: 07/11/00  
 Run: 1

Final Temperature (DGM #1) Degrees Rankin: 543.370  
 Final Temperature (DGM #2) Degrees Rankin: 543.304  
 Final Tunnel Temperature Degrees Rankin: 553.478  
 Final Tunnel Velocity (feet per second): 13.6271066  
 Standardized Tunnel Flow (dscfm): 143.147249

Tunnel	Tunnel Velocity	Average Inlet + Outlet Temp. Meter 1	Average Inlet + Outlet Temp. Meter 2	PR1	PR2	#1 dDGM Vol. Std. (ft <sup>3</sup> )	#2 dDGM Vol. Std. (ft <sup>3</sup> )	Time
0.039	13.392	539.0	537.0					0
0.039	13.477	540.0	538.5	102.98	99.36	2.321	2.220	10
0.039	13.429	541.0	539.0	102.43	103.21	2.316	2.314	20
0.041	13.769	542.0	540.0	99.71	92.10	2.312	2.117	30
0.041	13.756	543.0	541.5	99.44	108.45	2.308	2.495	40
0.041	13.769	544.5	543.0	99.25	99.92	2.302	2.297	50
0.041	13.818	544.0	543.0	99.70	100.28	2.304	2.297	60
0.041	13.830	544.0	544.0	99.79	100.18	2.304	2.293	70
0.040	13.636	544.0	544.0	100.85	101.25	2.304	2.293	80
0.041	13.793	544.0	545.0	99.52	103.89	2.304	2.384	90
0.041	13.769	544.0	545.0	95.21	95.40	2.208	2.193	100
0.040	13.600	545.0	545.0	96.21	96.59	2.204	2.193	110
0.040	13.575	544.5	546.0	104.49	100.42	2.398	2.284	120
0.040	13.563	545.0	545.5	100.12	100.42	2.299	2.287	130
0.040	13.563	544.5	545.5	100.22	100.42	2.302	2.287	140
0.040	13.575	544.0	545.0	100.40	100.61	2.304	2.289	150
0.041	13.744	544.0	544.5	99.17	99.46	2.304	2.291	160
0.041	13.669	544.0	544.5	98.63	98.92	2.304	2.291	170
0.041	13.657	544.0	544.5	98.54	98.83	2.304	2.291	180
0.040	13.477	544.0	544.5	99.67	99.97	2.304	2.291	190
0.040	13.465	543.0	543.5	99.76	100.06	2.308	2.295	200
0.041	13.632	543.0	544.0	102.64	98.74	2.404	2.293	210
0.040	13.465	543.0	543.5	99.76	100.06	1.154	1.147	215

Manufacturer: Morso  
 Model: Owl  
 Date: 07/12/00  
 Run: 2  
 Project #: 31222  
 Test Duration: 87  
 Total Gas Volume (DGM 1): 19.93602  
 Total Gas Volume (DGM 2): 20.09422  
 Average Barometric Pressure: 29.12  
 Molecular Weight: 28.56  
 Pitot Correction: 0.986  
 Calibration Factor (DGM #1): 1.0155  
 Calibration Factor (DGM #2): 1.0107  
 (1) VS: 0.072559  
 (2) VS: 0.071988

Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	Filter Face	Filter Face
								Velocity DGM 1	Velocity DGM 2
0	942.5	79	79	319.2	76	76	111		
10	944.8	80	79	321.5	78	77	128	19.25	19.15
20	947.1	80	80	323.9	79	77	122	19.15	19.97
30	949.5	81	80	326.3	79	78	120	19.97	19.95
40	951.9	82	81	328.7	80	79	117	19.93	19.91
50	954.3	82	82	331.1	81	79	107	19.91	19.89
60	956.7	83	82	333.5	81	80	103	19.89	19.87
70	959.1	84	83	335.9	82	81	101	19.86	19.84
80	961.5	84	84	338.4	82	83	98	19.84	20.63
87	963.2	84	84	340.1	83	82	98	20.08	20.04

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft2):	0.1963			Manufacturer:	Morso			
Wood moisture (% wet):	17.76			Model:	Owl			
Load Weight (lbs wet):	6.6			Date:	07/12/00			
Burn Rate (Dry kg/hr):	1.698			Run:	2			
Final Temperature (DGM #1) Degrees Rankin:				541.650				
Final Temperature (DGM #2) Degrees Rankin:				539.650				
Final Tunnel Temperature Degrees Rankin:				570.500				
Final Tunnel Velocity (feet per second):				13.7541969				
Standardized Tunnel Flow (dscfm):				140.027174				
		Average Inlet + Outlet Temp.	Average Inlet + Outlet Temp.			#1 dDGM Vol. Std. (ft3)	#2 dDGM Vol. Std. (ft3)	
Tunnel Velocity	Ft/Sec	Meter 1 Deg. R	Meter 2 Deg. R	PR1	PR2			Time
0.040	13.831	539.0	536.0					0
0.039	13.859	539.5	537.5	99.70	98.39	2.234	2.222	10
0.039	13.788	540.0	538.0	98.67	102.04	2.222	2.316	20
0.038	13.587	540.5	538.5	104.03	103.10	2.316	2.314	30
0.040	13.904	541.5	539.5	100.95	100.05	2.312	2.310	40
0.040	13.783	542.0	540.0	99.97	99.08	2.310	2.307	50
0.040	13.734	542.5	540.5	99.53	98.64	2.308	2.305	60
0.040	13.710	543.5	541.5	99.17	98.29	2.303	2.301	70
0.040	13.673	544.0	542.5	98.81	101.92	2.301	2.393	80
0.040	13.673	544.0	542.5	99.99	99.01	1.630	1.627	87

Manufacturer:		Morso							
Model:		Owl							
Date:		07/12/00							
Run:		3							
Project #:		31222							
Test Duration:		75							
Total Gas Volume (DGM 1):		17.15571							
Total Gas Volume (DGM 2):		17.03679							
Average Barometric Pressure:		29.12							
Molecular Weight:		28.56							
Pitot Correction:		0.9781							
Calibration Factor (DGM #1):		1.0155							
Calibration Factor (DGM #2):		1.0107							
(1) VS:		0.084967							
(2) VS:		0.08556							
								Filter Face Velocity	Filter Face Velocity
Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	DGM 1	DGM 2
0	963.3	82	82	340.1	80	80	112		
10	965.7	82	82	342.5	80	80	131	19.91	19.89
20	968.0	83	83	344.8	81	81	134	19.05	19.03
30	970.4	83	84	347.2	82	81	130	19.86	19.84
40	972.8	84	84	349.6	83	81	124	19.84	19.82
50	975.2	85	84	351.9	84	83	117	19.82	18.94
60	977.6	86	85	354.3	84	83	113	19.78	19.76
70	980.0	86	86	356.7	85	84	110	19.77	19.73
75	981.2	87	87	357.9	85	84	111	19.73	19.73

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft2):	0.1963			Manufacturer:	Morso			
Wood moisture (% wet):	17			Model:	Owl			
Load Weight (lbs wet):	6.5			Date:	07/12/00			
Burn Rate (Dry kg/hr):	1.958			Run:	3			
Final Temperature (DGM #1) Degrees Rankin:				544.167				
Final Temperature (DGM #2) Degrees Rankin:				542.278				
Final Tunnel Temperature Degrees Rankin:				580.222				
Final Tunnel Velocity (feet per second):				14.0961824				
Standardized Tunnel Flow (dscfm):				141.104182				
		Average Inlet + Outlet Temp. Meter 1	Average Inlet + Outlet Temp. Meter 2			#1 dDGM Vol.Std. (ft3)	#2 dDGM Vol.Std. (ft3)	
Tunnel Velocity	Ft/Sec	Deg. R	Deg. R	PR1	PR2			Time
0.040	13.733	542.0	540.0					0
0.040	13.959	542.0	540.0	103.87	104.48	2.310	2.307	10
0.042	14.340	543.0	541.0	97.21	97.78	2.210	2.207	20
0.042	14.292	543.5	541.5	101.00	101.60	2.303	2.301	30
0.042	14.219	544.0	542.0	100.39	100.99	2.301	2.299	40
0.042	14.133	544.5	543.5	99.70	95.93	2.299	2.197	50
0.042	14.084	545.5	543.5	99.17	99.75	2.295	2.293	60
0.042	14.047	546.0	544.5	98.82	99.31	2.293	2.288	70
0.042	14.060	547.0	544.5	98.72	99.40	1.144	1.144	75

**Manufacturer:** Morso  
**Model:** Owl  
**Date:** 07/13/00  
**Run:** 4  
**Project #:** 31222  
**Test Duration:** 177  
**Total Gas Volume (DGM 1):** 40.78394  
**Total Gas Volume (DGM 2):** 40.63902  
**Average Barometric Pressure:** 29.135  
**Molecular Weight:** 28.56  
**Pitot Correction:** 0.9821  
**Calibration Factor (DGM #1):** 1.0155  
**Calibration Factor (DGM #2):** 1.0107

**(1) VS:** 0.035824  
**(2) VS:** 0.035952

Elapsed Time	DGM 1 Reading	DGM 1 Inlet T	DGM 1 Outlet T	DGM 2 Reading	DGM 2 Inlet T	DGM 2 Outlet T	Tunnel Dry Bulb	Filter Face	Filter Face
								Velocity DGM 1	Velocity DGM 2
0	981.2	77	78	357.9	77	76	103		
10	983.6	78	78	360.3	77	76	109	20.07	20.03
20	985.9	79	79	362.7	78	76	112	19.20	20.01
30	988.3	80	80	365.2	79	78	114	20.00	20.79
40	990.7	81	80	367.5	79	78	113	19.98	19.13
50	993.2	82	81	369.9	80	79	110	20.77	19.92
60	995.6	83	82	372.3	81	80	105	19.90	19.88
70	998.0	84	83	374.7	82	81	102	19.87	19.85
80	1000.4	84	83	377.0	82	81	101	19.87	19.02
90	1002.8	85	84	379.4	83	82	99	19.83	19.81
100	1005.2	86	85	381.8	83	82	99	19.79	19.81
110	1007.6	86	85	384.2	84	83	98	19.79	19.77
120	1010.0	86	86	386.5	84	83	86	19.78	18.95
130	1012.4	86	86	389.0	84	84	97	19.78	20.58
140	1014.8	86	87	391.4	85	84	96	19.76	19.74
150	1017.2	87	87	393.8	85	84	95	19.74	19.74
160	1019.6	87	87	396.2	86	85	91	19.74	19.70
170	1022.0	88	85	398.6	86	85	94	19.76	19.70
177	1023.7	88	88	400.3	86	85	94	19.94	19.87

Proportional Rate Calculations				(EPA Formulas from PR5G)				
Stack area (ft2):	0.1963			Manufacturer:	Morso			
Wood moisture (% wet):	17.63			Model:	Owl			
Load Weight (lbs wet):	6.46			Date:	07/13/00			
Burn Rate (Dry kg/hr):	0.818			Run:	4			
Final Temperature (DGM #1) Degrees Rankin:				543.605				
Final Temperature (DGM #2) Degrees Rankin:				541.658				
Final Tunnel Temperature Degrees Rankin:				560.947				
Final Tunnel Velocity (feet per second):				13.659639				
Standardized Tunnel Flow (dscfm):				141.505557				
		Average	Average					
		Inlet +	Inlet +					
		Outlet	Outlet			#1	#2	
		Temp.	Temp.			dDGM	dDGM	
Tunnel	Tunnel	Meter 1	Meter 2			Vol.Std.	Vol.Std.	
Velocity	Ft/Sec	Deg. R	Deg. R	PR1	PR2	(ft3)	(ft3)	Time
0.040	13.676	537.5	536.5					0
0.040	13.749	538.0	536.5	101.83	101.99	2.328	2.324	10
0.040	13.785	539.0	537.0	97.66	102.17	2.227	2.322	20
0.040	13.809	540.0	538.5	101.90	106.31	2.320	2.412	30
0.040	13.797	540.5	538.5	101.71	97.72	2.317	2.219	40
0.040	13.761	541.5	539.5	105.48	101.52	2.410	2.311	50
0.040	13.700	542.5	540.5	100.63	100.88	2.309	2.306	60
0.042	14.001	543.5	541.5	97.76	98.01	2.305	2.302	70
0.040	13.652	543.5	541.5	100.09	96.16	2.305	2.206	80
0.040	13.627	544.5	542.5	99.73	99.97	2.300	2.298	90
0.040	13.627	545.5	542.5	99.54	99.97	2.296	2.298	100
0.040	13.615	545.5	543.5	99.45	99.70	2.296	2.294	110
0.040	13.468	546.0	543.5	98.29	94.51	2.294	2.198	120
0.039	13.432	546.0	544.0	100.54	104.99	2.294	2.387	130
0.040	13.591	546.5	544.5	99.09	99.34	2.292	2.290	140
0.040	13.579	547.0	544.5	98.91	99.25	2.290	2.290	150
0.040	13.530	547.0	545.5	98.56	98.71	2.290	2.285	160
0.040	13.566	546.5	545.5	98.91	98.98	2.292	2.285	170
0.040	13.566	548.0	545.5	99.82	99.80	1.619	1.613	177



# APPENDIX D

# Intertek Testing Services

**Warnock Hersey**  
Middleton, Wisconsin

## Post Test Dry Gas Meter Calibration Data

Manufacturer: Moroso      Model: Owl      Job Number: 31222      Date: 07/14/00      Tech: RA ACS  
 Barometric Press: 29.05      Calibration Factors:      DGM#1: 1.0155      DGM#2: 1.0107      Std. Meter DGM#3: 1.0293

### Standardized Meter # 3

Trial No.	Press Drop	System # 1		Change Ft. <sup>3</sup>	Temp °F	Std. Ft. <sup>3</sup>	Final Ft. <sup>3</sup>	Initial Ft. <sup>3</sup>	Change Ft. <sup>3</sup>	Temp °F	Std Ft. <sup>3</sup>	Cal Factor
		Final Ft. <sup>3</sup>	Initial Ft. <sup>3</sup>									
1	0.4	442.082	444.525	2.4430	73.5	2.4163	26.552	29.01	2.4580	77.5	2.3807	1.0150
2	0.4	444.525	446.894	2.3690	74	2.3409	29.01	31.527	2.5170	78	2.4356	0.9611
3	0.4	446.894	448.137	1.2430	74	1.2283	31.527	32.799	1.2720	78	1.2308	0.9979
Average:												0.9913

Previous Cal Factor: 1.0155      Minus Avg. Cal. Factor      divided by      Previous Cal Factor      Times 100      equals      Present Deviation      =      2.3800

### Standardized Meter #3

Trial No.	Press Drop	System # 2		Change Ft. <sup>3</sup>	Temp °F	Std. Ft. <sup>3</sup>	Final Ft. <sup>3</sup>	Initial Ft. <sup>3</sup>	Change Ft. <sup>3</sup>	Temp °F	Std Ft. <sup>3</sup>	Cal Factor
		Final Ft. <sup>3</sup>	Initial Ft. <sup>3</sup>									
1	0.4	449.8745	452.222	2.3475	75	2.3153	402.05	404.452	2.4020	78	2.3133	1.0009
2	0.4	452.222	454.512	2.2900	75.5	2.2565	404.452	406.741	2.2890	79	2.2004	1.0255
3	0.4	454.512	455.69	1.1780	76	1.1597	406.741	407.945	1.2040	77.5	1.1606	0.9992
Average:												1.0085

Previous Cal Factor: 1.0107      Minus Avg. Cal. Factor      divided by      Previous Cal Factor      Times 100      equals      Present Deviation      =      0.21491



Manufacturer \_\_\_\_\_ Model \_\_\_\_\_ Date \_\_\_\_\_

Job # \_\_\_\_\_ Run \_\_\_\_\_ Tech \_\_\_\_\_

POST TEST DRY GAS METER CALIBRATION DATA

MANUFACTURER: MOLSO MODEL: QWL LTO: 7/14/00 TECHNICIAN: RA/ACS

BAROMETRIC PRESSURE: 29.04 CALIBRATION FACTOR DGM#1: 1.0155 DGM#2: 1.0107 STANDARDIZED DGM#3:

TRAIL NO.	STANDARD METER						METER #1					
	PRESS DROP	FINAL FT. <sup>3</sup>	INITIAL FT. <sup>3</sup>	CHANGE FT. <sup>3</sup>	TEMP °F	STD FT. <sup>3</sup>	FINAL FT. <sup>3</sup>	INITIAL FT. <sup>3</sup>	CHANGE FT. <sup>3</sup>	TEMP °F	STD FT. <sup>3</sup>	CAL. FACTOR
1	.4	444.525	442.082	24436	73.5	2.4163	29.010	26.552	2.458	77.5	2.3807	1.0150
2	.4	446.894	444.525	2369	74	2.3409	31.577	<del>29070</del>	2.5770	78	2.4356	.9611
3	.4	448.137	446.894	1,2430	74	1.2283	32.799	31.527	1.2712	70	1.2308	.9979

AVERAGE CALIBRATION FACTOR: -9913

PREVIOUS CAL. FACTOR	MINUS	AVERAGE CAL. FACTOR		DIVIDED BY	EQUALS	MULTIPLIED *100	DEVIATION PERCENT
		MINUS	AVERAGE CAL. FACTOR				
-	-	-	-	/	=	*100	%

TRAIL NO.	STANDARD METER						METER #2					
	PRESS DROP	FINAL FT. <sup>3</sup>	INITIAL FT. <sup>3</sup>	CHANGE FT. <sup>3</sup>	TEMP °F	STD FT. <sup>3</sup>	FINAL FT. <sup>3</sup>	INITIAL FT. <sup>3</sup>	CHANGE FT. <sup>3</sup>	TEMP °F	STD FT. <sup>3</sup>	CAL. FACTOR
1	.4	452.224	449.874	23475	75	2.3153	404.470	402.050	2.420	76.5	2.3133	1.0209
2	.4	454.512	452.222	2290	75.5	2.2525	406.741	404.425	2.2890	79	2.2054	1.0253
3	.4	455.890	454.512	1,1780	76	1.1597	407.945	406.741	1.2040	77.5	1.1606	.9992

AVERAGE CALIBRATION FACTOR: 1.0086

PREVIOUS CAL. FACTOR	MINUS	AVERAGE CAL. FACTOR		DIVIDED BY	EQUALS	MULTIPLIED *100	DEVIATION %
		MINUS	AVERAGE CAL. FACTOR				
-	-	-	-	/	=	*100	%

PERCENT OF DEVIATION MUST BE LESS THAN 5 %. IF DEVIATION IS MORE THAN 5 %, THE UPDATED CALIBRATION FACTOR MUST BE USED.

# APPENDIX E

Manufacturer MORSO Model OWL Date 7/14 Page      of       
 Job # 31222 Run      Tech RA/ACS

### POST TEST 5-POINT GAS ANALYZER CHECK

	CO		CO <sub>2</sub>		O <sub>2</sub>	
	Actual	Should Be	Actual	Should Be	Actual	Should Be
Zero Gas	.0	0	.0	0	0	0
Span Gas	9.99	9.99	24.65	24.65	20.93	20.93
Cal Gas #1	2.34	2.489	5.78	6.086	5.36	5.20
Deviation						
Cal Gas #2	2.35	2.36	5.77	5.88	5.67	5.55
Deviation						
Cal Gas #3	7.68	7.68	19.28	19.86	17.47	17.16
Deviation						
Average Deviation						

Manufacturer: Morso  
 Project No: 31222  
 Model: 3410  
 Date: 07/14/00

	CO		CO2		O2	
	Actual	Should be	Actual	Should be	Actual	Should be
Zero Gas	0	0	0	0	0	0
Span Gas	9.99	9.99	24.63	24.65	20.93	20.93
Cal GAS #1 Deviation	2.34	2.489 5.99%	5.78	6.086 5.03%	5.36	5.2 3.08%
Cal GAS #2 Deviation	2.35	2.36 0.42%	5.77	5.88 1.87%	5.67	5.55 2.16%
Cal GAS #3 Deviation	7.68	7.68 0.00%	19.28	19.86 2.92%	17.47	17.16 1.81%
Average Deviation		2.14%		3.27%		2.35%

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# FE 500

DESCRIPTION: THERMOCOUPLES

MANUFACTURER: OMEGA

SERIAL #: \_\_\_\_\_ MODEL: \_\_\_\_\_

EQUIPMENT LOCATION: E+E LAB

PURPOSE & ACCURACY: \_\_\_\_\_ 6 mos.

CALIBRATION SPECIFICATIONS/INTERVAL: BOILING WATER ICE BATH 6 MONTHS

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
6-4-97	12-4-97	IN HOUSE	RA	
12-12-97	6-12-98	"	RA	
6-26/98	12-26-98	"	WK	
12-11-98	6-11-99	"	RA	
6/1/99	12/1/99	"	RA	
5/30/00	11/30/00			

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 5-30-08  
REVIEWED BY: GAT

CALIBRATED BY: RA

ITS # 500

ROOM TEMPERATURE 69

Thermocouple number and location	Thermocouple immersed in boiling water	Thermocouple immersed in ice bath
1) Flue Gas	211	32
2) Room Temperature	211	32
3) Dry Bulb (in tunnel)	211	32
4) Wet Bulb (in tunnel)	211	32
5) Unit Top	211	32
6) Unit Back	211	32
7) Unit Right Side	211	32
8) Unit Left Side	211	32
9) Unit Bottom	211	32
10) Catalyst Downstream	211	32
11) Catalyst Center	211	32
12)	211	32
13)	211	32
14)	212	32
15)	212	33
16)	211	33
17) DGM (in)	212	33
18) DGM (out)	212	33
19) Filter (1)	212	33
20) DGM (in)	212	33
21) DGM (out)	212	33
22) Filter (2)	212	33



ITS EQUIPMENT CALIBRATION RECORD

ITS# 8 v 259

DESCRIPTION: Weigh

MANUFACTURER: Tronix

SERIAL #: <sup>(6)</sup>(8) 6800082 <sup>(25)</sup>(259) 03082 MODEL: <sup>(8)</sup>NCI 5780 <sup>(259)</sup>WI 110

EQUIPMENT LOCATION: \_\_\_\_\_

PURPOSE & ACCURACY: .1 lb

CALIBRATION SPECIFICATIONS/INTERVAL: 6 Months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
8-11-98	2-11-99	In-house	RA	
5-19-98	11-19-98	Cream City	-	
11-98	5-99	CREAM CITY	JEFF	
5/21/99	11/21/99	" "	CC	
11/99	5/00	Cream City	Jeff	
3/00	9/00	" "	"	<del>Big sub only</del>

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

#6

# Certificate of Calibration CREAM CITY SCALE, CO INC.

2009 S. Stoughton Rd., Madison, WI 53716 (608) 222-9427 or (888) 934-4448

CUSTOMER LTC.  
ADDRESS \_\_\_\_\_  
CITY, STATE & ZIP Middleton

DATE 3/00  
GLA

INDICATOR MFG.	<u>GSE</u>	CAPACITY	<u>100</u>	CLASS	<u>III</u>
MODEL	<u>450</u>	DIVISIONS	<u>.01CB</u>	ACCURACY	<u>1%</u>
SERIAL NO.	<u>101722</u>	LOCATION	<u>E+E LAB</u>	TOLERANCES USED	
BASE MFG.	<u>NCJ</u>	I.D. #			<u>H649</u>
MODEL	<u>320</u>	CALIBRATION INTERVAL			<u>Semi Annual</u>
SERIAL NO.	<u>79043</u>	NEXT CALIBRATION DUE			<u>9/00</u>

### SHIFT TEST

#### FLOOR SCALE

#### BENCH SCALE

1	2
4	3

2	
1	3
4	

SECTION	LOAD	READING	ERROR
1	25.00	25.00	0
2	25.00	25.00	0
3	25.00	25.00	0
4	25.00	25.00	0

IS SHIFT TEST WITHIN TOLERANCE (  ) YES ( ) NO ( ) ADJUSTED

### INCREASING LOAD TEST

#### PRELIMINARY LOAD TEST

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR
	5.00	5.00	0
	10.00	10.00	0
	15.00	15.00	0
	20.00	20.00	0
	25.00	25.00	0
	30.00	30.00	0

#### FINAL LOAD TEST AFTER ADJUSTMENT

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR

IS SCALE WITHIN MAINTENANCE TOLERANCE (  ) Y ( ) N  
(if no, see final load test)

IS SCALE WITHIN ACCEPTANCE TOLERANCE ( ) Y ( ) N

WAS SCALE WITHIN CUSTOMERS REQUIRED ACCURACY? (  ) Y ( ) N

COMMENTS:

TEST WEIGHT CLASSIFICATION F  
 NIST TRACEABILITY CERTIFICATE NO. 098-206  
 LIST TEST WEIGHTS USED BY SERIAL NO. KIT 5

SCALES WERE CALIBRATED WITH THE CERTIFIED TEST WEIGHTS, ADJUSTMENTS TO RESTORE AND/OR MAINTAIN THE ACCURACY OF THE SCALE CONFORM TO THE TOLERANCES ESTABLISHED BY THE NATIONAL INSTITUTE OF STANDARDS & TECHNOLOGY AS SPECIFIED IN HANDBOOK 44.

TECHNICIAN Jeff Roy

**HORIBA** FIELD SERVICE REPORT

421407

PAGE \_\_\_ OF \_\_\_

<b>SERVICE LOCATION</b>		<b>INVOICE TO</b> CUST. NO:		DATE STARTED <i>4/27</i>	
INSTITUTION NAME <i>TERTER TESTING SERV.</i>		INSTITUTION NAME		CALL COMPLETE <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	
STREET ADDRESS <i>8431 MURPHY DR.</i>		STREET ADDRESS		PRODUCT CODE <i>PIR-2000</i>	
CITY COUNTY/PARISH <i>MIDDLETON</i>		CITY STATE ZIP		PRODUCT SER. # AND MFG. DATE <i>606026 1986</i>	
STATE ZIP <i>WISCONSIN 53562</i>		ATTENTION		SYSTEM PRODUCT CODE <i>0-11.3/5%CO</i>	
DEPT/BLDG/LOCATION <i>direct/608/824-7421</i>		TAX NUMBER (IF EXEMPT)		SYSTEM SER. # AND MFG. DATE	
INDIVIDUAL'S NAME <i>BILL KEEN</i>		P.O. NUMBER <i>29257</i>		CHARGE <input checked="" type="checkbox"/> CS <input type="checkbox"/> POL <input type="checkbox"/> WAR TYPE <input type="checkbox"/> IN <input type="checkbox"/> CO	
TELEPHONE NUMBER <i>(608) 836-4400 x421</i>		AUTHORIZED BY <i>HEATHER ROBINSON</i>		CONTRACT # TYPE: <input type="checkbox"/> CO <input type="checkbox"/> DEMAND	

ANALYSIS OF PROBLEM: *Will ZERO & SPAN, but doesn't read correctly sample. Intermittent problem - (modifying ON and OFF again & took time different results)*

- replaced BPA bd.

- repaired the mother bd. (power supply part; trays; soldering connectors)

- repaired the NOR-44 bd. (replaced 3-PIN & 6-PIN connectors)

- cleaned the optical bank (sample cell windows)

- cleaned the solid fibers w. spacers (there has been brown powder-like build-up)

- done optical alignment; linearization (new curve)

- tested and verified linearity => repeatability <math>\leq 0.5\% F.S.</math>

- lead test passed - O.K.

**MATERIAL AND OUTSIDE SERVICES**

ITEM	PART NUMBER	DESCRIPTION	QTY.	UNIT COST	TOTAL	CHG
01	352194	PCB, BPA (60Hz)	1	132.00	132.00	
02	NXPV	3-PIN CONNECTOR	1	12.00	12.00	
03	NXPV	6-PIN CONNECTOR	1	18.00	18.00	

**SERVICE LABOR**

**EXPENSES**

DATE	TYPE	HOURS	RATE	TOTAL	CHG	FIXED COST CONTRACT PRICE
4/27	L	1.0	120.00			AUTO MILES AT \$
4/28	L	3.5	420.00			PHONE
5/1	L	3.5	420.00			LODGING
						MEALS
						AUTO/TAXI/FUEL/PARKING/TOLLS
						OUTSIDE SERVICES
						AIRFARE & TRAVEL EXPENSES
						SUBTOTAL
						SALES TAX AT %
						FREIGHT AND INSURANCE
						TOTAL CHARGES

1,092.00

CUSTOMER SIGNATURE		DATE	SERVICE REPRESENTATIVE <i>JERRY BEDNAR</i>		EMPLOYEE NO. <i>274</i>
CARRIER <i>UPS</i>	PRIORITY <i>NEXT DAY</i>	WAYBILL NO.		SHIPPER NO. <i>66449</i>	

# NTEP CERTIFICATE OF CONFORMANCE CALIBRATION DATA

**MODEL:** 60001A300-1138  
**CAP:** 300 lbs  
**FSO:** 3.569 mV/V  
**CERT#:** 86-043  
**DATE:** 4/7/99  
  
**S/N:** 868456

*BIG SCALE*

Class III/ Single LC	Divisions 10000
Vmin 0.012LB	Min. Dead Load 6.0LB
Compensated Temp. 14 to 104 DegF	
Safe Overload 150 % of Capacity	
	Rated Excitation 10 Vdc
	Input Resistance 380 Ohms
	Output Resistance 350 Ohms
Barometric Effect Nil	Insulation Res > 1000 MOhms @ 50 Vdc

### WIRING CODE

- + Excitation: Red
- Excitation: Black
- Shield: Orange
- + Output: Green
- Output: White

Data obtained utilizing standards traceable to the National Institute of Technology.



IS CL I,II,III; DIV 1, GP A-G, NI CL 1; DIV 2, GP A-D  
 S CL II, III DIV 2, GP F&G. HAZ LOC. TEMP CODE: T4  
 OPERATING TEMP: 0 TO 150F  
 ENTITY PARAM: Vmax = 30V, Imax = 600mA, Ci = 0uF, Li = 0Mh  
 WHEN INSTALLED PER DWG: 20038

Approved

*Michael J. Maksim*  
 Q.A. Approval



# Certificate of Calibration CREAM CITY SCALE, CO INC.

2009 S. Stoughton Rd., Madison, WI 53716 (608) 222-9427 or (888) 934-4448

CUSTOMER I.T.S. DATE 3-20  
 ADDRESS \_\_\_\_\_  
 CITY, STATE & ZIP Madison

INDICATOR MFG. <u>WATTS</u>	CAPACITY <u>100 LB</u>	CLASS <u>III</u>
MODEL <u>WI110</u>	DIVISIONS <u>.1 LB</u>	ACCURACY <u>1%</u>
SERIAL NO. _____	LOCATION _____	TOLERANCES USED _____
BASE MFG. <u>Teledu</u>	I.D. # _____	<u>HB94</u>
MODEL <u>Dumont</u>	CALIBRATION INTERVAL <u>6 mo</u>	
SERIAL NO. <u>N/A</u>	NEXT CALIBRATION DUE <u>9-20</u>	

### SHIFT TEST

#### FLOOR SCALE

#### BENCH SCALE

1	2
4	3

2	3
1	4

SECTION	LOAD	READING	ERROR
1	500.0	500.0	0
2	500.0	500.0	0
3	500.0	500.0	0
4	500.0	500.0	0

IS SHIFT TEST WITHIN TOLERANCE (  ) YES (  ) NO (  ) ADJUSTED

### INCREASING LOAD TEST

#### PRELIMINARY LOAD TEST

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR
	100.0	100.0	0
	200.0	200.0	0
	300.0	300.0	0
	400.0	400.0	0
	500.0	500.0	0
	700.0	700.0	0
	900.0	900.0	0
	1000.0	1000.0	0

#### FINAL LOAD TEST AFTER ADJUSTMENT

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR

IS SCALE WITHIN MAINTENANCE TOLERANCE (  ) Y (  ) N  
(if no, see final load test)


IS SCALE WITHIN ACCEPTANCE TOLERANCE (  ) Y (  ) N

WAS SCALE WITHIN CUSTOMERS REQUIRED ACCURACY? (  ) Y (  ) N

COMMENTS: Replaced load cell

TEST WEIGHT CLASSIFICATION F  
 NIST TRACEABILITY CERTIFICATE NO. 478-206  
 LIST TEST WEIGHTS USED BY SERIAL NO. 71-80 + m685

SCALES WERE CALIBRATED WITH THE CERTIFIED TEST WEIGHTS, ADJUSTMENTS TO RESTORE AND/OR MAINTAIN THE ACCURACY OF THE SCALE CONFORM TO THE TOLERANCES ESTABLISHED BY THE NATIONAL INSTITUTE OF STANDARDS & TECHNOLOGY AS SPECIFIED IN HANDBOOK 44.

TECHNICIAN 

# CREAM CITY SCALE *LLC*

## STATELINE

2009 S. STOUGHTON RD., MADISON, WISCONSIN 53716 PHONE 608/222-9427  
 10350 N. SECOND ST. (HWY. 251), ROCKFORD, ILLINOIS 61115 PHONE 815/654-1055  
 www.creamcityscale.com


Initiated By \_\_\_\_\_  
 Date Initiated \_\_\_\_\_  
 Date Promised \_\_\_\_\_

### SERVICE REPORT

CUSTOMER <u>I.S.S.</u>	JOB NO.
ADDRESS	PURCHASE ORDER NO.
CITY / STATE / ZIP <u>Madison</u>	PHONE <u>608/222-9427</u>
SPECIAL INSTRUCTIONS	MECHANIC SHOULD SEE

SERVICE REQUESTED  CONTRACT  REG. SERVICE  OVERTIME  PARTS ORDER

WORK REQUESTED



WORK PERFORMED

Replaced load cell  
on Under Drum 4v9

cal test OK

See calibration cert.

Equipment Disposition: paired Calibrated Reject - Parts To Customer Reject - Scrap@CCS Confirmed w/ \_\_\_\_\_ Other: \_\_\_\_\_

PARTS USED	QTY.	PART NO. / LOCATION #	DESCRIPTION	PRICE
	1			Shovel 60001A 30-1128
			#1 850956	
			2nd Shovel	
			TOTAL PARTS	

THIS SERVICE AS DESCRIBED HAS BEEN RECEIVED

[Signature]  
 CUSTOMER'S SIGNATURE

X 5/24/08  
 DATE

[Signature]  
 TECHNICIAN

FOR OFFICE USE ONLY

COUNTY \_\_\_\_\_ @ \_\_\_\_\_

RH \_\_\_\_\_ @ \_\_\_\_\_

OT \_\_\_\_\_ @ \_\_\_\_\_

SHOP \_\_\_\_\_ @ \_\_\_\_\_

OTHER \_\_\_\_\_ @ \_\_\_\_\_

TAX RATE \_\_\_\_\_

TOTAL \_\_\_\_\_

# CREAM CITY SCALE *L.L.C.*

## STATELINE

2009 S. STOUGHTON RD., MADISON, WISCONSIN 53716 PHONE 608/222-9427  
 10350 N. SECOND ST. (HWY. 251), ROCKFORD, ILLINOIS 61115 PHONE 815/654-1055  
 www.creamcityscale.com


Initiated By \_\_\_\_\_  
 Date Initiated \_\_\_\_\_  
 Date Promised \_\_\_\_\_

### SERVICE REPORT

CUSTOMER <b>ITS</b>	JOB NO.
ADDRESS	PURCHASE ORDER NO.
CITY / STATE / ZIP <b>Madison</b>	PHONE
SPECIAL INSTRUCTIONS	WORK REQUESTED BY
	MECHANIC SHOULD SEE

SERVICE REQUESTED  CONTRACT  REG. SERVICE  OVERTIME  PARTS ORDER

WORK REQUESTED



WORK PERFORMED

*Delivered & set up Digital 4x9  
 Scale # 93211198 - 10/2011 # 521311  
 100 x 1 - calibration to parts  
 Sent out at 12:30P.*

Equipment Disposition:  Repaired  Calibrated  Reject - Parts To Customer  Reject - Scrap@CCS Confirmed w/ \_\_\_\_\_  Other: \_\_\_\_\_

PARTS USED	QTY.	PART NO./LOCATION #	DESCRIPTION	PRICE
			TOTAL PARTS	

THIS SERVICE AS DESCRIBED HAS BEEN RECEIVED  CUSTOMER'S SIGNATURE X <i>1/20/12</i> DATE  TECHNICIAN	COUNTY _____ @ _____		
	RH _____ @ _____		
	OT _____ @ _____		
	SHOP _____ @ _____		
	OTHER _____ @ _____		
	TAX RATE _____		TOTAL

#25

# Certificate of Calibration CREAM CITY SCALE, CO INC.

2009 S. Stoughton Rd., Madison, WI 53716 (608) 222-9427 or (888) 934-4448

CUSTOMER I.T.S.  
ADDRESS 8431 Murphy DR  
CITY, STATE & ZIP Middleton WI 53562

DATE 11/99

INDICATOR MFG. <u>Weightronix</u>	CAPACITY <u>980#</u>	CLASS <u>TII</u>
MODEL <u>WI 110</u>	DIVISIONS <u>.1</u>	ACCURACY <u>1%</u>
SERIAL NO. <u>30821</u>	LOCATION <u>E+E</u>	TOLERANCES USED <u></u>
BASE MFG. <u>Toledo</u>	I.D. # <u>259</u>	<u>HB 94</u>
MODEL <u>Durmant</u>	CALIBRATION INTERVAL <u>Semi Annual</u>	
SERIAL NO. <u>N/A</u>	NEXT CALIBRATION DUE <u>5/00</u>	

### SHIFT TEST

#### FLOOR SCALE

1	2
4	3

#### BENCH SCALE

1	2	3
	4	

SECTION	LOAD	READING	ERROR
1	50.0	50.0	0
2	50.0	50.0	0
3	50.0	50.0	0
4	50.0	50.0	0

IS SHIFT TEST WITHIN TOLERANCE (  ) YES ( ) NO ( ) ADJUSTED

### INCREASING LOAD TEST

#### PRELIMINARY LOAD TEST

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR
	50.0	50.0	0
	100.0	100.0	0
	200.0	200.0	0
	400.0	400.0	0
	600.0	600.0	0
	800.0	800.0	0
	900.0	900.0	0

#### FINAL LOAD TEST AFTER ADJUSTMENT

SUBSTITUTION WEIGHT	TEST WEIGHT	READING	ERROR

IS SCALE WITHIN MAINTENANCE TOLERANCE (  ) Y ( ) N  
(if no, see final load test)

IS SCALE WITHIN ACCEPTANCE TOLERANCE ( ) Y ( ) N

WAS SCALE WITHIN CUSTOMERS REQUIRED ACCURACY? (  ) Y ( ) N

COMMENTS:

TEST WEIGHT CLASSIFICATION F

NIST TRACEABILITY CERTIFICATE NO. 4198-206

LIST TEST WEIGHTS USED BY SERIAL NO. 71, 72, 73, 74, 75, 76, 77, 78, m 689

SCALES WERE CALIBRATED WITH THE CERTIFIED TEST WEIGHTS, ADJUSTMENTS TO RESTORE AND/OR MAINTAIN THE ACCURACY OF THE SCALE CONFORM TO THE TOLERANCES ESTABLISHED BY THE NATIONAL INSTITUTE OF STANDARDS & TECHNOLOGY AS SPECIFIED IN HANDBOOK 44.

TECHNICIAN [Signature]



# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 5-15-00  
REVIEWED BY: \_\_\_\_\_

CALIBRATED BY: RA

DESCRIPTION: Readout/75 lb Scale

MODEL: NCI 5780

SERIAL NUMBER: G800082

WHI INVENTORY #008

WEIGHT APPLIED

READING

5 lbs.

5.00 lbs.

10 lbs.

10.00 lbs.

15 lbs.

15.00 lbs.

THIS IS CALIBRATED BY  
CREAM CITY SCALE  
THIS SHEET REALLY  
ISN'T NECESSARY

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# #9, 10, 11

DESCRIPTION: CO, CO<sub>2</sub>, O<sub>2</sub> Analyzers

MANUFACTURER: Aloriba & Beckman

SERIAL #: CO PIR-2000 <sup>#9</sup> 6110019      MODEL: CO<sub>2</sub> PIR-2000 <sup>#10</sup> 607023      O<sub>2</sub> 755 <sup>#11</sup> 1001926

EQUIPMENT LOCATION: \_\_\_\_\_

PURPOSE & ACCURACY: ± 1% of FS

CALIBRATION SPECIFICATIONS/INTERVAL: 6 mos.

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
<u>7/16/99</u>	<u>1/16/00</u>	<u>In house</u>	<u>RA</u>	
<u>1/17/00</u>	<u>7/17/00</u>	<u>"</u>	<u>RA</u>	

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 1-17-00 CALIBRATED BY: RA  
REVIEWED BY: [Signature]

DESCRIPTION: Gas Analyzers  
Located in EE console

SERIAL NUMBER: 6110019 CO  
SERIAL NUMBER: 607023 CO<sub>2</sub>  
SERIAL NUMBER: 1001926 O<sub>2</sub>

WHI INVENTORY #009  
WHI INVENTORY #010  
WHI INVENTORY #011

## GAS ANALYZER RESPONSE TIME CALIBRATION GAS USED

	CO	CO <sub>2</sub>	O <sub>2</sub>
Analysis:	<u>.991</u>	<u>10.02</u>	<u>10.01</u>
Meter Reading			
Direct Connection:	<u>.98</u>	<u>9.74</u>	<u>10.08</u>
90% of Analysis:	<u>.892</u> <del>.991</del> RA	<u>9.02</u>	<u>9.01</u>

- Meters set with zero gas and span gas.
- Calibration gas routed through impinger train.
- Zero gas was introduced after each time trial to return meter to zero.

CO	90% ( <u>.892</u> )	Trial	Time	100% ( <u>.95</u> )	Trial	Time
		1.	<u>5</u> sec		1.	<u>11</u> sec
		2.	<u>5</u> sec		2.	<u>10</u> sec
		3.	<u>5</u> sec		3.	<u>10</u> sec
		Average	<u>5</u> sec		Average	<u>10.33</u> sec

CO <sub>2</sub>	90% ( <u>9.02</u> )	Trial	Time	100% ( <u>9.43</u> )	Trial	Time
		1.	<u>5</u> sec		1.	<u>11</u> sec
		2.	<u>5</u> sec		2.	<u>11</u> sec
		3.	<u>6</u> sec		3.	<u>11</u> sec
		Average	<u>5.33</u> sec		Average	<u>11</u> sec

O <sub>2</sub>	90% ( <u>9.01</u> )	Trial	Time	100% ( <u>10.16</u> )	Trial	Time
		1.	<u>14</u> sec		1.	<u>30</u> sec
		2.	<u>16</u> sec		2.	<u>30</u> sec
		3.	<u>16</u> sec		3.	<u>32</u> sec
		Average	<u>15.33</u> sec		Average	<u>30.67</u> sec

EQUIPMENT CALIBRATION RECORD  
 WARNOCK HERSEY, INC.  
 MIDDLETON, WISCONSIN 53562

A. IDENTIFICATION:

1. TYPE AND MODEL DESIGNATION - Dry Gas Meter Calibration

2. MANUFACTURER/SUPPLIER -  
 ① Rockwell T-110 #26866 WHI #12  
 ② Rockwell T-110 #26873 WHI #13  
 ③ Rockwell T-110 #27002 WHI #14

3. SERIAL NO./WH DESIGNATION NO. \_\_\_\_\_

B. EQUIPMENT LOCATION:

1. PURPOSE & ACCURACY - ±.05 CFH

2. CALIBRATION INTERVAL - 6 months

C. CALIBRATIONS: DONE BY- \_\_\_\_\_

CALIBRATION DATE	CALIBRATION DUE NEXT	CALIBRATION AGENCY	ACCEP	CALIBRATION RESULTS ADJUSTMENTS REQUIRED
1/3/96	7/3/96	Inhouse	By	
7/9/96	1/9/97	Inhouse	By	
12-4-96	6-4-97	Inhouse	RA	
6-2-97	12-2-97	"	RA	
12/12/97	6/12/98	"	RA	
6/22/98	12/22/98	"	WK	
1/19/99	7/19/99	"	RA	
5/3/99	11/3/99	MG + E	-	
1/12/00	7/12/00	In-house	RA	

D. MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR OR MAINTENANCE

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# 12, 13, 14

DESCRIPTION: Dry Gas Meter Calibration

MANUFACTURER: ① Rockwell T-110 #26860 #12

SERIAL #: ② Rockwell T-110 #26873 #13

MODEL: ③ Rockwell T-110 #27892 #14

EQUIPMENT LOCATION: E + E

PURPOSE & ACCURACY: ± .05 CFH

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

SPIROMETER									
1.003									
Inventory Number 14									
Meter Number 13									
Meter Number									
29.1									
Barometer:									
29.1									
Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
294.005	29.22	66	0.6380	65.5	0.47	23.03125	1.0469	295.005	1.0230
295.005	29.19	65	0.6160	65.5	0.47	23.125	1.0511	296.008	1.0269
296.008	29.19	66.5	0.6495	65	0.47	23.5625	1.0710	297.032	1.0197
298.083	29.19	66	0.6380	65.5	0.47	22.9375	1.0426	299.082	1.0199
299.3225	29.19	66	0.6380	65	0.47	23.125	1.0511	300.328	1.0206
300.328	29.19	65	0.6160	65	0.47	22.875	1.0398	301.329	1.0168
AVERAGE 1.0212									
Inventory Number 12									
Meter Number 1									
Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
902.825	29.22	66	0.6380	68	0.47	23.03125	1.0469	903.833	1.0198
903.833	29.19	65	0.6160	68.5	0.47	23.125	1.0511	904.848	1.0205
904.848	29.19	66.5	0.6495	69	0.47	23.5625	1.0710	905.893	1.0069
AVERAGE 1.0157									
Inventory Number 13									
Meter Number 2									
Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
283.205	29.19	66	0.6380	67	0.47	22.9375	1.0426	284.197	1.0300
284.436	29.19	66	0.6380	67	0.47	23.125	1.0511	285.428	1.0384
285.428	29.19	65	0.6160	67	0.47	22.875	1.0398	286.4105	1.0399
AVERAGE 1.0361									



Manufacturer ROCKWELL Page      of       
 Job #      Run      Tech RA Date 1-12-99  
 Model T110

### SPIROMETER (Six Month Dry Gas Meter Calibration)

Meter Number 3 Inventory Number 014 1.0469

Run Number	Meter Initial	Barometric Pressure	Spirometer Temperature	Vapor Press (H2O)	Meter Temperature	Meter Pressure	Measurement Inches	Spirometer Volume	Meter Final	Y
1	294.005	29.72	66	.6380	65.5	.47	23.03125	295.005	295.005	1.0230
2	295.005	29.19	65	.6160	65.5	.47	23.125	296.000	296.008	1.0269
3	296.008	29.19	66.5	.6495	65	.47	23.5625	1.0710	297.032	1.0197
4	298.083	29.19	66	<del>1.6380</del>	65.5	.47	22.9375	1.0426	299.082	1.0195
5	<del>299.082</del>	29.19	66	.6380	65	.47	23.125	1.0511	300.328	1.0201
6	300.328	29.19	65	.6160	65	.47	22.875	1.0398	301.329	1.0168
7										
									AVERAGE	1.0212

Meter Number 1 Inventory Number 012 1.0469

1	902.825	29.22	66	.6380	68	.47	23.03125	903.833	903.833	1.0198
2	903.833	29.19	65	.6160	68.5	.47	23.125	1.0511	904.848	1.0208
3	907.878	29.19	64.5	.6495	69	.47	23.5625	1.0710	905.893	1.0069
									AVERAGE	1.0157

Meter Number 2 Inventory Number 013

1	283.205	29.19	66	.6380	67	.47	22.9375	1.0426	284.197	1.0300
2	<del>284.197</del>	29.19	66	.6380	67	.47	23.125	1.0511	300.285428	1.0387
3	285.428	29.19	65	.6160	67	.47	22.875	1.0398	286.4105	1.0399
									AVERAGE	1.0361

$$Y = \left[ \frac{V_{SPR}}{MR} \right] \left[ 1 - \frac{P_{H2O}}{P_{BAR}} \right] \left[ \frac{T_M + 460}{T_{SPR} + 460} \right]$$

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# 021

DESCRIPTION: Alnor Velometer

MANUFACTURER: Alnor

SERIAL #: MD1057 MODEL: 8525

EQUIPMENT LOCATION: E+E Calibrated - In-house

PURPOSE & ACCURACY: ± 3% - 75-79° / ± 4% - 68-86° / ± 9% - 32-122°

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
10-30-96	4-30-97	Alnor Instruments		Was broken - repaired 10/96
12-4-96	6-4-97	In-house	RA	
6-2-97	12-2-97	"	RA	
12/12/97	6/12/98	"	RA	
8/11/98	2/11/99	"	RA	
1-22-99	7-22-99	"	RA	
7/16/99	1/16/00	"	RA	
1/14/00	7/14/00	"	RA	

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR



# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 1-14-00  
 REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: Alnor Hot Wire Anemometer  
 Located in EE lab

MODEL: 8525

SERIAL NUMBER: MD 1057

WHI INVENTORY #021

## PITOT TUBE IN TUNNEL CENTER.

Barometric Pressure:

Manometer Reading	Tunnel Temp	Static Pressure	Velocity ft/sec	ft/min	Velometer ft/min	Deviation
.056	69	.168	15.89	953.1	810	15.02%
.041	68	.111	13.57	814.0	730	10.32%
.026	68	.084	10.80	647.9	640	1.22%
.115	66	.353	22.77	1366.3	1170	14.37
.262	66	.8	34.64	2078.2	1750	15.79
.28	66	.89	35.82	2151.8	1840	14.49

AVG. DEV 11.87%

$K_p = 85.49$   
 $C_p = .99$   
 $T_s = ^\circ F + 460$   
 $P_s = P_{Bar} + (P_g \text{ (static)})$  (a negative number)  
 $M_s = 28.56$

$$V_s = K_{pCp(AP)} \sqrt{\frac{T_s}{P_s + M_g}}$$

Excel program is located: K:\groups\test\dept\misc\ee\calibrat\velomete

3/24/99

Cal-lab cannot do this.

Next date due is 7/22/99

We should send back to ALNOR  
prior to this date to have it  
serviced/calibrated by them.

~~EAH~~

#21

April 26, 1999

**Service Bulletin**

Subject: Repair obsolescence of some models of 8500 and 8525

Some previously discontinued thermal anemometers from Alnor are now no longer serviceable at our factory.

These include:      All models Compuflow 8500DI  
                         All models CompuFlow 8500 DII  
                         Some models of Compuflow 8525 identified as stated  
                         below.

Alnor is offering several options for the owners of these products.

1. While parts last, upgrade of the 8525, price \$370 (allows continuing calibration or service life).
2. Purchase of new Compuflow 8570 at 10% discount.

Identification of unserviceable 8525 units:

Open the battery compartment: If you can see a set of 2 white switches in a red plastic surround next to the battery connector, the unit can be serviced. If you cannot, the unit cannot be serviced or re-calibrated.

Please call Alnor Customer Service at 1-800-424-7427 for more information

at1-39

5/99 -

Will calibrate in-house until the unit is no longer calibratable in-house - Will then purchase new one.

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# 22

DESCRIPTION: Manometer 0-1" Inclined

MANUFACTURER: \_\_\_\_\_

SERIAL #: 882 MODEL: 125AV

EQUIPMENT LOCATION: Emissions Lab - E+E

PURPOSE & ACCURACY: ± 1% of FS (0.01 in)

CALIBRATION SPECIFICATIONS/INTERVAL: 6 mos. Yearly

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
3/17/94	9/17/94	Inhouse	WK	
10/1/94	4/1/95	"	WK	
4/11/95	10/11/95	"	RA	
10/16/95	4/16/96	"	RA	
4/19/96	10/19/96	"	WK	
10/9/96	4/9/97	"	RB	
5/14/97	11/14/97	"	RA	
12/16/97	6/16/98	"	RA	
8/12/98	2/12/99	"	RA	
1-22-99	7-22-99	"	RA	
7/16/99	1/16/00	"	RA	
1/14/00	7/14/00	"	RA	

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 6/14/00  
REVIEWED BY: [Signature]

CALIBRATED BY: R4

DESCRIPTION: Manometer Inclined 0-1"  
Located in EE lab

MODEL: 125 AV

SERIAL NUMBER: 8 82

WHI INVENTORY #022

CHANGE THIS TO  
1 TIME PER YEAR

MICROTECTOR	MANOMETER	DEVIATION IN.
.022	.034	.002
.051	.084	.018
.086	.166	.006
.113	.214	.012
.138	.262	.014
.165	.317	.013
.191	.364	.018
.239	.462	.016

AVERAGE DEVIATION = .0124 INCHES

Note: Microtector reading is exactly 1/2 of the manometer reading

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# 28

DESCRIPTION: Analytical Balance

MANUFACTURER: Ohaus

SERIAL #: 5336 MODEL: G110

EQUIPMENT LOCATION: E & E

PURPOSE & ACCURACY: ±.0001

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
6-2-97	12-2-97	In-house	RA	
6/25/98	12-25-98	"	WK	
12/11/98	6/11/99	"	RA	
6/1/99	12/1/99	"	RA	
1/14/00	7/14/00	"	RA	

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 1-14-00  
REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: Analytical Balance

MODEL: (Ohaus) Galaxy 110

SERIAL NUMBER: 5336

WHI INVENTORY #028

Ainsworth Class S Weight

WEIGHT	MEASURED	DEVIATION (g)
2 mg		
5 mg	.00506 5 mg	0
10 mg	.0099 G	.0001
20 mg	0200 G	0
50 mg	.05016	.0001
100 mg	.1001 G	.0001
1 g	.9998 G	.0002
20 g	20.0003	.0003
50 g	50.0002	.0002
100 g	100.0001	.0001

AVERAGE DEVIATION = .0002 grams

ITS EQUIPMENT CALIBRATION RECORD

ITS# 54

DESCRIPTION: Digital Type K Thermocouple Meter

MANUFACTURER: Omega

SERIAL #: 21662 MODEL: 199-KF-A-X

EQUIPMENT LOCATION: E+E

PURPOSE & ACCURACY:  ~~$\pm 1^\circ F$~~   $\pm 2^\circ F$  (with)

CALIBRATION SPECIFICATIONS/INTERVAL: 6 months

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
12/11/98	6/11/99	In house	RA	
6/11/99	12/11/99	"	RA	
1/14/00	7/14/00	"	RA	
5/24/00	11/24/00	Cal Lab		Cal Lab

MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR





# CERTIFICATE OF CALIBRATION

Cert. No. 1045166



Customer

Intertek Testing Services  
8431 Murphy Dr.  
Middleton, WI 53562

Equipment

Manufact:Omega  
Model #:199  
Descript:Digital Temp. Meter  
Serial #:NONE  
I.D. #:54

Calibration Interval: 12 month

Calibration Date: 05/24/2000

Recalibration Date: 05/24/2001

Test Conditions: Temperature: 71°F Humidity:57% Technician:Sara Cullum Calibrated On-site

Received Condition: Fully operational and within tolerance

Work Performed: No adjustments required and calibrated to manufacturers specifications using manufacturers procedure

Standards Used

Cal:01/27/2000 Due:01/31/2001 ID#1390 Fluke 743B Process Calibrator Serial#7005629

This instrument was calibrated with a minimum 4:1 TUR/TAR unless otherwise stated. These represent best uncertainties. Actual uncertainties are available upon request. CAL LAB Co., Inc. is accredited to ISO Guide 25 by A2LA.

Best Measurement Uncertainty

Temperature ±0.2°C

Reviewed and approved by

Quality Team Member - Issue Date: 05/26/2000

This Certificate may not be reproduced except in its entirety without the written approval of CAL LAB Co., Inc.

***This Report Certifies that all Calibration Equipment used in the test is traceable to the NIST, and the test was performed in accordance to ANSI/NCSL Z540-1-1994 (FORMERLY MIL-STD 45662A)***

17035 Westview Ave.  
South Holland, IL 60473

CAL LAB Co. Inc.  
800-373-1759

3695-K North 126th Street  
Brookfield, WI 53005

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# 56

DESCRIPTION: Chart Recorder

MANUFACTURER: Cole Parmer

SERIAL #: 221068 MODEL: 8376-XX

EQUIPMENT LOCATION: E & E

PURPOSE & ACCURACY: ±0.2°C

CALIBRATION SPECIFICATIONS/INTERVAL: 1 yr.

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
<u>11/24/98</u>	<u>11/24/99</u>	<u>Cal Lab</u>		
<u>11/22/99</u>	<u>11/22/00</u>	<u>"</u>		

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR



# CERTIFICATE OF CALIBRATION

Cert. No. 1041317

*GH*



Customer

Intertek Testing Services  
8431 Murphy Dr.  
Middleton, WI 53562

Equipment

Manufact: Cole Parmer  
Descript: Chart Recorder  
Model #: 8376-XX  
Serial #: 221068  
I.D. #: 000056

Calibration Date: 11/22/1999

Recalibration Date: 11/22/2000

Received Condition: Fully operational and within tolerance

Work Performed: No adjustments required and calibrated to manufacturers specifications using  
manufacturers procedure

Test Conditions: Temperature: 68°F Humidity: 45% Technician: Jim Goff On site

Standards Used

1239 Datron 4800 Multifunction Calibrator 01/31/2000

1390 Fluke 7438 Process Calibrator 01/31/2000

This instrument was calibrated with a minimum 4:1 TUR/TAR unless otherwise stated. These represent best uncertainties. Actual uncertainties are available upon request.

Best Measurement Uncertainty

DC Voltage  $\pm 8.5$ ppm

Temperature  $\pm 0.2$ °C

Reviewed and approved by  
Issue Date: 11/23/1999

*Mike Boothe*  
Quality Team Member

This Certificate may not be reproduced except in its entirety without the written approval of CAL LAB Co., Inc.

**This Report Certifies that all Calibration Equipment used in the test is traceable to the NIST, and the test was performed in accordance to ANSI/NCSL Z540-1-1994 (FORMERLY MIL-STD 45662A)**

17035 Westview Ave.  
South Holland, IL 60473

CAL LAB Co. Inc.  
800-373-1759

3695-K North 126th Street  
Brookfield, WI 53005

EQUIPMENT CALIBRATION RECORD  
 WARNOCK HERSEY, INC.  
 MIDDLETON, WISCONSIN 53562

#93

A. IDENTIFICATION:

1. TYPE AND MODEL DESIGNATION - Magnebelic 2000-00C
2. MANUFACTURER/SUPPLIER - Dwyer
3. SERIAL NO./WH DESIGNATION NO. R60825-m39

B. EQUIPMENT LOCATION:

1. PURPOSE & ACCURACY - ~~± 2%~~ ± 0.01 in.
2. CALIBRATION INTERVAL - 1 year

C. CALIBRATIONS: DONE BY-

CALIBRATION DATE	CALIBRATION DUE NEXT	CALIBRATION AGENCY	ACCEP	CALIBRATION RESULTS ADJUSTMENTS REQUIRED
3/28/95	3/28/96	Inhouse	WK	
3-19-96	3-19-97	INHOUSE	RB	
4-20-97	4-20-98	"	RA	
4-8-98	4-8-99	"	WK	
5/10/99	5/10/00	"	RA	
5/30/00	5/30/01	"	RA	

D. MAINTENANCE AND REPAIR:

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR OR MAINTENANCE

# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 5-30-00  
REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: MAGNEHELIC

MODEL: Dwyer - 2000

SERIAL NUMBER:

WHI INVENTORY #093

WHI # 103  
MICROTECTOR

MICROTECTOR	ACTUAL	MAGNEHELIC	DEVIATION %
.05	.10	.10	0
.024	.048	.05	.002
.039	.078	.08	.002
.050	.100	.100	0
.060	.120	.120	0
.073	.146	.150	.004

AVERAGE DEVIATION = .13 %

**ITS EQUIPMENT CALIBRATION RECORD**

ITS# 126

DESCRIPTION: Sling Psychrometer

MANUFACTURER: Taylor

SERIAL #: - MODEL: -

EQUIPMENT LOCATION: E+E

PURPOSE & ACCURACY: ±5% RH

CALIBRATION SPECIFICATIONS/INTERVAL: 6 mo.

CALIBRATION DATE	NEXT CALIBRATION	CALIBRATION AGENCY	CAL. BY	RESULTS/ADJUST.
5/24/99	11/24/99	In-house	RA	
5/15/00	11/15/00	"	RA	

**MAINTENANCE AND REPAIR:**

DATE OUT OF SERVICE	DATE BACK IN SERVICE	REPAIR AGENCY	DESCRIPTION OF REPAIR

# ITS Intertek Testing Services NA Inc.

Middleton, Wisconsin

CALIBRATION DATE: 5-15-00  
REVIEWED BY: [Signature]

CALIBRATED BY: RA

DESCRIPTION: SLING  
PSYCHROMETER

MODEL: TAYLOR

SERIAL NUMBER:

WHI INVENTORY #126

USING WHI#174 OMEGA CALIBRATOR TO CALIBRATE

Calibrator	Wet Bulb Thermometer	Deviation	Dry Bulb Thermometer	Deviation
34.4	36	+1.6	36	+1.6
40	41	+1	41	+1
55	56	+1	55	-1
70	70	0	71	+1
80	81	+1	80	0
90	91	+1	89	-2
		Avg .934°F	Avg .1°F	

# APPENDIX F



DRAWING INDEX

WHI FIGURE	MFG. DRAWING NUMBER	DESCRIPTION	CURRENT REVISION	ORIGINAL DRAWING DATE	WHI APPROVA L DATE
1	NA	PARTS LIST	NA	NA	16 AUG 00
2	1400-205	GLASS FITTING	A	7 MAR 00	16 AUG 00
3	1400-206	GLASS FITTING	A	7 MAR 00	16 AUG 00
4	3100-29	DOOR HANDLE	A	3 MAY 00	16 AUG 00
5	3100-30	DOOR HANDLE AXIS	B	4 MAY 00	16 AUG 00
6	3400-04	REAR PLATE CAST IRON	F	28 MAY 00	16 AUG 00
7	3400-04	REAR PLATE CAST IRON	F	28 MAY 00	16 AUG 00
8	3400-09	FUEL DOOR	D	15 MAY 98	16 AUG 00
9	3400-09	FUEL DOOR	D	15 MAY 98	16 AUG 00
10	3400-81	BAFFLE PLATE STAINLESS	A	19 JUN 00	16 AUG 00
11	3400-82	INSIDE REAR PLATE	A	4 JUN 00	16 AUG 00
12	3400-83	INTERMEDIATE FRAME (GRATE)	A	3 AUG 00	16 AUG 00
13	3400-84	BAFFLE PLATE CAST IRON	A	23 JUN 00	16 AUG 00
14	3400-85	PLATE FOR INTERMEDIATE FRAME	A	27 JUN 00	16 AUG 00
15	3400-87	HANDLE HANGER	A	7 JULY 00	16 AUG 00
16	3400-88	CUT AWAY VIEW	A	7 AUG 00	16 AUG 00
17	3400-89	CUT AWAY VIEW	A	7 AUG 00	16 AUG 00
18	3400-90	REAR PLATE	B	7 AUG 00	16 AUG 00

# Morse 3400 USA

Pos.No.	Parts	Drawing No.
LX 1	Intermediate frame	3400 - 83
2	Inside top plate	3400 - 08
LX 3	Plate for intermediate frame	3400-85
4	Draft reducer	2100-54
LX 5	Inside rear plate	3400-82
6	Fitting w. thread for flue collar	1400-204
7	Cover	1126-16
8	Handle for riddling grate	1120-42
9	Flue collar	1126-64
10	Base plate	3400-01
11	Front frame	3400-02
LX 12	Rear plate, cast iron	3400-04
13	Top plate	3400-12
14	Leg	"
LX 15	Door	3400-09
LX 16	Baffle plate, cast iron	3400-84
17	Side plate w. owl	3400-40
18	Poker	9000-05
19	Distance tube	3400-50
20	Distance tube	"
21	Ash tray	2100-33
22	Hinge pin	1126-38
23	Distance tube	1400-302
24	Radiant shielding, bottom	3400-44
LX 25	Hanging for handle	3400-87
26	Brick securing bracket, side	3400-79
LX 27	Convection rear plate	3400-45
LX 28	Rear plate	3400-90
29	Riddling bar	3400-46
30	Hinge pin	"
31	Flat bar	5000-63
32	Distance tube	5000-64
LX 33	Hinge pin	"
LX 34	Baffle plate, stainless	3400-81
35	Draught control	3400-15
36	Air inlet arm	3400-17
37	Assemble steel	3400-18
38	Assemble plate	3400-49
39	4x16 screw	"
40	5x8 black steel set screw	"
41	6x10 black steel set screw	"
42	6x16 black steel set screw	"
43	6x20 black steel set screw	"
44	6x25 black steel set screw	"
45	6x35 black steel set screw	"
46	6x40 black steel set screw	"
47	6x45 black steel set screw	"
48	6x55 black steel set screw	"
49	8x20 black steel set screw	"
50	Steel box 8 mm	"
51	Steel box 8 mm	"
52	3x8 indvendig 6kt. Skrue	"
53	4x5 pinol skrue	"
54	6x10 screw	"
55	4x30 screw	"
56	2x25 cotter pin	"
57	4x8 screw	"
58	5x8 screw	"
59	6x25 screw	"
60	6 mm brass washer	"
61	4 mm nut	"
62	Stainless handle for adjustment	3400-41
63	Knob for riddling grate	5000-60
64	Bush, brass	1126-27
LX 65	Handle	3100-29
LX 66	Axis for handle	3100-30
67	Stainless pressure spring	"
LX 68	Glass fitting	1400-205
69	8 mm air slider washer	"
70	8 mm washer	"
71	Ceramic glass	3400-20
72	Stone, side, back	3400-47
73	Stone, side, front	3400-47
74	Convection side plate	3400-11
75	Tightening tape	"
76	3.5x8.5 screw	"
LX 77	6x30 screw	"
78	Glass fitting	1400-206

①






AUG 16 2000

INTERTEK TESTING SERVICES

Middletown, WI  
By: [Signature]

PARTS LIST 3410, 3440



2



AUG 16 2000




INTEN TEK TESTING SERVICES

Middleton, WI


By: OK ER

1400-205 - Sheet 1

Rev.		Revisionstekst:		Sign.:	Date:
Materiale:	1 mm rustfri plade			Konstr.:	RSV
Vægt:	0,005 kg.	Bearbejdes:	buk/bore	Frigivet:	KDU
Overfladebeh.:	-		- m <sup>2</sup>	Tegn.format:	A4
Måltolerance:	Mål uden toleranceangivelse DS/ISO 2768-1 m			Målforshold:	2:1
Ruhedstolerance:				Varenr.:	71145700
Værktøjsnr.:	-			Tegningsnr.:	1400-205 a
Tegningstype:	Emnetegning				



3



AUG 16 2000




INTERTEK TESTING SERVICES

By: OR SK

1400-206 - Sheet 1

Materiale:		1 mm rustfri plade		Rev. / Revisionsleksl:	Sign.:	Dato:	
Vægt:	0.006 kg.	Bearbejdes:		Titel:	Konstr.:	RSV 07.03.2000	
Overfladebeh.:			m <sup>2</sup>		Glasbeslag 2	Frigivet:	RSV 30.06.2000
Måltolerance:	Mål uden toleranceangivelse DS/ISO 2768-1 m			GLASS FITTING		Tegn.format:	A4
Ruhedstolerance:				Morsø 1400		Målforhold:	2:1
Værkløjsnr.:						Varenr.:	71145900
Tegningstype:	Emnetegning					Tegningsnr.:	

Denne tegning tilhører Morsø Jernsløberi A/S og må ikke afhændes, udlånes eller kopieres uden firmaets skriftlige tilladelse




AUG 1 6 2000

INTERTEK TESTING SERVICES

Middleton WI

By: OK ER


Generelt radius = 1mm



Materiale:	GG15	Titel:	Håndtag	Signi:	KDU	Dato:	03.05.2000
Vægt:	0.33 kg.	Behandling:	Epox/fræses	Konstr.:	KDU	08.05.2000	
Overfladebeh.:	Moles	Mål:	0.01 m <sup>2</sup>	Figur:	KDU		
Måltolerance:	M5 uden tolerancespille	ISO-norm nr. 8042, C18		Tegn. format:	A3		
Ruldetolerance:				Målestok:	1:1		
Værktøjrnr.:	Modelnr. 3129			Varenr.:	34312900		
Tegningstype:	Støbelegning			Tegningnr.:	3100-29 a		

**morsø**

Denne tegning tilhører Morsø Jernstøberi A/S og må ikke offentliggøres, udlejes eller kopieres uden firmas tilladelse.



**Note:**  
Fræsning og boring orienteres j.v.f. tegning.

AUG 1 6 2000

**INTERTEK TESTING SERVICES**  
Middleton, WI  
By: OK ER

Materiale:	Rustfast stål
Vægt:	0,13 kg. Bearbejdes: Drejes/bores
Overfladebeh.:	Ubehandlet m <sup>2</sup>
Måltolerance:	Mål uden toleranceangivelse DS/ISO 2768-1 m
Ruhedstolerance:	
Værkøjsnr.:	
Tegningsstype:	Emnetegning

b	Tolerance hul påførl. Note iflg. leverandør påførl	KDU	09.06.2000
Rev.	Revisionstekst:	Sign.:	Dato:
Titel:		Konstr.:	KDU 04.05.2000
<b>Døraksel</b>		Frigivet:	KDU 30.05.2000
<i>DDR HANDLE AXIS</i>		Tegn.format:	A4
<b>Morsø 3100</b>		Målf forhold:	1:1
<b>morsø</b> <small>Drøbakvej 115 4600 Sønderborg</small>		Varenr.:	71312900
		Tegningsnr.:	<b>3100-30 b</b>



3100-30 - Særfil











Detail 1

9

FUEL DOOR



AUG 16 2000


INTERTEK TESTING SERVICES

Middleton, WI




ikke originale redler: R=1.5

By: OKER

Rev	Revision	Rev. Date	Titel:	Skala:	Date:
a	1	15.05.98	Der	KDU	15.05.98
b	2	15.05.98	Morse 3400	1:1	15.05.98
c	3	15.05.98	Morse 3400	1:1	15.05.98
d	4	15.05.98	Morse 3400	1:1	15.05.98
			3400-09	3400-09	3400-09
			MORSE	MORSE	3400-09 d 378



Detail 2



BAFFLE PLATE, STAINLESS

AUG 1 6 2000

INTERTEK TESTING SERVICES  
Middletown, WI

By: OK DR


Material: 1,5mm rustfri plade		Tilbehør: Røgledeplade rustfri		Konstr.: KDU		Dato: 19.06.2000	
Vægt: 1,43 kg	Bearbejdet: Ikke/bore	U.S.A.		Figur: KDU		08.06.2000	
Overfladebeht.: Ikkebehandlet	Behandling: Ikke	Morsø 3400		Tegn. format: A3			
Måltolerance: Målt uden toleranceangivelse	Material: PS/ISO 2768-1 m			Målestørrelse: 1:2			
Ruhestolerance: Ikke	Værktøjsnr.: Ikke			Varemnr.: 71348100			
Tegningsnr.: Ikke	Emnebetegnelse: Røgledeplade rustfri			Tegningsnr.: 3400-81 a			

Denne tegning tilhører Morsø Jernstøberi A/S og må ikke afleveres, udlånes eller kopieres uden firmasettets skriftlige tilladelse










14

PLATE FOR INTERMEDIATE FRAME

325.8






Rev. / Revisionsstadij:		Sign.: KDU	Date: 27.06.2000
Titel: Afdekningsplade luftkabinen		Rev. 1: KDU	Date: 06.08.2000
Materiale: 3mm Rustfri plade (AISI 316)		Tegn. format: A3	
Vægt: 0.5 kg	Bearbejdet: Bv/bore	Målestok: 1:1	
Overfladebeholdning: Ubehandlet	Fladeareal: - m <sup>2</sup>	Varenr.: 71348000	
Måltolerance: Ikke uden toleranceangivelse		Tegningsnr.: 3400-85 a	
Ruhestolerance: DS/ISO 2768-1 m			
Værktøjsnr.: -			
Tegningsstype: Emnetegning			


By: OK ER

C-C

Denne tegning tilhører Morse Jernstøberi A/S og må ikke ændres, udlånes eller kopieres uden firmoets skriftlige tilladelse



15



AUG 16 2000

INTERTEK TESTING SERVICES


By: Middelfart, WI

3400-87 - Sheet 1


Rev.		Revisionslekt:		Sign.:	Dato:
Materiale:	1 mm SPD plade			Konstr.:	RSV 07.07.2000
Vægt:	0,015 kg.	Bearbejdes:	Buk/bore	Frigivet:	KDU 08.08.2000
Overfladebeh.:	Males		- m <sup>2</sup>	Tegn.format:	A4
Måltolerance:	Mål uden toleranceangivelse DS/ISO 2768-1 m			Målforhold:	1:1
Ruhedstolerance:				Varenr.:	71347900
Værktøjsnr.:	-			Tegningsnr.:	3400-87 a
Tegningstype:	Emnetegning				

Denne tegning tilhører Morsø Jernstøberi A/S og må ikke udlånes, udlånes eller kopieres uden firmaets skriftlige tilladelse







Set bogfr




Set bogfr



Set bogfr



Set bogfr



AUG 16 2000

CUT AWAY VIEW  
3410


INTERTEK TESTING SERVICES

Middleton, WI


By: *C. K. Z. R.*

Rev.	Revision	Sign.	Date	Titel:	Sign.	Dat.
				Gockendelsestegning	KDU	07.05.00
				Morsb 3410 USA	Techn.:	Wahrscheinl.
				Finanz:	A2	1:5
				3400-88	Varenr.:	-
				MORSØ	Testnummer:	-
				3400-88 c	Testnummer:	3400-88 c


116



Set: bag'ra




Snit B-B




Snit A-A

17



Snit C-C



CUT AWAY VIEW  
3440

INTERTEK TESTING SERVICES

Middleton, WI

By: PK EK

Rev.	Revisjon	Rev. Data	Titel:	Sign:	Date:
			Godkennelsestegning	KDU	07.08.00
			Morsø 3440 USA	Tegn. form.: AZ	Kalibrering
			filnavn: 3400-89	Verenummer: -	1:5
				Tegningsnummer: 3400-89 c	



# APPENDIX G

# MORSØ JERNSTØBERI A/S

BY APPOINTMENT TO THE ROYAL DANISH COURT

DK-7900 NYKØBING MORS

July 6, 2000

Mr. Rick Armstrong  
Intertek Testing Services  
8431 Murphy Drive  
Middleton, WI 53562  
USA

RECEIVED  
JUL 11 2000  
INTERTEK TESTING SERVICES  
Middleton, WI

Dear Mr. Armstrong:

The following information is being provided regarding the Morsø Owl stove you will be testing for EPA certification starting on Monday, July 10, 2000.

The stove is a non-catalytic model. The model number is 3400.

The combustion air control is located on the lower right front of the stove beneath the ashlip.

Based on our pre-testing, appropriate air settings for EPA testing are as follows:

Minimum burn rate - Air control lever to the fully clockwise (closed) position. The air control has a minimum setting with a "stop". The width of the air opening at this position is 0.75" when measured at the actual air opening. A minimum burn rate less than 1 kg/hour but above 0.8 kg/hour is anticipated.

Maximum burn rate - Air control lever to the fully counterclockwise (open) position.

Medium Low burn rate - Air control open at #1 position as indicated by the holes in air position locator plate by the air control handle. This corresponds to an air opening width of 1.188" at the actual air opening.

Medium High burn rate - Air control open at #3 position as indicated by the holes in air position locator plate by the air control handle. This corresponds to an air opening width of 2.00" at the actual air opening.

These air settings should be used only as a guideline. Adjustments should be made as required, based on the results of each previous certification test run.

The startup procedure during the first five minutes is the same the low and medium low categories. The air control lever should be in the maximum position for the first five minutes. The front door should be cracked open until the fuel load is burning briskly, 3 1/2 minutes maximum and then closed. The air control should be set at the run setting after 5 minutes. On the high and medium high categories, the door should be cracked open for the first 1 minute only

Address:  
Morsø Jernstøberi A/S  
Furvej 6  
DK-7900 Nykøbing Mors  
Phone: Salesdept.: +45 96 69 19 00  
Accounts: +45 96 69 19 20  
Production: +45 96 69 19 30

A/S no. 209,161  
VAT no. DK 17 06 35 37 (export only)  
PBS nr. 00 18 27 96 (only for DK)  
E-mail Stoves@morsoe.com  
Homepage www.morsoe.com  
Fax +45 97 72 21 69

Bank:  
DKK Giro 3 35 11 57  
DKK Den Danske Bank, Thisted - acc.no. 4784 - 421465  
DKK Morsø Bank, Nykøbing Mors - acc.no. 7380 - 2010865  
DEM Den Danske Bank, Hamburg - Kto. Nr. 32394009  
(BLZ 203 205 00)  
GBP Den Danske Bank, London - acc. no. 69639

Mr. Rick Armstrong  
July 6, 2000  
Page 2

and then closed. The air control should be left open for the full 5 minutes and then set at the run setting.

Questions about air control settings should be directed to Mr. Derik Andors, of Ferguson, Andors & Company. They will be witnessing the certification testing on Morsø's behalf.

Sincerely,

Morsø Jernstøberi A/S

A handwritten signature in blue ink, appearing to read "Svend Erik Nielsen", written over a horizontal line.

Svend Erik Nielsen  
Development Manager


# morsø

By appointment to  the Royal Danish Court

## Installation and Operating Instructions

### 3410 and 3440

For use in North America



Read this entire manual before you install and use your new room heater. If this room heater is not properly installed, a house fire may result. To reduce the risk of fire, follow the installation instructions. Failure to follow instructions may result in property damage, bodily injury, or even death.

Contact local building officials about restrictions and installation inspection requirements in your area.

Save these instructions

MORSØ JERNSTØBERI A/S · DK-7900 NYKØBING MORS  
E-Mail: [stoves@morsoe.com](mailto:stoves@morsoe.com) · Website: [www.morsoe.com](http://www.morsoe.com)

Distributed by: HEARTHLINK INTERNATIONAL  
9 Maple St. - Randolph, Vermont - 05060 - USA

We congratulate you on your choice of a Morsø stove. Morsø has been producing some of the world's best stoves since 1853. If you follow this installation- and operating instruction carefully, we can assure you many years of warmth and pleasure.

#### Optional Accessories

A wide range of accessories (such as handling gloves, fireside tools, glass cleaner and heatproof paint) are available for use with your Morsø stove. They help with day-to-day running and maintenance. Contact your Morsø dealer for more information.

The Morsø 3410 owl the U.S. Environmental Protection Agency's emission limits for wood heaters sold on or after July 1, 1990



The Morsø 3410 owl has been tested by Intertek Testing Services and is listed by Warnock Hersey, Inc. The test standards are ANSI/UL-1482 for the United States and ULC S627 for Canada.

The stove is listed for burning wood only. Do not burn other fuels.

#### CONTENTS:

<b>1.0</b>	<b>Installation of your Morsø stove</b>	
1.1	Checking loose parts in the stove	4
1.2	The chimney / flue system	4
1.3	Flue Connection	5
1.4	Connection to existing chimney	6
1.5	Positioning the stove	8
<b>2.0</b>	<b>Operation</b>	
2.1	Before you start firing	10
2.2	Lighting and loading intervals	11
<b>3.0</b>	<b>Maintenance</b>	
3.1	Exterior maintenance	12
3.2	Internal maintenance	12
3.3	Cleaning the Stove and the Flue	14
3.4	Leaving the stove for extended periods	16
3.5	Parts diagram	17
3.6	Parts list	18





## 1.0 Installation of your Morsø stove

Installation of woodburning stoves must be safe and legal.

If your Morsø stove is not installed correctly, it may cause a house fire. To reduce the risk of fire, the installation instructions must be followed carefully. Contact the local building officials about restrictions and installation inspection in your area.

Before you start installing your stove, make sure that:

- The stove and chimney connection are placed far enough from combustible materials to meet all clearance requirements.
  - The floor protection must be adequate and must be made correctly according to the requirements.
- All necessary approvals are needed from the local building officials.

The data plate, which is located on the back of the stove, provides information regarding safety testing information, name of certified testing laboratory, and installation requirements. Installation requirements vary in different districts, and the local building officials have authorization to approve your installation. You should discuss the installation with them before beginning. Please ask your dealer for further information.

Do not connect to any air distribution duct or system.

Important: If the installation instructions are not followed carefully, it may cause dangerous situations like chimney - and house fires. Follow the instructions carefully and do not deviate from them as it may cause injuries to people or property.

### 1.1 Checking loose parts in the stove

After unpacking, check that the center grate (in the centre of the fire bed) and the fire bricks are firmly in position and have not shifted in transit. Check also that the air control works freely.

#### Standard Accessories

Poker, ceramic flue connection gasket and riddling tool are standard accessories, and can usually be found in the ashpan or firebox area.

### 1.2 The chimney / flue system

Note that the flue system must be independently secured and must not rely on the stove for support.

The stove must not be connected to a chimney flue serving any other appliance. (Several flues may run up a single chimney stack; use one flueway per appliance).

Use a residential type masonry or listed type HT factory-built chimney.


High Temperature (H.T.) Chimney Standard UL-103-1985 (2100° F.) for the USA, and High Temperature (650°C) Standard ULC S-629 for Canada.

The internal dimensions of the chimney connector and chimney must not be less than 6 inches diameter (or equivalent cross section), and should not be significantly larger than this. Too large a section will tend to allow the flue gases to cool excessively, causing sluggishness or unpredictability in the stove's performance.

The length of the chimney system should be at least 16 feet above the stove in normal domestic situations, measured from the flue collar to the top of the chimney.

Local conditions like for example - roof constructions, large trees nearby and high altitude, may influence the chimney draft and height. Therefore, contact the local professional chimney sweep or your Morsø dealer.

### Typical Factory-Built or Masonry Chimney Installations



### 1.3 Flue Connection

The stove is supplied from the factory with a flue collar fitted to the top plate and a round blanking plate blocking off the rear flue exit (behind the rear shield plate).

Use a 24 MSG black or blue chimney connector or listed double wall chimney connector. Refer to local codes and the chimney manufacturer's instructions for precautions required for passing a chimney through a combustible wall or ceiling. Remember to secure the chimney connector with a minimum of three screws to the product and to each adjoining section.

The collar can be fitted to the rear outlet. Simply knock out the round panel on the rear heat shield plate to reveal the cast iron plate. Untwist the blanking plate and the flue collar and swap their positions. Re-secure by pushing down and tighten the enclosed screws. Position the stove and connect to the flue system.

**Wear gloves and protective eyewear when drilling, cutting or joining sections of chimney connector**

### 1.4 Connection to the existing chimney

A chimney connector is the double-wall or single-wall pipe that connects the stove to the chimney. The chimney itself is the masonry or prefabricated structure that encloses the flue. Chimney connectors are used only to connect the stove to the chimney.

Double-wall connectors must be tested and listed for use with solid-fuel burning appliances. Single-wall connectors should be made of 24 gauge or heavier gauge steel. Do not use galvanized connector; it cannot withstand the high-temperatures that smoke and exhaust gases can reach, and may release toxic fumes under high heat. The connector must be 6 inches (150mm) in diameter.

**If possible, do not pass the chimney connector through a combustible wall or ceiling. If passage through a combustible wall is unavoidable, refer to the sections on Wall Pass-Throughs. Do not pass the connector through an attic, a closet or similar concealed space when installing the chimney connectors.**


It is important to keep the flue gases moving smoothly in the right direction. Do not vent into a large void at this location; rather form one continuous section all the way up. Use mild bends (e.g. 45° vs. 90°) rather than sharp angles where a change of direction is required. All parts of the venting must be accessible for cleaning purposes.

In horizontal runs of chimney, maintain a distance of 18 inches from the ceiling. Keep it as short and direct as possible, with no more than two 90 degree turns. Slope horizontal runs of connector upward 1/4 per foot (20 mm per metre) going from the stove toward the chimney. The recommended maximum length of a horizontal run is 3 feet (1 metre), and the total length should be no longer than 8 feet (2.5 metres).


Information on assembling and installing connectors is provided by the manufacturer's instructions exactly as you assemble the connector and attach it to the stove and chimney.

**Be sure the installed stove and chimney connector are correct distances from near by combustible materials. See the clearance paragraph page 8.**


### Chimney Connector Systems and Clearances from Combustible Walls for Residential Heating Appliances




**A** Minimum 3.5-in-thick brick masonry all framed into combustible wall with a minimum of 12-in brick separation from clay liner to combustibles. The fireclay liner shall run from outer surface of brick wall to, but not beyond, the inner surface of chimney flue liner and shall be firmly cemented in place.



**B** Solid-insulated, listed factory-built chimney length of the same inside diameter as the chimney connector and having 1-in. or more of insulation with a minimum 9-in. air space between the outer wall of the chimney length and combustibles.



**C** Sheet steel chimney connector, minimum 24 gauge in thickness, with a ventilated thimble, minimum 24 gauge in thickness, having two 1-in. air channels, separated from combustibles by a minimum of 6-in. of glass fiber insulation. Opening shall be covered, and thimble supported with a sheet steel support, minimum 24 gauge in thickness.



**D** Solid insulated, listed factory-built chimney length with an inside diameter 2-in. larger than the chimney connector and having 1-in. or more of insulation, serving as a pass-through for a single wall sheet steel chimney connector of minimum 24 gauge thickness, with a minimum 2-in. air space between the outer wall of chimney section and combustibles. Minimum length of chimney section shall be 12-in. chimney section spaced 1-in. away from connector using sheet steel support plates on both ends of chimney section. Opening shall be covered, and chimney section supported on both sides with sheet steel supports securely fastened to wall surfaces of minimum 24 gauge thickness. Fasteners used to secure chimney section shall not penetrate chimney flue liner.

### 1.5 Positioning the stove

#### Distance to walls and lintel

When the stove is positioned near *combustible* materials, observe all current local and national building regulations with regards to clearances. Whatever regulations apply to your area, do not in any case install the stove within 8 inches of combustible materials around the sides or 16 inches above the top of the stove. These distances may need to be increased if the materials are sensitive to heat. Note also that wall paper and other decorative materials may become detached with the effects of heat and care should be taken to ensure that they do not fall towards the stove in such an event.

When the stove is positioned near *non-combustible* materials, a gap of 4 inches or more is recommended for cleaning purposes and to ensure that heat circulates around the stove and out into the room.

Clearance chart:

	In	Mm	In	Mm
Using single or double wall chimney connector				
Unit to sidewall	16	405	Unit to backwall	12 305
Unit corner to diagonal wall	12	305	Flue collar to backwall	14,5 370
<b>Fireplace Hearth mount</b>				
Unit to top trim	19	485	Unit to side trim	11 280
Unit to mantle	20	510	Unit to sidewall	15 380


3440

	In	Mm	In	Mm
Using single or double wall chimney connector				
Unit to sidewall	8	205	Unit to backwall	8 205
Unit corner to diagonal wall	6	150	Flue collar to backwall	10,5 265
<b>Fireplace Hearth mount</b>				
Unit to top trim	19	485	Unit to side trim	8 205
Unit to mantle	20	510	Unit to sidewall	8 205

#### On the floor

If the stove is to be placed on a combustible floor, a solid, non-combustible layer should cover the floor beneath the stove. This layer should cover an area of at least 16 inches in front of the stove door and at least 8 inches either side of the opening and 6" to the rear. You must ensure that the floor in this area can hold the weight of the stove comfortably.

In Canada non-combustible floor protector is required under the stove as well. The floor protector must extend 18 inches (460mm) to the front and 6 inches (155mm) from the sides and rear.



U.S. Canada

- A. 41" (1045 mm)
- B. 43" (1145 mm)
- C. 6" (155 mm)
- D. 8" (155 mm)
- E. 16" (460 mm)

#### Distance to furniture

The recommended minimum distance from stove to furniture is 30 inches. Note that some furniture is more easily affected by heat and may need to be moved to a greater distance. This is your responsibility.

In addition other combustible materials, away from the stove. In general, a distance of 30 inches must be maintained between the stove and moveable combustible item such as drying clothes, newspapers, firewood etc.

#### Note:

##### Acid Protection

If acid-washing the masonry around the stove, protect the stove surface with an acid-proof cover

##### Fresh Air Inlet

Unless there is deemed to be sufficient ambient leakage of air into the room via doorways, windows and the like, a dedicated fresh air inlet will be needed. This inlet should have 2 square inches (1250 square mm) of free air space. This is particularly important where the room is well sealed, or where an extractor hood or ventilation system disturbs the natural air pressure. Such an inlet should not be on a wall that is usually subject to negative pressure from normal wind pattern. Avoid placing the inlet directly across the room from the stove, thus causing a cold air draft.

## 2.0 Operation

### 2.1 Before you start firing

For Use with Solid Wood Fuel Only. Do Not Overfire, If Heater or Chimney Connector Glows You Are Overfiring. Inspect and Clean Chimney Frequently. Under Certain Conditions of use creosote buildup may occur rapidly. Because of risk of smoke and flame spillage, operate only with door fully closed.

#### Caution:

Hot while in operation. Keep children, clothing and furniture away. Contact may cause skin burns.

Do not use chemicals or fluids to start the fire.

Do not burn garbage or flammable fluids.

Do not use gasoline, gasoline-type lantern fuel, kerosene, charcoal lighter or fluid or similar liquids to start or freshen up a fire in this heater. Keep all such liquids away from the heater while it is in use.

#### Choosing your fuel

All types of natural wood can be burned on your stove, but they must be well-seasoned and dry. Once the wood is cut to length, it should be split down middle - to suit the dimensions given below - to allow moisture to evaporate.

Cut the wood to a length of 10 inches (25 cm) and approx. 3 to 3.5 inches (7-8 cm) in section. If you can weigh your wood, aim for around 0,7 Kg.

The maximum moisture content of the wood should be around 20%.

Store the logs under cover in a location where fresh air can move through the stack. Some soft woods may take as little as one good summer to season, where some harder woods may take a couple of years or more. Well seasoned wood will be remarkably light to hold and will probably have radial cracking at the ends, if your wood spits or sizzles when burnt, and your stove's door glass persistently mists up, your wood is not properly seasoned. Never use drift wood (from the sea), whose salt content may cause corrosion, nor construction wood that may have been impregnated with chemicals.

#### Firing

The initial fire should be small, so that the stove paint can cure and the main plates of the stove can settle into position. Some fumes will be given off by the paint. Ventilate the room during this phase.

The setting of the valve, lighting techniques and loading intervals will depend on chimney draft, the fuel used, the heat required and so on. Some basic techniques are outlined below.

#### In principle

Your stove has two air supplies:

Primary air is controlled by the upper air controller under the ash lip. The air eventually washes at high speed down the back face of the door glass. This super-heated air helps with the combustion of volatile gases produced by the fire.

Secondary air is supplied to the top of the fire through two rows of holes in the steel baffle. This effectively burns off other residual gases, making for very clean emissions. This air supply is

10

constant and cannot be varied.

### 2.2 Lighting and loading intervals

When first lighting the stove, a large volume of air is needed. When the stove is cold, you should leave the door open an inch or two for the first few minutes and open the primary air supply completely. While the door is open, do not leave the stove unattended.

To form a reasonable bed of ash on the floor of the stove, you should use 5-6 inches thickness (2-4 pound) of dry kindling at the initial lighting. Always maintain a 1-1.5 inch (2-3 cm) layer of ash on the floor of the combustion chamber at all other times.

#### Step-by-step procedure

1. The air supply must be fully open. Maximum 4 turns.
2. Light the fire. An ember bed will quickly be formed by lighting with firelighters, morso kindling bags or 7-10 pieces of twisted paper under the dry kindling wood (see above).
3. After lighting, partially close the door, leaving it open an inch or two to allow in plenty of combustion air.
4. When the chimney is warmed through after 5-10 minutes, the door should be closed. A suitable ember bed will be formed after a further 15-20 minutes.
5. When ready to reload, use a poker to spread the ember across the firebox floor, bringing plenty towards the front of the stove.
6. Lay three pieces of wood (see dimensions above) onto the embers. Leave half an inch (1 cm) or more between each piece. Place the ends of your logs towards the opening, but not too close to the front.



7. Close the door. Leave the primary air supply fully open.
8. After a few minutes, and adjust the primary air supply to suit your heating requirements.
9. Anticipate each refueling, remembering to add a modest layer of wood while there are still plenty of live embers. Repeat steps 5-8.

11

Do not for any reason attempt to increase the firing of your heater by altering the air control adjustment range outlined in these directions.

**Warning:** Fireplace stoves must never be left unattended with doors open.

If door are left partly open, gas and flame may be drawn out of the fireplace stove opening, creating risks from both fire and smoke. We recommend you to fit a smoke detector in the room where the stove is installed.

**DO NOT OVERFIRE THIS HEATER.** Overfiring may cause a house fire, or can result in permanent damage to the stove. If any part of the stove glows, you are overfiring.

#### Draft conditions

If smoke or fumes come out of your stove when lightning up and reloading, or if the fire simply will not respond, a poor draft is almost certainly to blame. (In a very few cases, there may be insufficient fresh air getting into the room - see installation advice above). Take advice from your stove supplier on how best to upgrade your flue system to improve draft.

#### Rules of woodburning

If you want less heat, put fewer logs on the stove and reduce the amount of air. It is still important to maintain a good layer of embers.

Less heat - less wood - less air

Greater heat - more wood - more air

Soot deposits will settle on the glass if the stove is run too slowly or if your wood is not well seasoned.

### 3.0 MAINTENANCE

When performing maintenance on your stove, always protect yourself, using safety goggles or gloves

#### 3.1 Exterior Maintenance

The stove surface is painted with heat-resistant Senotherm paint. It is best kept clean by vacuuming with a soft brush attachment or by wiping with a lint-free cloth. Over a period of time, the painted surface may become slightly grey. A can of Morso touch-up spray paint should be available from your stove supplier. This can be applied - in accordance with the instructions - in just a few minutes. When first firing after touching up, the stove will give off a slight smell as the paint cures. Make sure to ventilate the room well during this phase.

#### 3.2 Internal maintenance

Glass

If the stove is generally run at the correct temperatures, there should be little or no dirt on the glass. If dirt does settle during lighting, most will burn off as temperatures increase. For heavier deposits that will not burn off, use morso glass cleaner, applied when the glass is cold, in accordance with the instructions. Never use abrasive cleaners on the glass surface.

12

#### Reasons for dirty glass

- Fuel too wet
- Logs too large or not split
- Combustion temperatures too low

Replace broken glass immediately.


Do not operate your stove if the glass in the door is damaged.

If you need to replace the glass, it should be replaced with the high temperature ceramic glass supplied by Morso, contact your Morso dealer.

Installing the glass

Never install the glass when the stove is in function.

Lift the door off its hinges and place face-down on a sheet of cardboards or other non-abrasive fabric. The door is removed by loosening the 2 screws with a hexagon box wrench by the hinges



2. Unscrew the eight bolts that secure the glass. (In the event that a bolt sheers off when being unscrewed, remove the remaining body of the bolt by drilling down its centre with 1/8 inch high speed steel drill bit. Smaller drill bits may be successful, but do not use a larger bit. Make sure the bit stays away from the edges of the bolt - this may damage the thread in the cast iron).

3. Remove the old ceramic gaskets and clean up the surface underneath with wire wool or emery paper to remove loose particles.

4. Place the new gasket material in position around the perimeter of the window area, making sure to pinch them to the length in such a way that they make a continuous seal. Leave no gaps.

5. Place the new glass in position on the strips and screw home the fresh bolts and fitting by hand.

6. Finally, give each of the bolts an extra half turn or so. The glass should held tight enough that cleaning will not dislodge it. Do not over-tighten the bolts as this may put excessive pressure on the glass, resulting in cracking - important!

To reduce the risk of breaking the glass, avoid striking the glass or slamming the door.

**Internal service parts**

The flame-path equipment - consisting of the ashpan, grate, firebricks, glass, baffle and flue collar - are subject to the extremes of heat produced by the fire. From time to time, one or other of these parts may need replacing as a matter of routine maintenance.

**NOTE: The flame-path equipment, the ceramic rope and the paint finish are not covered by guarantee.**

All of these service parts can be bought from your morsø dealer, and we recommend that damaged parts are replaced as soon as possible to avoid collateral damage.

The grate may be replaced by lifting it by its left hand edge and twisting it backwards. Dislocate the riddling arm from the grate by feel from beneath the floor of the firebox. If you find this difficult for any reason, raising the rectangular grate surround casting may help.



Should the baffle be distorted by an overfire, the stove will still function, although its efficiency may be compromised. Replace it as soon as possible. The rear casing is removed (for bolts). Remove these and withdraw the baffle from the firebox (this may be easier if the firebricks are first removed).

Before replacing the baffle, scrape out the old fire furnace and replace with new to make an effective seal.

**Reasons for fast internal wear and tear**  
Persistent heavy firing

Soot and ashes left to accumulate

**Ceramic Gasket**

The gasket around the perimeter of the door may harden over a period of time. It should be replaced if it becomes difficult to close the door or if air starts to leak in around the perimeter of the door, causing the fire to become a little less controllable. A morsø rope gasket kit is available from your stove supplier.

**3.3 Cleaning the Stove and the Flue**

Check for soot above the baffle plate and around the flue outlet every month or so to start with. If the stove suddenly becomes sluggish, check for a soot fall around the flue collar or in the flue/chimney. - at least once a year. Inspect every month.

Clean the flue/chimney - all the way from the stove to the flue terminal point above the house.

A good routine is to clean the flue after each heating season in any case, and inspect prior to the season to ensure that bird's nests or other blockages have not occurred during the off season.

**Ash disposal**

Empty the ashpan on a daily basis or as needed. Ash allowed to build up towards the underside of the grate will trap heat and could cause premature failure of the grate.

**Empty the ashpan according to this procedure:**

When the door is closed, the grate can be operated by means of the riddling bar. Open the front door, and use a shovel or poker to stir excess ash through the ash slots in the grate down into the ash pan. Remove the ash pan, making sure to keep it level.

Dispose the ash in a metal container with a tight fitting lid. The closed container of ashes should be placed on a noncombustible floor or on the ground, well away from all combustible materials, pending final disposal. If the ashes are disposed of by burial in soil or otherwise locally dispersed, they should be retained in the closed container until all cinders have thoroughly cooled.

Return the ash pan to its original position in the stove, and close.

**Caution:**

Never empty a stove in operation.  
Never use your household or shop vacuum cleaner to remove ash from the stove; always remove and dispose of the ash properly.

**Creosote - formation and need for removal**

When wood is burned slowly, it produces tar and other organic vapors, which combine with expelled moisture to form creosote. The creosote vapors condense in the relatively cool chimney flue of a slow-burning fire. As a result, creosote residue accumulates on the flue lining. When ignited this creosote makes an extremely hot fire. When burning wood, inspect the chimney connector periodically to determine if a creosote buildup has occurred.

**Chimney sweeping**

Inspect the system regularly during the heating season as part of a regular maintenance schedule. To inspect the chimney, let the stove cool completely. Then, using a mirror, sight up through the flue collar into the chimney flue. If you cannot inspect the flue system in this fashion, the stove must be disconnected to provide better viewing access.

Clean the chimney using a brush the same size and shape as the flue liner. Run the brush up and down the liner, causing any deposits to fall to the bottom of the chimney where they can be removed through the clean-out door.

Clean the chimney connector disconnecting the sections, taking them outside, and removing any deposits with a stiff wire brush. Reinstall the connector sections after cleaning, being sure to secure the joints between individual sections with sheet metal screws.

If you cannot inspect or clean the chimney yourself, contact your local Morsø Dealer or a professional chimney sweep.

If you do experience a chimney fire, act promptly and:  
 Close the air control.  
 Get everyone out of the house.  
 Call the Fire Department.

#### Annual maintenance

Before the heating season, perform a thorough cleaning, inspection and repair:  
 Thoroughly clean the chimney and chimney connector.  
 Inspect the chimney for damage and deterioration. Replace weak sections of prefabricated chimney. Have a mason make repairs to a masonry chimney.  
 Inspect the chimney connector and replace any damaged sections.  
 Check gasketing for wear or compression, and replace if necessary.  
 Check the glass for cracking; replace if needed.  
 Check door and handles for tightness. Adjust if needed.

#### 3.4 Leaving the stove for extended periods

##### Important:


If the stove is to be left unused for any period of time, clean it out thoroughly and leave the spinner slightly open to allow airflow. Make sure that the flue does not allow rainwater to come anywhere near the stove; install a chimney cap, but do not block off the flue completely. These measures should ensure there is a slight movement of air through the stove, and that the body of the stove remains dry, right into the corners.  
 Any ash left within an unfired stove can attract moisture like blotting paper. If moisture is allowed to settle within the stove, rust will form. Rust expands as it takes a grip. This can lead to undue pressure on the stove joints, and this in turn may result in damage to the stove.

**NOTE:** It is best to thoroughly clean the stove after the heating season has concluded. Adding a desiccant, such as kitty litter, into the ash pan helps absorb moisture during the summer months. Be sure to remove this prior to the heating season.

#### Thank you for buying a morsø stove.

We hope you have many years of carefree warmth in its company. Some initial experimentation with loading and running techniques will decide your normal routine. If you have any problems after this short learning phase, please refer to your stove dealer. Should they be unable to help for any reason, please contact us in writing at the address on the front of this publication.

#### 3.5 Parts diagram for the model Morsø 3410 and 3440



## 3.6 Parts list for the model Morsø 3410 and 3440

Pos.No.	Parts	
1	Intermediate frame	
2	Inside top plate	
3	Plate for intermediate frame	
4	Draft reducer	
5	Inside rear plate	
6	Fitting w. thread for flue collar	
7	Cover	
8	Handle for riddling grate	
9	Flue collar	
10	Base plate	
11	Front frame	
12	Rear plate, cast iron	
13	Top plate	
14	Leg	
15	Door	
16	Baffle plate, cast iron	
17	Side plate w. owl	
18	Poker	
19	Distance tube	
20	Distance tube	
21	Ash tray	
22	Hinge pin	
23	Distance tube	
24	Radiant shielding, bottom	
25	Hanging for handle	
26	Brick securing bracket, side	
27	Convection rear plate	
28	Rear plate	
29	Riddling bar	
30	Hinge pin	
31	Flat bar	
32	Distance tube	
33	Hinge pin	
34	Baffle plate, stainless	
35	draught control	
36	Air inlet arm	
37	Assemble steel	
38	Assemble plate	
39	4x16 screw	
40	6x8 black steel set screw	
41	6x10 black steel set screw	
42	6x16 black steel set screw	
43	6x20 black steel set screw	
44	6x25 black steel set screw	
45	6x35 black steel set screw	
46	6x40 black steel set screw	
47	6x45 black steel set screw	
48		6x65 black steel set screw
49		8x20 black steel set screw
50		Steel box 6 mm
51		Steel box 8 mm
52		3x8 indvendig Bkt. Skrue
53		4x5 pinol skrue
54		6x10 screw
55		4x30 screw
56		2x25 cotter pin
57		4x8 screw
58		5x8 screw
59		6x25 screw
60		6 mm brass washer
61		4 mm nut
62		Stainless handle for adjustment
63		Knob for riddling grate
64		Bush, brass
65		Handle
66		Axis for handle
67		Stainless pressure spring
68		Glass fitting
69		6 mm air slider washer
70		8 mm washer
71		Ceramic glass
72		Stone, side, back
73		Stone, side, front
74		Convection side plate
75		Tightening tape
76		3.5x9.5 screw
77		6x30 screw
78		Glass fitting





# APPENDIX H

1. TUNNEL FLOW RATE

Tunnel flow rates are determined using the velocity pressure measurement made by a standard Pitot tube. The Pitot tube is located at the center of the dilution tunnel. Three x/y axis traverses were used to determine the relationship between the center velocity pressure and the average obtained by traversing. This procedure was carried out in accordance with EPA Method 2.

Velocity pressure and tunnel temperature data are used to calculate tunnel velocity via EPA Method 2, equation 2-9 as follows:

$$T_v = K_p * C_p * \sqrt{\Delta P} * \sqrt{\frac{T_s}{P_s * M_s}}$$

- Where:
- $K_p$  = 85.49 (English units constant for ft/sec.)
  - $F_p$  = Pitot tube center point coefficient determined from traverses
  - $C_p$  = .99 Coefficient for standard pitot tube
  - $\Delta P$  = Pitot tube velocity pressure (in. w.c.)
  - $T_s$  = Absolute tunnel temperature (1R)
  - $P_s$  = Absolute tunnel pressure (in. Hg)
  - $M_s$  = Mole. Wt. of tunnel gas stream (lb./lb.-mole, wet basis) = 29 \* (1-.04) + 18 \* .04 = 28.56
  - $T_v$  = Tunnel velocity (ft./sec.)

Tunnel flow is calculated by multiplying the average velocity as calculated by the above formula by the following equation (adaptation of EPA Method 2, formula 2-10).

$$T_f = \bar{T}_v * 60 * 0.1961 * \frac{528}{TT_{ave}} * \frac{PS}{29.92} * 1 - .04$$

Where:

- $\bar{T}_v$   
= Average tunnel velocity (ft/sec.)
- 0.1961 = Tunnel cross sectional area (ft<sup>2</sup>)
- $T_f$  = Tunnel flow rate (SCFM)
- $TT_{ave}$  = Average tunnel temp. (1R)
- PS = Average barometric pressure during test.
- 60 = sec. to min. conversion
- 0.04 = Assumed tunnel moisture content (4% by Vol.)

## 2. EMISSIONS RATE CALCULATION

Emissions rates are calculated from the total weight gain of the probe and first and second filters of each sampling system as follows:

$$ER = \left( \frac{T_f * Wt.Gain * 60}{vol.sampled} \right)^{0.81} * 1.82$$

Where:  
ER = Emissions rate (grams/hour OM7 equivalent)  
Vol. Samp. = Total volume sampled (SCFM, Dry)  
Wt. Gain = Total weight gain for filter system (grams)  
 $T_f$  = Tunnel flow rate (SCFM, Dry)

## 3. CORRECTIONS TO STANDARD CONDITIONS

The tunnel flow rate is corrected to standard conditions through the EPA Method 2 formulae. The volume sampled is measured by dry gas meters and must be corrected for meter temperature and ambient barometric pressure. The inlet and outlet temperatures of each dry gas meter are measured and recorded at 10-minute intervals during the test. The ambient barometric pressure is recorded at the beginning and end of each test.

The following formula is used to correct the total volume as measured by the dry gas meter to total volume at standard conditions (681F, 29.92 in. Hg):

$$VOL_{std} = VOL_m * \frac{PS}{29.92} * \frac{528}{AMT} * Y$$

Where:  
 $VOL_{std}$  = Total volume in Standard Cubic Feet  
 $VOL_m$  = Total volume as measured by dry gas meter.  
PS = Average barometric pressure  
AMT = Average meter temperature (1R)  
Y = Dry gas meter calibration factor

EXAMPLE CALCULATIONS

1. TUNNEL VELOCITY

INPUTS:  $P = .038$  in. w.c.  
 $T_s = 1001$ F  
 $P_s = 29.3$  in. Hg.  
 $M_s = 28.56$  lb./lb.-mole  
 $C_p = .99$   
 $F_p = .945$

$$T_v = 85.49 * .99 * .945 * \sqrt{.038} * \sqrt{\frac{560}{29.3 * 28.56}} = 12.754$$

2. TUNNEL FLOW RATE

INPUTS:  $T_v = 12.754$  ft./sec.  
 $TT_{ave} = 5601$ R  
 $PS = 29.3$  in. Hg.

$$T_f = 12.754 * 60 * 0.1961 * \frac{528}{560} * \frac{29.3}{29.92} * (1 - .04) = 133.0 SCFM$$

3. EMISSIONS RATE

INPUTS:  $T_f = 133.0$  SCFM  
Wt. Gain = .0200 grams  
Vol. Samp. = 100 Std. cubic feet

$$ER = \left( \frac{133 * .0200 * 60}{100} \right)_{83} * 1.82 = 2.68 \text{ grams / hour}$$

4. VOLUME CORRECTION FOR DRY GAS METERS

INPUTS:  $VOL_m = 104.479$  (Metered Feet<sup>3</sup>)  
 $PS = 29.3$  (Average baro. pressure)  
 $AMT = 801F$  (Ave. meter temp.) = 5401R  
 $Y = .9996$  (Meter cal. factor)

$$VOL_{std} = 104.479 * \frac{29.3}{29.92} * \frac{528}{540} * .9996 = 100.00 \text{ Standard Feet}^3$$

# APPENDIX I

Manufacturer: Morso  
 Model: Owl  
 Date: 36718  
 Run: 1  
 Control #: 31222  
 Test Duration: 215

	Start	End
Baromet	29.15	29.12
W	70	70
D	76	79
Hu	74	64

Average Stove Temperature: 320.7  
 Moisture cont 17.71  
 Average 1.41 5.969 14.01 223.086957 85.04

Warnock Hersey Efficiency Test Report

Overall Heating Efficiency: 59.07%  
 Combustion Efficiency: 74.40%  
 Heat Transfer Efficiency: 79.39%

Heat Output: 8153 BTU/Hr 8595 KJ/Hr  
 Heat Input: 13802 BTU/Hr 14550 KJ/Hr

Burn Duration: 3.58 Hours  
 Burn Rate: 1.54 Lb/Hr 0.700 Kg/Hr

Stack Temp: 223.1 Deg.F 106.2 Deg.C

Elapsed Time	Weight Remaining	CO	CO2	O2	Flue Gas	Room Temp	Comb %	Combust Eff %	#DIV/0! Heat Transfer	#DIV/0! Net Eff	6.66119 air Fuel	0.246 Unit MN
0	6.72	1.09	5.10	14.88	191	82	0.37	80.7%	23.4%	18.9%	11	3.05
10	5.60	0.89	5.52	14.95	284	81	1.56	57.4%	43.8%	25.1%	11	2.54
20	5.10	1.12	4.90	15.38	232	82	1.45	55.5%	54.6%	30.3%	12	2.31
30	4.70	1.18	5.97	14.49	225	82	2.03	52.2%	60.7%	31.7%	10	2.13
40	4.10	1.04	8.90	11.10	250	84	1.58	70.3%	73.0%	51.3%	8	1.86
50	3.40	0.14	13.54	7.39	313	84	2.21	75.1%	78.1%	58.7%	6	1.54
60	2.50	0.21	16.60	4.23	362	85	1.31	86.8%	83.2%	72.3%	6	1.13
70	1.50	0.44	11.61	9.40	337	87	0.69	88.2%	86.4%	76.2%	11	0.68
80	1.30	1.15	6.38	13.71	276	87	-0.08	93.1%	84.7%	78.9%	19	0.59
90	1.30	1.40	5.32	14.42	246	86	-0.36	97.5%	84.7%	82.6%	23	0.59
100	1.20	1.75	4.93	14.69	228	85	-0.25	91.2%	85.5%	78.0%	23	0.54
110	1.20	1.77	4.41	15.40	213	85	0.00	83.2%	85.7%	71.3%	24	0.54
120	1.10	1.93	4.19	15.32	203	85	-0.27	89.0%	86.3%	76.8%	26	0.50
130	1.00	1.56	5.00	14.73	195	86	-0.27	93.2%	88.4%	82.3%	25	0.45
140	0.80	1.37	5.13	14.76	190	88	-0.19	92.5%	90.3%	83.6%	29	0.27
150	0.50	1.62	4.42	15.29	185	89	-0.23	90.4%	90.1%	81.4%	33	0.23
160	0.50	1.88	3.87	15.77	180	89	-0.12	83.5%	89.9%	75.1%	34	0.23
170	0.40	2.02	3.95	15.56	176	88	-0.16	83.8%	90.5%	75.8%	34	0.18
180	0.40	1.90	4.52	15.18	176	88	0.00	81.5%	91.6%	74.7%	31	0.18
190	0.30	2.12	3.55	15.99	172	85	-0.04	77.6%	90.6%	70.3%	37	0.14
200	0.30	2.10	3.38	16.17	169	83	-0.05	77.3%	90.3%	69.8%	38	0.14
210	0.20	1.91	3.07	16.64	165	82	0.01	75.1%	90.3%	46.4%	43	0.09
215	0.00	1.84	3.02	16.76	163	83	0.07	72.7%	91.2%	66.3%	47	0.00

Manufacturer: Morso  
 Model: Owl  
 Date: 36719  
 Run: 2  
 Control #: 31222  
 Test Duration: 87

	Start	End
Baromet	29.12	29.12
W	67	67
D	78	82
Hu	57	45

Average Stove Temperature: 448.32  
 Moisture cont 17.76  
 Average 0.54 9.045 11.234

Elapsed Time	Weight Remaining	CO	CO2	O2
0	6.60	0.52	5.76	14.43
10	5.00	0.27	15.42	4.37
20	3.50	0.07	14.80	5.86
30	2.30	0.05	14.77	5.60
40	1.20	0.03	12.82	7.94
50	0.60	0.29	7.08	13.17
60	0.40	0.63	6.28	14.03
70	0.30	0.88	5.07	15.30
80	0.01	1.23	4.27	15.82
87	0.00	1.43	4.18	15.82

### Warnock Hersey Efficiency Test Report

Overall Heating Efficiency: 65.53%  
 Combustion Efficiency: 86.52%  
 Heat Transfer Efficiency: 75.74%

Heat Output: 22539 BTU/Hr 23760  
 Heat Input: 34393 BTU/Hr 36257

Burn Duration: 1.45 Hours

Burn Rate: 3.74 Lb/Hr 1.698

Stack Temp: 406.1 Deg.F 207.8

*	*	*	*	*	*	*	*	*	*	*	*	*
Flue Gas	Room Temp	Comb %	Combust Eff %	Heat Transfer	Net Eff	air	Fuel					
406.1	87.3	0.051598	0.11221488	#DIV/0!	#DIV/0!	2.65714						
362	85	0.19	90.3%	16.8%	15.2%	11						
518	90	2.23	76.3%	59.9%	45.7%	5						
516	89	2.14	77.6%	71.4%	55.4%	6						
508	88	0.23	97.2%	79.6%	77.4%	7						
478	89	-0.01	100.0%	83.8%	83.8%	12						
392	88	-0.55	113.1%	81.7%	92.4%	27						
355	88	-0.20	99.9%	82.7%	82.6%	30						
330	86	0.07	88.5%	81.5%	72.1%	34						
307	86	0.02	84.9%	81.4%	68.1%	42						
295	84	0.06	81.3%	82.2%	66.8%	41						



Warnock Hersey Efficiency Test Report

Manufacturer: Morso  
 Model: Owl  
 Date: 36719  
 Run: 3  
 Control #: 31222  
 Test Duration: 75

	Start	End
Baromet	29.12	29.12
W	67	69
D	82	88
Hu	45	38

Overall Heating Efficiency: 74.84%  
 Combustion Efficiency: 94.50%  
 Heat Transfer Efficiency: 79.19%

Heat Output: 30130 BTU/Hr 31763  
 Heat Input: 40262 BTU/Hr 42444

Burn Duration: 1.25 Hours

Burn Rate: 4.32 Lb/Hr 1.958

Stack Temp. 463.8 Deg.F 239.9

Average Stove Temperature: 498.64  
 Moisture cont 17  
 Average 0.3789 9.1178 10.822 463.77778 89 -0.02202 0.13132259 #DIV/0! #DIV/0! 2.489161

Elapsed Time	Weight Remaining	CO	CO2	O2	Flue Gas	Room Temp	Comb % K	Combust Eff %	Heat Transfer	Net Eff	air Fuel
0	6.50	0.48	5.26	13.26	428	89	-2.32	211.4%	50.9%	107.6%	21
10	4.70	0.08	15.39	4.96	597	89	2.84	71.3%	58.2%	41.5%	5
20	3.20	0.03	13.89	6.60	569	89	1.38	84.1%	71.4%	60.1%	6
30	1.90	0.04	12.85	7.35	544	89	-0.43	105.9%	79.2%	83.8%	10
40	1.10	0.10	9.73	10.60	481	89	-0.57	110.7%	80.9%	89.5%	17
50	0.09	0.34	6.88	11.91	423	89	-2.34	192.9%	80.5%	155.2%	48
60	0.70	0.64	6.47	13.76	394	89	-0.32	103.3%	80.3%	83.0%	26
70	0.10	0.80	6.14	14.14	375	89	-0.05	93.9%	82.0%	73.7%	33
75	0.00	0.90	5.45	14.82	363	89	0.02	90.1%	81.1%	73.1%	37

Warnock Hersey Efficiency Test Report

Manufacturer: Morso  
 Model: Owl  
 Date: 36720  
 Run: 4  
 Control #: 31222  
 Test Duration: 177

	Start	End
Baromete	29.15	29.12
W	68	71
D	76	85
Hu	63	50

Overall Heating Efficiency: 64.91%  
 Combustion Efficiency: 83.44%  
 Heat Transfer Efficiency: 77.79%

Heat Output: 10471 BTU/Hr 11039 KJ/Hr  
 Heat Input: 16132 BTU/Hr 17006 KJ/Hr

Burn Duration: 2.95 Hours

Burn Rate: 1.80 Lb/Hr 0.818 Kg/Hr


Stack Temp: 267.7 Deg.F 130.9 Deg.C

Average Stove Temperature: 364.2  
 Moisture cont 17.63

Elapsed Time	Weight Remaining	CO	CO2	O2	Flue Gas	Room Temp	% Comb	Combust Eff	#DIV/0! Heat Transfer	#DIV/0! Net Eff	6.32163 air Fuel	0.166 Unit MN
0	6.46	0.32	5.22	14.44	308	83	-0.85	127.9%	38.5%	49.2%	15	2.93
10	5.40	0.78	5.46	14.98	339	84	-1.37	60.9%	40.9%	24.9%	11	2.45
20	4.40	0.10	13.45	7.13	424	84	2.67	69.7%	65.1%	45.4%	6	2.00
30	3.10	0.02	14.80	5.73	435	86	1.47	84.1%	76.6%	64.5%	6	1.41
40	2.10	0.20	15.87	4.44	425	88	0.19	97.3%	83.1%	80.9%	7	0.95
50	1.50	0.09	10.62	9.76	370	88	-0.41	106.7%	84.3%	89.9%	13	0.68
60	1.30	0.56	6.83	13.37	316	86	-0.40	105.8%	83.0%	87.8%	20	0.59
70	1.10	0.82	6.17	13.91	278	87	-0.38	103.3%	84.7%	87.5%	23	0.50
80	1.00	1.08	5.55	14.41	262	86	-0.34	100.0%	84.9%	84.9%	25	0.45
90	0.09	1.26	5.40	14.52	247	86	-0.16	92.5%	88.4%	81.7%	35	0.04
100	0.80	1.09	5.43	14.38	239	86	-0.53	105.7%	86.6%	91.5%	28	0.36
110	0.70	1.31	5.18	14.72	232	86	-0.24	94.5%	87.2%	82.4%	28	0.32
120	0.60	1.50	4.72	15.20	224	85	-0.06	86.9%	87.4%	76.0%	30	0.27
130	0.40	1.20	4.70	15.36	21	85	-0.10	90.4%	102.1%	92.3%	34	0.18
140	0.30	1.37	3.91	16.16	208	85	0.05	82.0%	88.0%	72.1%	39	0.14
150	0.20	1.15	3.45	16.73	198	85	0.01	83.5%	87.7%	73.3%	47	0.09
160	0.10	1.18	3.23	16.91	190	85	-0.01	83.1%	88.1%	73.2%	51	0.05
170	0.10	1.16	3.29	16.88	186	85	0.02	82.5%	88.8%	46.5%	50	0.05
177	0.00	1.25	3.54	16.88	184	85	0.44	67.2%	91.2%	61.2%	45	0.00

# APPENDIX J





PRINTED IN U.S.A.

REORDER NO. 8866-45

Cole-Parmer Instrument Company  
Chicago, Illinois 60648



PRINTED IN U.S.A.

EP NO. 8386-45

0756

MERSO  
7-7-00  
d cm/ Hour  
0-1000 P

